

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Jesse E. Price Operator Well No.: 7519

LOCATION: Elevation: 1,073.99' Quadrangle: Big Run W.Va
District: Grant County: Wetzel
Latitude: 39.51706 Feet South of 39 Deg. 31 Min. 01.3986 Sec.
Longitude: -80.50343 Feet West of 80 Deg. 30 Min. 12.3591 Sec.

RECEIVED
JAN 20 2026
RECEIVED
JAN 20 2026

Well Type: OIL GAS

Company	<u>West Virginia Land Resources, Inc</u> <u>1 Bridge Street</u> <u>Monongah, WV 26554</u>	Coal Operator or Owner	<u>West Virginia Land Resources, Inc</u> <u>1 Bridge Street</u> <u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator or Owner	
Permit Issued Date	<u>09/05/2025</u>		

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of October, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Hydrostatic w/ Gas Block and Green Dyed	1178'	721'	3/4" Cable - 3027'	0'
Expandable	721'	Surface	2 3/8" Tubing - 3000'	0'
			7" Casing - 6' <u>787</u>	787' to Unknown depth
			16" Conductor Casing - 0'	20'

Description of monument: 77' of 7' casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 4th day of November, 2025.


And further deponents saith not.

Matthew A Yearsley

Delbert Moore

Sworn and subscribe before me this 2nd day of January, 2026.

My commission expires: August 13, 2029



Digital Notary Public

Mccoy

Date: 2026.01.15 08:34:42

-05'00'

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

01/23/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

MARY JANE PINGLEY & EDNA COLLEEN WISE

Lease or Property Owner

986 Picken Paw Rd., Smithfield, WV 26437

Address

WEST VIRGINIA LAND RESOURCES, INC.

Name of Well Operator

1 BRIDGE STREET MONONGAH, WV 26554

Complete Address

BIG RUN W.Va

Well Location

GRANT

District

WETZEL

County

7519

Well No.

JESSE E. PRICE

Farm

Stephen Mccoy

Digitally signed by Stephen Mccoy
Date: 2026.01.15 08:34:59 -05'00'

STATE INSPECTOR SUPERVISING PLUGGING

Stephen McCoy


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of October, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Pulled 3,027' of 3/4" cable from surface. Pulled 3,000' of 2 3/8" tubing from surface. Cleaned 6 1/4" hole from surface to 1,178'. Removed 787' of 7" casing from surface to 787'. Cleaned a 12 1/4" hole from surface to 245'. Reduced to 9 7/8" bit and cleaned 9 7/8" hole from 245' to 787'. Made a diligent effort to remove remaining 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount of 7" casing from 787' to an unknown depth.	3/4" Cable	3027'	0'	
Cut 7" casing at depths 1178', 1128', 1078', 978', 938', 933', 928', 925.5', 923', 921', 916', 911', 871', 821', 787'. Perforated 7" casing with 6 shots each at depths 928', 921', 916', 911'.	2 3/8" Tubing	3000'	0'	
Cemented hole from 1,178' to surface as follows: Cemented hole from 1,178' to 721' using 110 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 721' to Surface using 510 sacks of Expandable Cement. Cement did circulate at the surface. A total of 620 sacks of Cement were used to fill the hole from 1,178 to the surface.	7" Casing	787'	Unknown	
	16" Conductor Casing	0'	20'	
Coal Seams		Description of Monument		
Pittsburgh	921' - 928'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 4th day of November, 2025



Matthew A. Yearsley

Matthew A. Yearsley

Delbert Moore

Delbert Moore

Sworn to and subscribed before me this

20 day of January 2026


Kerrri McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-01431

Well No. 7519

Latitude: 39° 31' 01.40"N

Longitude: 80° 30' 12.36"W

01/23/2026