

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Stevens Operator Well No.: 7514

LOCATION: Elevation: 912' Quadrangle: Big Run, W.VA

District: Grant County: Wetzel

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 53.41 Sec.

Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 25.57 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Creston Oil Corporation Coal Operator West Virginia Land Resources, Inc.  
500 Old Goff Mountain Rd. or Owner 1 Bridge Street  
Cross Lanes, WV 25313 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 03/27/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29th day of March, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	960'	546'	5 1/2" Casing - 990'	Unknown
Expandable Cement	546'	Surface	7" Casing - 852'	Unknown - Cuts at 902' and 952'
			16" Conductor - 0'	19'


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 17th day of April, 2023.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 24 day of April, 2023

My commission expires: June 8, 2027  
Christopher Andrew Willis  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**DOUGLAS JOE SMITH**  
Lease or Property Owner  
403 PICKENPAW RD. SMITHFIELD, WV 26437  
Address

**CRESTON OIL CORPORATION**  
Name of Well Operator  
500 OLD GOFF MOUNTAIN RD. CROSS LANES, WV 25313  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7514  
Well No.  
J.L. STEVENS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**MATTHEW A. YEARSLEY** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Creston Oil Corporation well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29<sup>th</sup> day of March, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned 4 3/4" hole through existing 5 1/2" casing from the surface to 990'. Removed 990' of 5 1/2" casing from the surface to 990'. Left an unknown amount of 5 1/2" casing in the hole from 990' to an unknown depth. Removed 852' of 7" casing from the surface to 852'. Attempt to remove additional 7" casing by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 7" casing in the hole from 852' to an unknown depth. Cut the remaining 7" casing at 952' and 902'. Cleaned a 12 1/4" hole from the surface to 385'. Cleaned a 9 7/8" hole from 385' to the top of the remaining 7" casing at 852'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (746' - 752'). Cleaned a 6 1/4" hole from 852' to 960'. Left 19' of 16" conductor pipe in the hole from the surface to 19'.	5 1/2" Casing  7" Casing  16" Conductor	990'  852'  0'	Unknown  Unknown  19'
<b>Cemented the hole from 960' to the surface as follows:</b> From 960' to 546' with 170 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 546'. Cemented the hole from 546' to the surface with 345 sacks of Expandable Cement. Cement did circulate at the surface. A total of 515 sacks of cement were used to fill the hole from 960' to the surface.				
Coal Seams		Description of Monument		
Pittsburgh	746' - 752'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 17<sup>th</sup> day of April, 2023

And further deponents saith not.


*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 24 day of April, 2023



My commission expires:

June 8, 2027

*Christopher Willis*  
Notary Public

Permit No. 47-103-01434

Well No. 7514

Latitude: 39° 30' 53.41"N

Longitude: -80° 30' 25.57"W