

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Price Operator Well No.: WJ Price #1
LOCATION: Elevation: 1131.06' Quadrangle: Glover Gap 7.5'
District: Grant County: Wetzel
Latitude: 39.51583 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.49112 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company Diversified Energy Coal Operator West Virginia Land Resources, Inc.
414 Summers Street or Owner 46226 National Road West
Charleston, WV 26301 St. Clairsville, OH
Agent Chris Veazey Coal Operator _____
Permit Issued Date 10/29/25 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Ed Burrows and Tim Hicks being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12th day of December, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
108 sks Cement Expanding	3104'	2050'	3000' rods	0
134 sks Cement Expanding	2042'	1240'	3081' of 2 3/8"	0
55 sks Cement Expanding	1375'	1163.5'	2032' of 5 1/2"	1048'
90 sks Cement Thixotropic	1163'	763.5'	1165' of 7"	Unknown
250 sks Cement Expanding	730'	0'	8" 0'	Unknown
			20" 0'	14'

Description of monument: Steel Casing W/API # welded on at least 36" above ground and that the work of plugging and filling said well was completed on the 12th day of February, 2026.


And further deponents saith not.

Ed Burrows
Tim Hicks

Sworn and subscribe before me this 16 day of March, 2026

My commission expires: 7/26/29

Rebecca Wanstreet
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy Digitally signed by Stephen Mccoy Date: 2026.03.11 07:18:53 -0400 Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

American Consolidated Natural Resources, Inc.
Coal Operator or Owner
46226 National Rd., St. Clairsville, OH 43950
Address
American Consolidated Natural Resources, Inc.
Coal Operator or Owner
226 National Rd., St. Clairsville, OH 43950
Address
Joseph Rex Smith
Lease or Property Owner
4464 Mannington Rd., Smithfield, WV 26437
Address

Diversified Energy
Name of Well Operator
414 Summers Street Charleston, WV 25301
Complete Address
Price Fork Rd., Mannington, WV
Well Location
Grant
District
Wetzel
County
1 (ACNR #7672)
Well No.
Price
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Stephen Mccoy

Digitally signed by Stephen Mccoy
Date: 2020.03.11 07:18:38 -0400

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Wetzel

ss: Ed Burrows

and Tim Hicks

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Next LVL Energy a well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12/12/2025 that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Pulled 3000' of rods/pump and 3081' of 2 3/8" tubing. Placed cut in 5 1/2" casing at 2032'. Pulled 2032' of 5 1/2" casing leaving 1048' of 5 1/2" casing in the hole. Made a diligent effort to remove 7" casing from surface. Perforated 7" casing at 1940', 1840', 1740', 1640', 1540', 1440', 1340', and 1240' using 6 shots at each location. Cut 7" casing at 1165'. Pulled 1165' of 7" casing leaving an unknown footage of 7" in the hole. Made a diligent effort to remove 8" casing but all attempts were unsuccessful. Perforated the 8" casing at 1163.5', 1113.5', 1063.5', and 1013.5' using 6 shots at each location. Cut 8" casing at 977', 968', 963.5', 961.5', 959.5', 957.5', 956', 951', 946', 906', and 856'. Perforated 8" casing at 973.5' using 6 shots. Pittsburgh Coal Seam (956'-963.5'). Cemented hole from 3104' to surface as follows: Cemented hole from 3104' to 1164' using 236 sacks of Expandable Cement. Cemented from 1164' to 730' using 132 sacks of Thixotropic Cement with Green Dye and Gas Block Additive. Cemented hole from 730' to surface using 250 sacks of Expandable Cement. A total of 618 sacks of cement were used to fill the hole from 3104' to surface. Cement did circulate at surface.				
CONTINUED ON PAGE 2				
Coal Seams		Description of Monument		
Pittsburgh	956'-963.5'	Steel casing w/API # welded on at least 36" above ground		

... and that the work of plugging and filling said well was completed on the 2/12/2026

And further deponents saith not.

Ed Burrows

Tim Hicks

Sworn to and subscribed before me this 12 day of March 2020

Rebecca Wanstreet
Notary Public

My commission expires: 7/26/29

Permit No. 4710301524
Well No. 1
Latitude: 39° 30' 56.988
Longitude: -80° 29' 28.032

