

WR-38  
Rev. 5/08

API # 47-103-01829-P

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Consolidation Coal Company Operator Well No.: 6316

LOCATION: Elevation: 1436.43' Quadrangle: Wallace WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 28 Min. 58.4 Sec.  
Longitude: \_\_\_\_\_ Feet West of 80 Deg. 29 Min. 20.0 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Consolidation Coal Co Coal Operator 1 Bridge St  
or Owner Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 9/14/16

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

William H. Barker, Jr. and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of October, 2018, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable	1308'	Surface		
8 5/8"	1308'	862'	0'	447'
10 3/4"	308'	190'	0'	118'
16" Conductor	20'	Surface	0	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 19th day of October, 2018.

And further deponents saith not. William Barker  
Matthew A. Yearsley

Sworn and subscribe before me this 5th day of November, 2018

My commission expires: 06/17/2021  
Notary Public



RECEIVED  
Office of Oil and Gas

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector NOV 13 2018

Supplemental

11/16/2018

FORM WR-38  
(Affidavit of Plugging)

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

TALL TIMBER, INC.  
Lease or Property Owner  
RT 1 BOX 100, SMITHFIELD, WV 26437  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

WALLAGE WV 7.5'  
Well Location

GRANT  
District  
WETZEL  
County  
6316  
Well No.  
J.L. PRICE  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek W. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

WILLIAM H. BARKER, JR. and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2<sup>nd</sup> day of October, 2018 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from surface to 190', tagged 10 3/4" casing. Reduced hole to 9 7/8" and cleaned hole from 190' to 862', tagged 8 5/8" casing. Reduced hole to 7 7/8" and cleaned from 862' to 1309', tagged plug at 1309'. Attempted to remove 10 3/4" and 8 5/8" casing by pulling 150% at string weight. All attempts were unsuccessful. Left 118' at 10 3/4" casing in hole and perforated with 4 shots per foot at 218' and 278'. Left 447' of 8 5/8" casing in hole and perforated with shots per foot at 865', 882', 1081', 1180', 1280'.		8 5/8"	0'	447'
		10 3/4"	0'	118'
		16" Conductor	0'	20'
<u>Cemented hole from 1309' back to the surface as follows:</u> From 1309' to surface with 575 sacks of expandable cement. Cement did circulate at surface. Left 20' of 16" conductor pipe in well at surface.				
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	<u>(1036' - 1042')</u> 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 19<sup>th</sup> day of October, 2018

And further deponents saith not.


William H. Barker, Jr.  
Matthew A. Yearsley

Sworn to and subscribed before me this 5<sup>th</sup> day of November, 2018

Richard O'Dell  
Notary Public

My commission expires:

06/17/2021



Permit No. 47-103-01829-P  
Well No. 6316  
Latitude: 39° 28' 58.4"N  
Longitude: 80° 28' 20.0"W

RECEIVED  
Office of Oil and Gas

NOV 13 2018

WV Department of  
Environmental Protection