

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Mary R. Kocher Operator Well No.: 6324

LOCATION: Elevation: 1276.55 Quadrangle: Wallace, WV 7.5'
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 15.23 Sec.
Longitude: _____ Feet West of -80 Deg. 29 Min. 52.32 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 03/15/2021 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of March, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1400'	Surface		
8 5/8" Casing	789'	Unknown	0'	Unknown
16" Conductor	Surface	11'	0'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 30th day of March, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 19th day of Apr, 2021

My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

06/04/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
MARY R. KOCHER
Lease or Property Owner
185 MCDUGAL HOLLOW RD. SMITHFIELD, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV 7.5'
Well Location
GRANT
District
WETZEL
County
6324
Well No.
MARY R. KOCHER
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc., well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of March, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 284'. Reduced the hole to 9 7/8" at 284'. Cleaned the hole with a 9 7/8" bit from 284' to the top of existing 8 5/8" casing at 789'. Reduced the hole to 6 1/4" at 789'. Cleaned out 8 5/8" casing with a 6 1/4" bit from 789' to 1400'. Attempted to remove 8 5/8" casing by pulling 150% of the string weight. All attempts to remove the 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 798' to unknown depth. The remaining 8 5/8" casing was cut at 1370', 1320', 1270', 1220', 1180', 1175', 1170', 1168', 1166', 1163', 1158', 1153', 1113', and 1063'. Left 8 5/8" casing through the Pittsburgh Coal Seam (1163.3'- 1169.7'). Left 11' of 16" conductor pipe in the hole from the surface to 11'		16" Conductor 8 5/8" Casing	0' 0'	11' Unknown
Cemented the hole from 1400' to surface as follows: From 1400' to surface with 595 sacks of Expandable Cement with a gas blocker additive. Cement did circulate at surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1163.3' - 1169.7'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 30th day of March, 2021


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 19th day of Apr, 2021

[Signature] **06/04/2021**
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01846
Well No. 6324
Latitude: 39° 29' 15.23"N
Longitude: -80° 28' 52.32"W