

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: COASTAL FOREST RESOURCES/D.H.COX PNG-29 Operator Well No.: 510845S

LOCATION: Elevation: 881' Quadrangle: PINE GROVE
District: GRANT County: WETZEL
Latitude: 11100 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: 0620 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company EQT PRODUCTION CO Coal Operator SEE ATTACHMENT RECEIVED
625 LIBERTY AVE, SUITE 1700 or Owner _____ Office # _____
PITTSBURGH PA 15222 _____
Agent CECIL RAY Coal Operator _____ OCT 14
Permit Issued Date 04/26/2022 or Owner _____
_____ WV Department of Environmental Protection

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of WETZEL ss:

JUSTIN FARRAR and PATRICK CARNAHAN being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5TH day of MAY, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
CLASS A CMT (50SKS)	6770	6300	5 1/2" CASING 3790'	3150 OF 5 1/2" CASING
GEL	6300	5330		8 5/8" CASING 2298'
CLASS A CMT (40 SKS)	5330	5050		11 3/4" CASING 1192'
GEL	5050	3890		16" CASING 44'
CLASS A CMT(223 SKS)	3890	2114		
GEL	2114	1850		
CLASS A 2% CALCIUM GAS BLOCK (2)	1850	0		

Description of monument: 2X2 PLATE 5' ABOVE GROUND ON 6" CASING and that the work of plugging and filling said well was completed on the 29TH day of JUNE, 2022.

And further deponents saith not. Justin Farrar
Patrick Carnahan



Sworn and subscribe before me this 19th day of August, 2022

My commission expires: Aug 12, 2027 Dana A Bacorn
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____