

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Martin Operator Well No.: 4H

LOCATION: Elevation: 924' Quadrangle: Porter Falls
District: Greene County: Wetzel
Latitude: 39.61270597 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.76600782 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company 400 Woodcliff Dr Coal Operator See attached document
Canonsburg, PA, 15317 or Owner _____
Agent Joseph C. Mallow Coal Operator _____
Permit Issued Date 4/13/2023 or Owner _____

AFFIDAVIT

RECEIVED
Office Of Oil and Gas

APR 04 2024

STATE OF WEST VIRGINIA,
County of Wetzel ss:

James Fields and Charles Swales being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 30 day of May, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
CIBP	6545	6545	5-1/2" - cut 2' below slips,	20" 85'
6% GEL	6545	5000	washed over & pulled 14'	13 3/8" 888'
Class A CMT	5000	4800	milled additional 581'	9 5/8" 2232
6% GEL	4800	2332	(total 5-1/2" removed is 595')	5 1/2" 12,615
Class A CMT	2332	346	Multi String Cuts @ 1380,1000,180,135	
CIBP	346	346		
Inflatable Packer	272	272 - Class A CMT to Surface		


Description of monument: 2x2 plate attached to 7" casing 48" above ground and that the work of plugging and filling said well was completed on the 9th day of January, 2024.

And further deponents saith not. James Fields
Charles Swales

Sworn and subscribe before me this 19 day of FEB, 2024

My commission expires: 8/30/2024

Stephen Mccoy
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy
Digitally signed by Stephen Mccoy
Date: 2024.03.14 09:28:21 -04'00'

Title: _____

04/12/2024