

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Martin Operator Well No.: 8H

LOCATION: Elevation: 924' Quadrangle: Porter Falls
District: Greene County: Wetzel
Latitude: 39.61270597 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.76600782 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company EQT Production Coal Operator See attached document
400 Woodcliff Dr or Owner _____
Canonsburg, PA, 15317 _____
Agent Joseph C. Mallow Coal Operator _____
Permit Issued Date 4/13/2023 or Owner _____

AFFIDAVIT

RECEIVED
Office Of Oil and Gas

APR 04 2024

STATE OF WEST VIRGINIA,
County of Wetzel ss:

James Fields and Charles Swales being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12 day of October, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
CIBP	8790	8790		20" 85'
Class A CMT	8790	8200		13 3/8" 904'
6% GEL	8200	5000		9 5/8" 2231
Class A CMT	5000	4460		5 1/2" 12072
6% GEL	4460	2174	#Multi String Cuts @ 980,1514	
Class A CMT	2174	775		
Inflatable Packer	775	775 - Class A CMT to Surface		

Description of monument: 2x2 plate attached to 7" casing 48" above ground
said well was completed on the 9th day of January, 2024.

and that the work of plugging and filling


And further deponents saith not.

James Fields
Charles Swales

Sworn and subscribe before me this 19 day of FEB, 2024

My commission expires: 8/30/2027

Notary Public
Digitally signed by Stephen Mccoy
Mccoy
Date: 2024.03.14 09:29:00 -04'00'



Affidavit reviewed by the Office of Oil and Gas: _____

Title: _____

04/12/2024