

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Genine Robinson Operator Well No.: 6723

LOCATION: Elevation: 1260.06' Quadrangle: FOLSOM WV 7.5'

District: Grant County: Wetzel

Latitude: _____ Feet South of 39 Deg. 28 Min. 45.066 Sec.

Longitude: _____ Feet West of 80 Deg. 30 Min. 10.10160 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co. Coal Operator 1 Bridge Street Monongah, WV 26554
or Owner _____

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 04/19/2019

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Mark A. Wilson and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of June, 2019, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic with Green Dye	1423'	963'		
Expandable Cement	963'	Surface		
16" Conductor	Surface	20'	0	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 2nd day of July, 2019.

And further deponents saith not. Mark A. Wilson

Matthew A. Yearsley

Sworn and subscribe before me this 15th day of July, 2019



My commission expires: 9-15-22

Carol A. Mayle
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught

Title: Oil & Gas Inspector

09/13/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
LARRY HOOD
Lease or Property Owner
1007 SAMS RUN RD. FOLSOM, WV 26348
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM, WV 7.5'
Well Location
GRANT
District
WETZEL
County
6723
Well No.
GENINE ROBINSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MARK A. WILSON and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13TH day of June, 2019 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from surface to 310'. Reduced hole to 9 7/8" at 310'. Cleaned a 9 7/8" hole from 310' to 1337'. Reduced hole to 7 7/8" hole at 1337'. Cleaned a 7 7/8" hole from 1337' to 1423'. Tagged plug at 1423'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 1163' to 1170'. <u>Cemented hole from 1423' back to surface as follows:</u> Cement from 1423' to 963' with 230 sacks of Thixotropic Cement. From 963' to surface with 375 sacks of Expandable Cement. Cement did circulate at surface. Left 20' of 16" conductor from surface to 20'.	16" Conductor	0	20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1163' - 1170'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 2nd day of July, 2019


And further deponents saith not.

Mark A. Wilson
Mark A. Wilson

Matthew A. Yearsley
Matthew A. Yearsley

Sworn to and subscribed before me this 15th day of July 2019

09/13/2024



My commission expires:

Carol A. Mayle
Notary Public

Permit No. 47-103-03288
Well No. 6723
Latitude: 39° 28' 45.066"N
Longitude: 80° 30' 10.10160"W