

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7241

LOCATION: Elevation: 1094.82 Quadrangle: Big Run, WV 7.5'
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 10.46 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 52.13 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 05/14/2019 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of August, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1118'	650'		
Expandable Cement	650'	Surface		
8 5/8" Casing	116'	Unknown	0' (multiple cuts - parting)	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 21st day of August, 2020.

And further deponents saith not. Matthew A. Yearsley

Kevin Wright

Sworn and subscribe before me this 31st day of Jan, 2022

My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/08/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

CONSOLIDATION COAL COMPANY
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7241
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11th day of August, 2020 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Removed all 2 3/8" tubing from the surface to 124'. Cleaned a 12 1/4" hole from the surface to 116'. Tagged top of existing 8 5/8" casing at 116'. Reduced hole to 7 7/8" and cleaned out the 8 5/8" casing from 116' to 1118'. Attempted to remove 8 5/8" casing from 116' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing on the hole from 116' to an unknown depth. Cut remaining 8 5/8" casing at 1091', 1041', 989', 941', 899', 895', 890.9', 888.5', 886', 884', 879.5', 874.5', 834' and 784'. 8 5/8" casing had pre-existing parting from 739' to 741'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (884.5' - 890.9'). Left 20' of 16" conductor in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 20'
	<u>Cemented the hole from 1118' back to the surface as follows:</u> From 1118' to 650' with 135 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 650'. Cemented to hole from 650' to the surface with 265 sacks of Expandable Cement. Cement did circulate at the surface. A total of 400 sacks of cement were used to fill the hole from 1118' to the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>884.5' - 890.9'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 21st day of August, 2020

And further deponents saith not.



Sworn to and subscribed before me this 31st day of Jan, 2022

Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Thomas J. Sullivan 04/08/2022
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03300
Well No. 7241
Latitude: 39° 30' 10.46"N
Longitude: -80° 31' 52.13"W