

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Genine Robinson Operator Well No.: 7135

LOCATION: Elevation: 1354.28 Quadrangle: Folsom, WV  
District: Grant County: Wetzel  
Latitude: 39.486006 Feet South of 39 Deg. 29 Min. 9.6216 Sec.  
Longitude: -80.519637 Feet West of -80 Deg. 31 Min. 10.6932 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 6/11/2019

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Kevin S. Wright and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 11th day of June, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic/ Green Dye	1414'	963'		
Expandable Cement	963'	315'		
Expandable Cement	315'	Surface		
8 5/8" Casing	1434'	Unknown	849'	Unknown
16" Conductor	20'	Surface	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 1st day of July, 2020.

And further deponents saith not. Kevin S. Wright  
Matthew A. Yearsley



Sworn and subscribe before me this 13<sup>th</sup> day of July, 2020

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

# Plugging Report for MSHA

Well Number: 7135

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03310

Date Clean Out Started: 6/11/2020

Date Well Bore Plugged: 7/1/2020

Pittsburgh Coal Seam: 1072 ft. To 1079 ft.

Plugs:	From	To	Type of Cement
	<u>1414'</u>	<u>963'</u>	<u>Thixotropic Cement w/ Green Dye</u>
	<u>963'</u>	<u>315'</u>	<u>Expandable Cement</u>
	<u>315'</u>	<u>Surface</u>	<u>Expandable Cement</u>

**Casing Remaining in Well Bore**

**Thix Top: 963'**

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing	1434'	Unknown	Unknown	849'
10 3/4" casing				
16" Conductor				

Expandable Cement

Thixotropic Cement w/ Green Dye

Thixotropic Cement w/ Green Dye

6% Gel Spacer

Pittsburgh Coal  
1172.2'-  
1178.9'

**Cement:**

Expandable	<u>520</u>	sacks
Thixotropic	<u>260</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

**Comments:**

Caving: Extreme Moderate **Normal**

Lost Circulation: Extreme **Moderate** Normal

Difficulty in Removing Casing: Extreme Moderate **Normal**

Debris in Well Bore: Wood **Steel** Other: \_\_\_\_\_

**Thix Bottom: 1414'**

Top of 8 5/8" Casing at 1434'

Surface Elevation (Surveyed)	<u>1329.71'</u>
Bottom of Coal Structure (Map)	<u>151'</u>
Difference	<u>1078.71</u>

**Total Depth: 1682'**

Bottom of 8 5/8" casing unknown

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MICHAEL W. & ANGIE L. COEN  
Lease or Property Owner  
732 SAMS RUN RD., FOLSOM WV 26348  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, WV 7.5'  
Well Location  
GRANT  
District  
WETZEL  
County  
7135  
Well No.  
GENINE ROBINSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

KEVIN S. WRIGHT and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11<sup>TH</sup> day of June, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned hole with a 14 3/4" bit from the surface to 176'. Reduced hole to 12 1/4" at 176'. Cleaned hole with a 12 1/4" bit from 176' to 293'. Reduced hole to 9 7/8" at 293'. Cleaned hole with a 9 7/8" bit from 293' to the top of the 8 5/8" casing at 585'. Reduced hole to 7 7/8" at 585'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 585' to 1682'. Tagged plugged at 1682'. Removed 849' of 8 5/8" casing from 585' to 1434'. Left an unknown amount of 8 5/8" casing in the hole from 1434' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 1172.2' to 1178.9'.	8 5/8" Casing 16" Conductor	849' 20'	Unknown 20'
<b>Cemented hole from 1414' to surface as follows:</b>	From 1414' to 963' with 260 sacks of Thixotropic Cement with Green Dye. Cemented from 963' to 315" with 245 sacks of Expandable Cement. From 315' to surface with 275 sacks of Expandable Cement. Cement did circulate at surface. A total of 780 sacks of cement were used to cement the hole from 1414' to surface. Left 20' of 16" conductor in the hole from 20' to surface.			
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1172.2' – 1178.9'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1<sup>st</sup> day of July, 2020

And further deponents saith not.


*Kevin S. Wright*  
\_\_\_\_\_  
Kevin S. Wright

*Matthew A. Yearsley*  
\_\_\_\_\_  
Matthew A. Yearsley

Sworn to and subscribed before me this 13<sup>th</sup> day of July, 2020

*[Signature]*  
\_\_\_\_\_  
Notary Public

My commission expires: 09/15/22



Permit No. 47-103-03310  
Well No. 7135  
Latitude: 39° 29' 9.6216"N  
Longitude: -80° 31' 10.6932"W