

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Chas Snodgrass Operator Well No.: 6390

LOCATION: Elevation: 1201.93' Quadrangle: Glover Gap, WV 7.5'
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 10.83 Sec.
Longitude: _____ Feet West of -80 Deg. 29 Min. 21.94 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Company Coal Operator Consolidation Coal Company
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 09/24/2019

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1,355'	902'		
Expandable Cement	902'	Surface		
8 5/8" Casing	1018'	Unknown	0'	Unknown
10 3/4" Casing	Surface	74'	0'	0'
16" Conductor	Surface	20'	0'	Unknown

Description of monument: 77' of 7" casing with company name, well #, API# and date cemented. and that the work of plugging and filling said well was completed on the 11th day of August, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 13th day of Sept, 2021

My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 01/19/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WILLIAM J ROHRIG ET AL
Lease or Property Owner
RT 1 BOX 79A SMITHFIELD, WV 26437
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

GLOVER GAP, WV 7.5'
Well Location

GRANT
District

WETZEL
County

6390
Well No.

CHAS SNODGRASS
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bryan Harris

Inspector

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Reamed the hole with a 15 3/8" bit from the surface to 102'. Installed 10 3/4" casing from the surface to 74'. Cemented the 10 3/4" casing in the hole from 74' to 47' with 230 sacks of Thixotropic Cement. Cleaned a 9 7/8" hole from 102' to 1018'. Tagged top of existing 8 5/8" casing at 1018'. Reduced the hole to 7 7/8" at 1018'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 1018' to 1355'. Attempted to remove the existing 8 5/8" casing from 1018' by pulling 150% of string weight. All attempts to remove existing 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1018' to an unknown depth. Cut remaining 8 5/8" casing at 1309', 1159', 1119', 1114', 1109', 1107', 1104.5', 1102', 1097', and 1092'. The 8 5/8" casing was previously ripped or parted at the following depths: 1247' to 1240', 1228' to 1224', 1220' to 1199', 1126' to 1120', 1115' to 1111', 1107' to 1102', 1080' to 1055' and from 1044' to 1032'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1102' - 1109'). Left 20' of 16" conductor in the hole from the surface to 20'. <u>Cemented the hole from 1355' to surface as follows:</u> From 1355' to 902' with 160 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic plug at 915'. Cemented the hole from 915' to the surface with 415 sacks of Expandable Cement. Cement did circulate at surface.	8 5/8" Casing	0'	Unknown	
	10 3/4" Casing	0'	74'	
	16" Conductor	0'	20'	
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	1102' - 1109'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 11th day of August, 2021

And further deponents saith not.


Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 13th day of Sept, 2021



My commission expires: 09/15/22

[Signature] 01/19/2024
Notary Public

Permit No. 47-103-03324
Well No. 6390
Latitude: 39° 30' 10.83"N
Longitude: -80° 29' 21.94"W