

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Sol. M. Shriver Operator Well No.: 4598

LOCATION: Elevation: 1228.00 Quadrangle: Hundred WV, PA 7.5'
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 38 Min. 49.65 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 25.98 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 09/27/2019 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of March, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1315'	893'		
Thixotropic Cement w/ Green Dye	893'	857'		
Expandable Cement	857'	Surface		
8 5/8" Casing	1265'	Unknown	413'	Unknown
16" Conductor Pipe	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 1st day of April, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 19th day of Apr, 2021
My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

06/04/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
RANDALL L. & JANET H. MOORE
Lease or Property Owner
326 POGUE RUN, BURTON, WV 26562
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED WV, PA 7.5'
Well Location
GRANT
District
WETZEL
County
4598
Well No.
SOL. M. SHRIVER
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 4/20/21
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2nd day of March, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
		8 5/8' Casing	413'	Unknown
		16" Conductor	0'	20'
<p>Cleaned the hole with a 12 1/4" bit from the surface to 167'. Reduced hole to 9 7/8' at 167'. Cleaned the hole with a 9 7/8" bit from 167' to the top of the existing 8 5/8" casing at 852'. Reduced hole to 7 7/8" at 852'. Cleaned the hole with a 7 7/8" bit from 852' to 1315'. Removed 413' of 8 5/8" casing from 852' to 1265'. Left an unknown amount of 8 5/8" casing in the hole from 1265' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1057' - 1064'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.</p> <p>Cemented the hole from 1315' to surface as follows: From 1315' to 893' with 245 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 893'. From 893' to 857' with 25 sacks of Thixotropic Cement. From 857' to surface with 450 sacks of Expandable Cement. Cement did circulate at surface. A total of 720 sacks of cement were used to fill the hole from 1315' to surface.</p>				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1057' - 1064'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1st day of April, 2021


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 19th day of Apr, 2021

[Signature] 06/04/2021
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03329
Well No. 4598
Latitude: 39° 38' 49.65"N
Longitude: -80° 24' 25.98"W