

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7240

LOCATION: Elevation: 1129.94' Quadrangle: Big Run, WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 59.78 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 51.11 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 02/14/2020

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of November, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thotropic w/ Green Dye and Gas Block	1180'	853'		
Expandable Cement	853'	Surface		
7" Casing	1025'	Unknown	580'	Unknown
16" Conductor	Surface	20'	0'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 28th day of May, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 21<sup>st</sup> day of June, 2021  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 6/22/21

08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

COASTAL FOREST RESOURCES COMPANY  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN, WV 7.5'  
Well Location

GRANT  
District

WETZEL  
County

7240  
Well No.

B.W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING

*Bryan Harris*

6/22/21

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16<sup>th</sup> day of November, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 14 3/4" hole from the surface to the top of the existing 7" casing at 445'. Had extreme difficulty getting inside 7" casing at 445'. Removed 580' of 7" casing from 445' to 1025'. Cleaned the hole with a 14 3/4" bit from 445' to 554'. Reduced the hole to 12 1/4" at 554'. Cleaned the hole with a 12 1/4" bit from 554' to the top of the remaining 7" casing at 1025'. Reduced the hole to 4 3/4" at 1025'. Cleaned a 4 3/4" hole from 1025' to 1180'. Left an unknown amount of 7" casing in the hole from 1025' to an unknown depth. The remaining 7" casing was previously ripped from 1170' to 1168', 1132' to 1129' and from 1101' to 1025'. Cleaned a 12 1/4" hole through the Pittsburgh Coal Seam (953' - 958'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.		7" Casing  16" Conductor	580'  0'	Unknown  20'
<b>Cemented the hole from 1180' to surface as follows:</b> From 1180' to 753' with 215 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 853'. From 853' to surface with 635 sacks of Expandable Cement. Cement did circulate at surface. A total of 850 sacks of cement were used to fill the hole from 1180' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>953' - 958'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 28<sup>th</sup> day of May, 2021

And further deponents saith not.



*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 21<sup>st</sup> day of June, 2021

*[Signature]*

08/13/2021

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03339  
Well No. 7240  
Latitude: 39° 29' 59.78"N  
Longitude: -80° 31' 51.11"W