

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Genine Robinson Operator Well No.: 6731

LOCATION: Elevation: 1477.13 Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 08.58 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 00.00 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 03/29/2021 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 23rd day of April, 2021, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1592'	1177'		
Expandable Cement	1177'	Surface		
8 5/8" Casing	887'	Unknown	0'	Unknown
16" Conductor	Surface	14'	0'	14'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 11th day of May, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 24th day of May, 2021



My commission expires: 09/15/22  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES CO.  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

WEST VIRGINIA LAND RESOURCES CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
6731  
Well No.  
GENINE ROBINSON  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 5/25/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23<sup>rd</sup> day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 313'. Reduced the hole to 9 7/8" at 313'. Cleaned the hole with a 9 7/8" bit from 313' to the top of the existing 8 5/8" casing at 887'. Reduced the hole to 7 7/8" at 887'. Cleaned the hole with a 7 7/8" bit from 887' to 1592. Attempted to remove existing 8 5/8" casing by pulling 150% of the string weight but all attempts to remove 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 887' to an unknown depth. Cut remaining 8 5/8" casing at the following depths; 1584', 1534', 1484', 1434', 1394', 1389', 1384', 1382', 1380', 1378', 1373', 1368', 1328' and 1278'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1378' - 1384'). Left 14' of 16" conductor pipe in the hole from the surface to 14'.  <u>Cemented the hole from 1592' to surface as follows:</u> From 1592' to 1177' with 125 sacks of Thixotropic Cement with Green Dye and gas blocker additive. Tagged top of Thixotropic plug at 1177'. From 1177' to surface with 495 sacks of Expandable Cement. Cement did circulate at surface. A total of 620 sacks of cement were used to fill the hole from 1592' to surface.	8 5/8" Casing	0'	Unknown	
		16" Conductor	0'	14'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1378' to 1384'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 11<sup>th</sup> day of May, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 24<sup>th</sup> day of May, 2021

08/13/2021

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03379  
Well No. 6731  
Latitude: 39° 29' 08.58"N  
Longitude: -80° 30' 00.00"W