

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7204

LOCATION: Elevation: 1385.49' Quadrangle: Folsom, W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 48.54 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 02.96 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 04/21/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of August, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Green Dye and Ga	1498'	930'		
Expandable Cement	930'	Surface		
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 7th day of September, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribe before me this 23rd day of Sept, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
PO BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM WV
Well Location
GRANT
District
WETZEL
County
7204
Well No.
B, W. PETERSON
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4th day of August, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 218'. Reduced the hole to 9 7/8" at 218'. Cleaned the hole with 9 7/8" bit from 218' to 1498'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam from (1209.3' -1216.2'). Left 20' of 16" conductor in the hole from the surface to 20'. Cemented the hole from 1498' to surface as follows: From 1498' to 930' with 295 sacks of Thixotropic Cement with a gas blocker additive. From 930' to surface with 600 sacks of Expandable Cement. Cement did circulate at surface. A total of 895 sacks of cement were used to fill the hole from 1498' to the surface.		16" Conductor	0'	20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1209.3' -1216.2'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of September, 2021

And further deponents saith not.



Sworn to and subscribed before me this 23rd day of Sept, 2021

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature] 09/20/2024
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03394
Well No. 7204
Latitude: 39° 29' 48.54"N
Longitude: -80° 32' 02.96"W