

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7770

LOCATION: Elevation: 1453' Quadrangle: Folsom W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 53 Sec.
Longitude: _____ Feet West of -80 Deg. 30 Min. 54 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah WV 26554 Monongah WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 4/21/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thiotropic W/ Green Dye and Gas Block	1,473'	957'		
Expandable Cement	957'	Surface		
8 5/8" Casing	1,155'	Unknown	202'	Unknown (Multiple Cuts and Rips)
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 29th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 29th day of Aug, 2021

My commission expires: 09/15/22
Thomas J. Sullivan
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

01/19/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES
Lease or Property Owner
PO BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM W.VA
Well Location
GRANT
District
WETZEL
County
7770
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 8/9/21
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8TH day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from the surface to 419'. Reduced the hole to 9 7/8" at 419'. Cleaned a 9 7/8" hole from 419' to 946'. Tagged top of existing 8 5/8" casing at 946'. Reduced the hole to 7 7/8" at 946'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 946' to 1473'. Removed 202' of 8 5/8" casing from 946' to 1148'. Attempted to remove remaining 8 5/8" casing by pulling 150% of the string weight. All additional attempts were unsuccessful. Left an unknown amount of casing in the hole from 1155' to unknown depth. Cut remaining 8 5/8" casing at 1473', 1423', 1373', 1323', 1283', 1278', 1273', 1270.5', 1268.5', 1266', 1261', 1256', 1216', and 1166'. The 8 5/8" casing was ripped from 1330' to 1321' and from 1155' to 1160'. Left 20' of 16" conductor in the hole from the surface to 20'.		8 5/8" Casing 16" Conductor	202' 0'	Unknown 20'
Cemented the hole from 1473' to the Surface as follows: From 1473' to 957' with 140 sacks of Thixotropic Cement with Green Dye and a Gas Blocker Additive. Tagged top of Thixotropic plug at 957'. From 957' to the surface with 450 sacks of Expandable Cement. Cement did circulate at the surface. A total of 590 sacks of cement were used to fill the hole from 1473' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1,266' - 1,273'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29th day of July, 2021


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 29th day of Aug, 2021

[Signature]
Notary Public

01/19/2024

My commission expires: 09/15/22

Permit No. 47-103-03395
Well No. 7770
Latitude: 39° 29' 53"N
Longitude: -80° 31' 54"W