

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7203A

LOCATION: Elevation: 1438.28' Quadrangle: Folsom W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 49.00 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 45.82 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 04/02/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of August, 2021, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|---------|---------|--------------|---------|
| Thixotropic w/ Green Dye and Gas Blocker | 1498' | 1111' | | |
| Expandable Cement | 1111' | Surface | | |
| 8 5/8" Casing | 1317' | Unknown | 249' | Unknown |
| 10 3/4" Casing | 271' | 606' | 0' | 335' |
| 16" Conductor | Surface | 20' | 0' | 20' |


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 15th day of September, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 4th day of Oct, 2021

My commission expires: 09/15/22 [Signature]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES
Lease or Property Owner
PO BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Folsom, W.VA
Well Location
GRANT
District
WETZEL
County
7203A
Well No.
B.W. PETERSON
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24th day of August, 2021 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|--|------------------|--|---------------|----------------|
| Cleaned the hole with a 12 1/4" bit from the surface to the top of the existing 10 3/4" casing at 271'. Reduced the hole to 9 7/8" at 271'. Cleaned the hole with a 9 7/8" bit from 271' to the top of the existing 8 5/8" casing at 1068'. Reduced the hole to 7 7/8" at 1068'. Cleaned the hole with a 7 7/8" bit from 1068' to 1498'. Removed 249' of 8 5/8" casing from 1068' to 1317'. Additional attempts to remove the remaining 8 5/8" casing from 1317' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1317' to an unknown depth. Cut the remaining 8 5/8" casing at 1360', 1410' and 1460'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1254' - 1260'). Left 335' of 10 3/4" casing in the hole from 271' to 606'. Left 20' of 16" conductor in the hole from the surface to 20'. Cemented the hole from 1498' to surface as follows: From 1498' to 1111' with 195 sacks of Thixotropic with Green Dye and a gas blocker additive. From 1111' to the surface with 535 sacks of Expandable Cement. Cement did circulate at the surface. A total of 730 sacks of cement were used to fill the hole from 1498' to the surface. | 16" Conductor | 0' | 20' | |
| | | 10 3/4" Casing | 0' | 335' |
| | | 8 5/8" Casing | 249' | Unknown |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | 1254' - 1260' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |

... and that the work of plugging and filling said well was completed on the 15th day of September, 2021

And further deponents saith not.



Sworn to and subscribed before me this 4th day of Oct, 2021

Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

09/20/2024

[Signature]

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03396
Well No. 7203A
Latitude: 39° 29' 49.00"N
Longitude: -80° 31' 45.82"W