

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7249

LOCATION: Elevation: 941.46 Quadrangle: Big Run, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 21.42 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 23.58 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 07/13/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 21st day of October, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	970'	534'		
Expandable Cement	534'	Surface		
7" Casing	901'	Unknown	121'	Unknown
10 3/4" Casing	374'	459'	0'	75'
16" Conductor	Surface	100'	0'	100'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 4th day of November, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 30th day of Nov, 2021

My commission expires: 09/15/22  
Thomas J. Sullivan  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/08/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MAGNOLIA LAND PARTNERS LLC.  
Lease or Property Owner  
104 S 20<sup>TH</sup> ST STE A PHILADELPHIA, PA 19103  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7249  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
**MATTHEW A. YEARSLEY** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21<sup>st</sup> day of October, 2021 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned the hole with a 12 1/4" bit from the surface to the top of the existing 10 3/4" casing at 374'. Reduced the hole to 9 7/8" at 374'. Cleaned the hole with a 9 7/8" bit from 374' to the top of the existing 7" casing at 780'. Reduced the hole to 6 1/4" at 780'. Cleaned the hole with a 6 1/4" bit from 780' to a total depth of 970'. Removed 121' of 7" casing from 780' to 901'. A diligent effort was made to pull the remaining 7" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 901' to an unknown depth. Cut the remaining 7" casing at 941'. The 7" casing had a pre-existing rip from 926' to 901'. Left 75' of 10 3/4" casing in the hole from 374' to 459'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (734.8' - 740.9') Left 100' of 16" conductor in the hole from the surface to 100'. <b>Cemented the hole from 970' to the surface as follows:</b> From 970' to 534' with 225 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 534'. Cemented the hole from 534' to the surface with 345 sacks of Expandable Cement. Cement did circulate at the surface. A total of 570 sacks of cement were used to fill the hole from 970' to the surface.	7" Casing 10 3/4" Casing 16" Conductor	121' 0' 0'	Unknown 75' 100'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<b>Pittsburgh</b>	<b>734.8' - 740.9'</b>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 4<sup>th</sup> day of November, 2021

And further deponents saith not.



Sworn to and subscribed before me this 30<sup>th</sup> day of Nov, 2021

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

04/08/2022

*[Signature]*  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03439  
Well No. 7249  
Latitude: 39° 30' 21.42"N  
Longitude: -80° 32' 23.58"W