

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Shuman Heirs #4 Operator Well No.: 7197

LOCATION: Elevation: 1231.35' Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 40.21 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 52.46 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 08/24/21

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1291'	953'	2 3/8" Tubing - 1085' Removed	Unknown
Expandable Cement	953'	Surface	7" Casing - 0' Removed	Unknown
			16" Conductor - 0' Removed	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 13th day of September, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 20th day of Sept, 2021

My commission expires: 09/15/22 [Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 01/19/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
BERNARD R. ELLIOTT SR.  
Lease or Property Owner  
104 WHITE RD. WELLSBURG, WV 26070  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7197  
Well No.  
SHUMAN HEIRS #4  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 9/23/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28<sup>th</sup> day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 1085' of 2 3/8" from 15' to 1100'. Left an unknown amount of 2 3/8" tubing in the hole from 1100' to an unknown depth. Cleaned the hole with a 12 1/4" bit from the surface to 321'. Reduced the hole to 9 7/8" at 321'. Cleaned the hole with a 9 7/8" bit from 321' to the top of the existing 7" casing at 1173'. Reduced the hole to 6 1/4" at 1173'. Cleaned the hole with a 6 1/4" bit from 1173' to 1291'. Left an unknown amount of 7" casing in the hole from 1173' to an unknown depth. Cut remaining 7" casing at 1291', 1241' and 1192'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from (1084.3' -1090.6'). Left 20' of 16" conductor in the hole from the surface to 20'.		7" Casing 16" Conductor	0' 0'	Unknown 20'
<b>Cemented the hole from 1291' to the surface as follows:</b> From 1291' to 953' with 175 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. From 953' to surface with 590 sacks of Expandable Cement. Cement did circulate at surface. A total of 765 sacks of cement were used to fill the hole from 1291' to the surface.				
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	1084.3' -1090.6'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 13<sup>th</sup> day of September, 2021

And further deponents saith not.



Sworn to and subscribed before me this 20<sup>th</sup> day of Sept, 2021

Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

[Signature] 01/19/2024  
Notary Public

My commission expires: 01/15/22

Permit No. 47-103-03451  
Well No. 7197  
Latitude: 39° 29' 40.21"N  
Longitude: -80° 30' 52.46"W