

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Robert Smith Operator Well No.: 7277

LOCATION: Elevation: 1105' Quadrangle: Folsom W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 57.25 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 10.09 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 03/07/2022 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of August, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1147'	730'	2 3/8" Tubing - 1361'	Unknown
Expandable Cement	730'	Surface	5 1/2" Casing - 1152'	Unknown
			7" Casing - 1204'	Unknown
			8 5/8" Casing - 386'	Unknown
			16" Conductor Pipe - 0'	27'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 7th day of September, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 29 day of September, 2022

My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

EDGAR D. & EDGAR D. BYARD JR.
Lease or Property Owner
2198 DEAD FALL RD. SMITHFIELD, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

FOLSOM W.VA

Well Location

GRANT

District

WETZEL

County

7277

Well No.

ROBERT SMITH

Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of August, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 1361' of 2 3/8" tubing from the surface to 1361'. Left an unknown amount of 2 3/8" tubing in the hole from 1361' to an unknown depth. Removed 1152' of 5 1/2" casing from the surface to 1152'. Left an unknown amount of 5 1/2" casing in the hole from 1152' to an unknown depth. Removed 1204' of 7" casing from the surface to 1204'. Left an unknown amount of 7" casing in the hole from 1204' to an unknown depth. Removed 386' of 8 5/8" casing from the surface to 386'. Attempts to remove additional 8 5/8" casing from 386' were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 386' to an unknown depth. Left 8 5/8" through the Pittsburgh Coal Seam (930.1' - 936.5'). Cut remaining 8 5/8" casing at the following depths: 618', 830.1', 880.1', 920.1', 925.1', 930.1', 931.7', 933.5', 935', 936.5', 941.5', 946.5', 986.5', 1036.5', 1086.5' and 1136.5'. Cleaned the hole with a 12 1/4" bit from the surface to 29'. Cleaned the hole with a 9 7/8" bit from 29' to 386'. Cleaned the hole with a 6 1/4" bit from 386' to 1147'. Left 27' of 16" conductor pipe in the hole from the surface to 27'.	2 3/8" Tubing 5 1/2" Casing 7" Casing 8 5/8" Casing 16" Conductor	1361' 1152' 1204' 386' 0'	Unknown Unknown Unknown Unknown 27'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>930.1' - 936.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of September, 2022

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 29 day of September, 2022

Cheryl Woods
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03490

Well No. 7277

Latitude: 39° 29' 57.25"N

Longitude: -80° 31' 10.09"W