

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7288

LOCATION: Elevation: 967.8' Quadrangle: Big Run WV

District: Grant County: Wetzel

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 00.87 Sec.

Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 30.7662 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah WV 26554 Monongah WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date 04/15/22

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of November, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1040'	553'		
Expanding Cement	553'	Surface		
16" Conductor Casing	Surface	30'	0'	30'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 7th day of December, 2022.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 30 day of December, 2022

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: WV Oil and Gas Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

COASTAL FOREST RESOURCES  
Lease or Property Owner  
P.O BOX 1023 HAVANA FL 32333  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN WV

Well Location

GRANT

District

WETZEL

County

7288

Well No.

B.W. PETERSON

Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of November, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned the hole with 12 1/4" bit from the surface to 143'. Reduced the hole to 9 7/8" at 143'. Cleaned the hole with 9 7/8" bit from 143' to 1040'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (753.6' to 759.5'). Left 30' of 16" Conductor pipe in the hole from the surface to 30'.	16" Conductor	0'	30'
	<b>Cemented the hole from 1040' to the surface as follows:</b> From 1040' to 553' with 235 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 553'. Cemented the hole from 553' to surface with 395 sacks of Expandable Cement. Cement did circulate at surface. A total of 630 sacks of cement were used to fill the hole from 1040' to the surface.			
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	753.6' - 759.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7<sup>th</sup> day of December, 2022

And further deponents saith not.



*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 30 day of December, 2022

*Christopher Andrew Willis*  
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03499  
Well No. 7288  
Latitude: 39° 30' 00.87"N  
Longitude: -80° 31' 30.75"W