

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: S&S Barker Operator Well No.: 7285

LOCATION: Elevation: 951.4' Quadrangle: Big Run W.VA

District: Grant County: Wetzel

Latitude: _____ Feet South of 39 Deg. 30 Min. 03.35 Sec.

Longitude: _____ Feet West of -80 Deg. 31 Min. 10.93 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 07/12/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 9th day of November, 2022, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1984'	1352'	5 1/2" Casing - 1984'	Unknown
Thixotropic Cement w/ Green Dye	1352'	589'	7" Casing - 1352'	Unknown
Expandable Cement	589'	Surface	8 5/8" Casing - 249'	248'
			16" Conductor Pipe - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 5th day of December, 2022.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 30 day of December, 2022.



My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: WV Oil and Gas Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN W. SHRIVER ETAL
Lease or Property Owner
704 GREENWOOD MANOR CIR. MELBOURNE, FL 32904
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7285
Well No.
S&S BARKER
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of November, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 1984' of 5 1/2" casing from the surface to 1984'. Left an unknown amount of 5 1/2" casing in the hole from 1984' to an unknown depth. Cleaned a 6 1/4" hole through the existing 7" casing from the surface to the top of the remaining 5 1/2" casing at 1984'. Removed 1352' of 7" casing from the surface to 1352'. Left an unknown amount of 7" casing in the hole from 352' to an unknown depth. Cemented the bottom hole from 1984' to 1352' with 105 sacks of Expandable Cement with a Gas Blocker additive. Cleaned a 12 1/4" hole from the surface to 252'. Reduced the hole to 9 7/8" at 252'. Cleaned a 9 7/8" hole from 252' to the top of the existing 8 5/8" casing at 747'. Reduced the hole to 7 7/8" at 747'. Cleaned a 7 7/8" hole from 747' to the top of the bottom hole plug at 1352'. Removed 249' of 8 5/8" casing from 747' to 996'. Left 248' of 8 5/8" casing in the hole from 996' to 1244'. Cleaned a 9 7/8" from 747' to the top of the remaining 8 5/8" casing at 996'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (789.1' - 795.2'). Left 20' of 16" conductor pipe in the hole from the surface to 20'. Cemented the hole from 1352' back to the surface as follows: From 1352' to 589' with 230 sacks of Thixotropic Cement with Green Dye and from 589' to the surface with 450 sacks of Expandable Cement. Cement did circulate at the surface. A total of 785 sacks of cement were used to fill the hole from 1352' to the surface.	5 1/2" Casing	1984'	Unknown	
	7" Casing	1352'	Unknown	
	8 5/8" Casing	249'	248'	
	16" Conductor	0'	20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>789.1' - 795.2'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 5th day of December, 2022

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 30 day of December, 2022

Christopher Andrew Willis
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03517
Well No. 7285
Latitude: 39° 30' 03.35"N
Longitude: -80° 31' 10.93"W