

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: G.W. Ensimer Operator Well No.: 7319

LOCATION: Elevation: 1338.6' Quadrangle: Folsom, W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 59.56 Sec.
Longitude: _____ Feet West of -80 Deg. 30 Min. 41.10 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 12/08/2022 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of December, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1512	1390'	7" Casing - 516'	Unknown
Thixotropic Cement w/ Green Dye-Gas Bl	1390'	982'	8 5/8" Casing - 276'	Unknown
Expandable Cement	982'	Surface	16" Conductor - 0' Removed	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 10th day of January, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 14 day of February, 2023

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CYNTHIA L. MERRIFIELD
Lease or Property Owner
3268 MANNINGTON ROAD SMITHFIELD, WV 26437
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM W.VA
Well Location
GRANT
District
WETZEL
County
7319
Well No.
G.W. ENSIMINGER
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6th day of December, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In	
Cleaned a 12 1/4" hole from the surface to 319'. Reduced the hole to 9 7/8" at 319'. Cleaned a 9 7/8" hole from the surface to the top of the existing 8 5/8" casing at 877'. Reduced the hole to 7 7/8" at 877'. Cleaned a 7 7/8" hole from 877' to the top of the existing 7" casing at 984'. Reduced the hole to 6 1/4" at 984'. Cleaned a 6 1/4" hole from 984' to 1512'. Removed 516' of 7" casing from 984' to 1500'. Left an unknown amount of 7" casing in the hole from 1500' to an unknown depth. Removed 276' of 8 5/8" casing from 877' to 1153'. Attempts to remove additional 8 5/8" casing from 1153' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1153' to an unknown depth. Cut the remaining 8 5/8" casing at the following depths; 1389.1, 1339.1', 1289.1', 1239.1', 1189.1', 1187.1', 1186.1', 1184.7' and 1182.7'. The 8 5/8" casing had an existing rip in it at 1186'. Perforated the 8 5/8" casing with 6 shots at each of the following depths; 1199.1', 1194.1', 1187.1', 1185.1', 1177.7' and 1172.7'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1182.7' - 1189.1'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.		7" Casing	516'	Unknown	
			8 5/8" Casing	276'	Unknown
			16" Casing	0'	20'
Cemented the hole from 1512' back to the surface as follows: From 1512' to 1390' with 30 sacks of Expandable Cement with a Gas Blocker additive and 170 sacks of Thixotropic Cement with a Gas Blocker additive and Green Dye. Tagged top of Thixotropic plug at 982'. Cemented the hole from 982' to the surface with 550 sacks of Expandable Cement. Cement did circulate at the surface. A total of 750 sacks of cement were used to fill the hole from 1512' to the surface.		Description of Monument			
Coal Seams <u>Pittsburgh</u>	1182.7' - 1189.1'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 10th day of January, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 14 day of February 2023

Christopher Andrew Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03537
Well No. 7319
Latitude: 39° 29' 59.56"N
Longitude: -80° 30' 41.10"W