

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7292

LOCATION: Elevation: 938 Quadrangle: Big Run, W.VA

District: Grant County: \_\_\_\_\_

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 49.37 Sec.

Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 55.59 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 01/12/2023 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 11th day of April, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1010'	437'	8 5/8" Casing - 0'	Unknown
Expandable Cement	437'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 25th day of April, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 15th day of May, 2023

My commission expires: June 8, 2027  
Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MICHAEL A. BAKER SR.  
Lease or Property Owner  
P.O. BOX 93 SMITHFIELD, WV 26437  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7292  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11<sup>th</sup> day of April, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 384'. Cleaned a 9 7/8" hole from 384' to top of existing 8 5/8" casing at 938'. Cleaned a 7 7/8" hole from 938' to 1010'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (730.0' – 736.3'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 20'
<b><u>Cemented the hole from 1010' to the surface as follows:</u></b> From 1010' to 437' with 265 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 437'. Cemented the hole from 437' to the surface with 360 sacks of Expandable Cement. Cement did circulate at the surface. A total of 625 sacks of cement were used to fill the hole from 1010' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	730.6' – 736.3'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 25<sup>th</sup> day of April, 2023

And further deponents saith not.


Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 15<sup>th</sup> day of May, 2023

Christopher Andrew Willis  
Notary Public

My commission expires:  
June 8, 2027



Permit No. 47-103-03544  
Well No. 7292  
Latitude: 39° 30' 49.37" N  
Longitude: -80° 31' 55.59" W