

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: L. Stanton Leezer Operator Well No.: 8097

LOCATION: Elevation: 1469' Quadrangle: Hundred W.VA, PA

District: Church County: Wetzel

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 39 Min. 53.88 Sec.

Longitude: \_\_\_\_\_ Feet West of -80 Deg. 24 Min. 43.33 Sec.

Well Type: OIL  GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 02/23/2023 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of June, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1522'	1092'	7" Casing - 104'	Unknown (Cuts at 1448.5' and 1398.5')
Expandable Cement	1092'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of July, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 7th day of August, 2023

My commission expires: June 8, 2027  
Stephen Mccoy  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_  
Digitally signed by Stephen Mccoy Date: 2023.08.10 10:43:19 -04'00'

RECEIVED  
Office of Oil and Gas  
SEP 01 2023  
10/13/2023  
WV Department of  
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
LEEZER FAMILY IRREVOCABLE TRUST  
Lease or Property Owner  
P.O. BOX 933 BARRACKVILLE, WV 26559  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED W.VA, PA  
Well Location  
CHURCH  
District  
WETZEL  
County  
8097  
Well No.  
L. STANTON LEEZER  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen Mccoy Digitally signed by Stephen Mccoy  
Date: 2023.08.10 10:42:49 -04'00'

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22<sup>nd</sup> day of June, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 278'. Cleaned a 9 7/8" hole from 278' to top of existing 7" casing at 1252'. Cleaned a 6 1/4" hole from 1252' to 1522'. Cut 7" casing at 1498.5'. Removed 104' of 7" casing from 1292' to 1356'. A diligent effort was made to remove additional 7" casing from 1356' by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1292' to an unknown depth. Cut remaining 7" casing at 1448.5' and 1398.5'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1292.5' - 1298.5'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.		7" Casing  16" Conductor	104'  0'	Unknown  20'
<b>Cemented the hole from 1522' to the surface as follows:</b> From 1522' to 1092' with 185 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 1092'. Cemented the hole from 1092' to the surface with 585 sacks of Expandable Cement. Cement did circulate at the surface. A total of 770 sacks of cement were used to fill the hole from 1522' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>1292.5' - 1298.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12<sup>th</sup> day of July, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 7<sup>th</sup> day of August 2023

[Signature]  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03560  
Well No. 8097  
Latitude: 39° 39' 53.88"N  
Longitude: -80° 24' 43.33"W

RECEIVED  
Office of Oil and Gas

SEP 01 2023

10/13/2023  
Department of Environmental Protection