

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Douglas Joe Smith Operator Well No.: 7402

LOCATION: Elevation: 1315.65' Quadrangle: Big Run WV  
District: Grant County: Wetzel  
Latitude: 39.51455 Feet South of 39 Deg. 30 Min. 52.38 Sec.  
Longitude: -80.50803 Feet West of -80 Deg. 30 Min. 28.908 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 4/11/2024 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of June, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Green Dye and Gas Blocker	1,350'	895'	8 5/8" Casing - 467'	Unknown
Expanding Cement	895'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 24th day of July, 2024.

And further deponents saith not. Matthew A. Yearsley  
Delbert L. Moore



Sworn and subscribe before me this 23rd day of August, 2024

My commission expires: June 8, 2027  
Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
DOUGLAS JOE SMITH  
Lease or Property Owner  
4464 MANNINGTON ROAD SMITHFIELD, WV 26437  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7402  
Well No.  
DOUGLAS JOE SMITH  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by WEST VIRGINIA LAND RESOURCES INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19<sup>th</sup> day of June, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 644'. Reduced hole to 9 7/8" at 644'. Cleaned 9 7/8" hole from 644' to 1111'. Reduced hole to 7 7/8" at 1111'. Cleaned a 7 7/8" hole from 1111' to 1350'. Cleaned 9 7/8" hole through Pittsburgh Coal Seam (1095' - 1101.5'). Removed 467' of 8 5/8" casing from 644' to 1,111'. A diligent effort was made to remove the remaining 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount of 8 5/8" casing from 1111' to an unknown depth. Cut remaining 8 5/8" casing as 1304'. Perforated the remaining 8 5/8" casing at the following depths: 1301.5', 1251.5', 1201.5', 1151.5', and 1111.5'. Left 20' of 16" conductor casing in hole from surface to 20'.		8 5/8" Casing  16" Conductor	467'  0'	Unknown  20'
<b>Cemented Hole from 1350' to Surface as follows:</b> Cemented from 1350' to 895' with 195 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 895' to Surface with 590 sacks Expanding Cement. Cement did circulate at surface. A total of 785 sacks were used to fill the hold from 1350' to Surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>1095' - 1101.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 24<sup>th</sup> day of July, 2024

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Delbert L. Moore

Delbert Moore

Sworn to and subscribed before me this 23<sup>rd</sup> day of August, 2024

My commission expires:

June 8, 2027



Christopher Willis  
Notary Public

Permit No. 47-103-03651  
Well No. 7402  
Latitude: 39° 30' 52.38"N  
Longitude: -80° 30' 28.908"W