

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B W Petersons 2282 Operator Well No.: 5561

LOCATION: Elevation: 1305.77' Quadrangle: Glover Gap WV
District: Grant County: Wetzel
Latitude: 39.50970 Feet South of 39 Deg. 30 Min. 34.9189 Sec.
Longitude: -80.49027 Feet West of 80 Deg. 29 Min. 24.9763 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 05/29/24

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of October, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
<small>Thrusting Cement w/ Green Clay and Gas Blocker</small>	1413'	975'	8 5/8" Casing - 0'	Unknown
Expandable	975'	Surface	16" Conductor Casing - 0'	20'

Description of monument: 77" of 7' casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 24th day of October, 2024.

And further deponents saith not. Matthew A. Yearsley
Thomas Thrasher



Sworn and subscribe before me this 5th day of November, 2024
My commission expires: August 13, 2029 Kerri A. McCormick
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

DALLASON LUMBER INC.
Lease or Property Owner
PO BOX 159 JACKSONBURG, WV 26377
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Glover Gap WV
Well Location
GRANT
District
WETZEL
County
5561
Well No.
B W PETERSON 2282
Farm

STATE INSPECTOR SUPERVISING PLUGGING STEVE MCCOY

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:
MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1st day of October, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 12 1/4" hole from surface to 66'. Reduced to a 9 7/8" bit and cleaned a 9 7/8" hole from 66' to 1140'. Tagged the top of 8 5/8" casing at 1140'. Reduced to a 6 1/4" bit and cleaned a 6 1/4" hole from 1140' to 1413'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (1175' - 1182.5'). Cut 8 5/8" casing at 1382.5' and 1175'. A diligent effort was made to pull the 8 5/8" casing by pulling 150% of the string weight. All attempts were unsuccessful. Additional cuts in the 8 5/8" casing were made at 1332.5', 1282.5', 1232.5', 1192.5', 1187.5', 1182.5', 1180.6', 1178.7', 1176.8', 1170', and 1165'.	8 5/8" Casing 16" Conductor Casing	0' 0'	Unknown 20'	
Cemented hole from 1413' to surface as follows:				
Cemented hole from 1413' to 975' using 165 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 975' to surface with 515 sacks of Expandable Cement. Cement did circulate at the surface. A total of 680 sacks of Cement were used to fill the hole from 1413' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1175' - 1182.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 24th day of October, 2024

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 5th day of November

Kerri A. McCormick
Notary Public

My commission expires:
August 13, 2029



Permit No. 47-103-03671
Well No. 5561
Latitude: 39° 30' 34.92"N
Longitude: -80° 29' 24.98"W