

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Jeremy B And Lisa Kele Operator Well No.: 8182  
 LOCATION: Elevation: 1180.00' Quadrangle: Hundred W.Va Pa  
 District: Church County: Wetzel  
 Latitude: 39.672403 Feet South of 39 Deg. 40 Min. 20.7 Sec.  
 Longitude: -80.409186 Feet West of 80 Deg. 24 Min. 33.1 Sec.

RECEIVED  
Office of Oil and Gas

JAN 20 2025

WV Department of  
Environmental Protection

Well Type: OIL  GAS

Company West Virginia Land Resources Coal Operator West Virginia Land Resources  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, Wv 26554 Monongah, Wv 26554  
 Agent David Roddy Coal Operator \_\_\_\_\_  
 or Owner \_\_\_\_\_  
 Permit Issued Date 9/16/2024

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Mathew A Yearsley and Cody Weaver being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12th day of December, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic with green dye	1200'	778'	<u>5 5/8" casing</u>	Unknown
Expandable cement w/ gas blocker	778'	Surface	<u>no casing removed</u>	

Description of monument: 77" of 7" casing with company name, well #, API#, and date completed. and that the work of plugging and filling said well was completed on the 18th day of January, 2025.

And further deponents saith not. Mathew Yearsley  
Cody Weaver



Sworn and subscribe before me this 7th day of February, 2025

My commission expires: August 13, 2029 Kerri A McCormick

Notary Public  
Digitally Signed By  
Stephen Mccoy  
Date: 2025.02.20  
10:39:36 -05'00'

Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy Title: \_\_\_\_\_

02/21/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554

Address  
WEST VIRGINIA LAND RESOURCES  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
Jeremy B And Lisa Kelch  
Lease or Property Owner  
1011 Santee run rd. Hundred WV  
Address

WEST VIRGINIA LAND RESOURCES  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address  
Hundred Wv  
Well Location  
Church  
District  
WETZEL  
County  
8182  
Well No.  
JEREMY B AND LISA KELE  
Farm

RECEIVED  
Office of Oil and Gas

JAN 20 2025

WV Department of  
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING STEPHEN MCCOY

Digitally signed by Stephen  
Mccoy  
Date: 2025.02.20 10:39:51  
-05'00'

AFFIDAVIT

Stephen Mccoy

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and CODY WEAVER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by WEST VIRGINIA LAND RESOURCES well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12<sup>th</sup> day of December, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 12 1/4" hole from surface to 127'. Reduced hole to 9 3/8" at 127'. Cleaned a 9 3/8" hole from 127' to top of existing 8 5/8" casing at 935'. Reduced hole to 6 1/4" at 935'. Cleaned a 6 1/4" hole from 935' to 1200'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (978' - 985'). Cut 8 5/8" casing at 1185'. A diligent effort was made to remove the 8 5/8" casing by pulling 150% of string weight, all attempts were unsuccessful. Perforated 8 5/8" casing at the following depths with six shots each: 1135', 1085', 1035', 995', 990', 985', 983.25', 981.5', 979.75', 978', 973', and 968'. Left an unknown amount of 8 5/8" casing from 935' to an unknown depth.	8 5/8" Casing	0'	Unknown	
Cemented hole from 1200' to surface as follows:				
Cemented hole from 1200' to 778' with 160 sacks of Thixotropic Cement with Green Dye and from 778' to surface with 385 sacks of Expandable Cement. Cement did circulate at surface. A total of 545 sacks of cement were used to fill 1200' to surface.				
Coal Seams		Description of Monument		
Pittsburgh	978'-985'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 18<sup>th</sup> day of January , 2025

And further depose and say that



Matthew A. Yearsley

Matthew A. Yearsley

Cody Weaver

Cody Weaver

Sworn to and subscribed before me this

7<sup>th</sup> day of February 2025

Kerri A. McCormick  
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03685  
Well No. 8182  
Latitude: 39°40'20.7"N  
Longitude: -80°24'33.1"W

02/21/2025