

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. HIXENBAUGH Operator Well No.: 8139

LOCATION: Elevation: 1,414.04' Quadrangle: HUNDRED W.VA,PA
District: CHURCH County: WETZEL
Latitude: 39.67109 Feet South of 39 Deg. 40 Min. 15.9350 Sec.
Longitude: -80.39968 Feet West of -80 Deg. 23 Min. 58.8615 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
Permit Issued Date 09/16/2024 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of November, 2024, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Hydroptic with Green Eye and Gas Ejector	1500'	1037'	8 5/8" Casing - 0'	Unknown
Expandable	1037'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 6th day of December, 2024.

And further deponents saith not. Matthew A. Yearsley
John Campbell

Sworn and subscribe before me this 13th day of December, 2024

My commission expires: August 13, 2029
Kerri A McCormick
Notary Public



JAN 08 2025

WV Department of Environmental Protection
01/17/2025

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
SAMUEL M. & JENNIFER SNYDER
Lease or Property Owner
43 ROCK LAKE ROAD, FAIRMONT, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED, W.VA, PA
Well Location
CHURCH
District
WETZEL
County
8139
Well No.
J. HIXENBAUGH
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCoy

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC., operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of November, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from surface to 229'. Reduced to 9 7/8" bit and cleaned a 9 7/8" hole from 229' to 1290'. Cleaned a 9 7/8" hole through the Pittsburgh Coal seam (1237.5' - 1244'). Top of 8 5/8" casing found at 1290'. Reduced to 7 7/8" bit and cleaned 7 7/8" hole inside the 8 5/8" casing from 1290' to 1500'. A diligent effort was made to remove the 8 5/8" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left and unknown amount of 8 5/8" casing in hole below 1290'. 8 5/8" casing was cut at 1444', 1394' and 1344'. 8 5/8" casing was perforated at 1294'.		8 5/8" Casing 16" Conductor Casing	0' 0'	Unknown 20'
<u>Cemented hole from 1500' to surface as follows:</u>				
Cemented hole from 1500' to 1037' with 185 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented hole from 1037' to surface with 495 sacks of Expandable Cement. Cement did circulate at the surface. A total of 680 sacks of cement were used to fill the hole from 1500' to the surface.				
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 6th day of December, 2024

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Sworn to and subscribed before me this 13th day of December

Kerrri A. McCormick
Notary Public

My commission expires: August 13, 2029

Permit No. 47-103-03686
Well No. 8139
Latitude: 39° 40' 15.94"N
Longitude: -80° 23' 58.86"W

RECEIVED
Office of Oil and Gas

JAN 08 2025

WV Department of
Environmental Protection

01/17/2025