

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: R L Ensminger Est Operator Well No.: 7341
LOCATION: Elevation: 1241.61' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.50669 Feet South of 39 Deg. 30 Min. 24.08 Sec.
Longitude: -80.52869 Feet West of 80 Deg. 31 Min. 43.28 Sec.

Well Type: OIL X GAS

Company West Virginia Land Resources Coal Operator West Virginia Land Resources
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator
Permit Issued Date 11/21/2024 or Owner

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Mathew A Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1st day of January, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED		LEFT
Thix/ With green dye	1,257'	818'	7" Casing	21'	Unknown
Expanding	818'	Surface	16" Conductor	None	20'

Description of monument: 77" of 7" Casing with company name, Well #, API#, and date completed. and that the work of plugging and filling said well was completed on the 7th day of February, 2025.


And further deponents saith not. Matthew A Yearsley

Delbert Moore

Sworn and subscribe before me this 26th day of March, 2025

My commission expires: August 13, 2029

Kerri A McCormick
Notary Public



Office of Oil and Gas

APR 14 2025

Affidavit reviewed by the Office of Oil and Gas: [Signature]

Title:

WV Department of
Environmental Protection
03/23/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
R.L ENSMINGER EST
Lease or Property Owner
10100 Schneiter Cir Anchorage, AK 99507
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
SMITHFIELD, WV
Well Location
GRANT
District
WETZEL
County
6341
Well No.
R L ENSMINGER EST
Farm

STATE INSPECTOR SUPERVISING PLUGGING STEVE MCCOY


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and **Delbert Moore** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by **West Virginia Land Resources** well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24th day of January, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 387'. Reduced hole to 9 7/8" at 387'. Cleaned 9 7/8" hole from 387' to 1,103' to the top of existing 7" casing. Reduced hole to 6 1/4" at 1,103'. Cleaned 6 1/4" hole from 1,103' to 1257'. Removed 21' of 7" casing from 1,103' to 1,124'. Continued to clean 9 7/8" hole from 1,103' to 1,124'. Cleaned 9 7/8" hole through Pittsburgh Coal (1018.5' to 1025'). Cut remaining 7" casing at 1,225'. Perforated 7' casing at the following depths 6 shots each: 1,175' and 1,025'. A diligent effort was made to remove the remaining 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount of 7" casing in hole from 1,124' to unknown. Left 20' of 16" casing in hole from surface to 20'.	7" Casing 16" Conductor	18' 0'	Unknown 20'	
<u>Cemented hole from 1,257' to surface as follows:</u> Cemented from 1,257' to 818' with 185 sacks Thixotropic Cement with Green Dye and Gas Blocker additive through the Pittsburgh Coal. From 818' to surface with 510 sacks Expanding Cement. Cement did circulate at surface.				
Coal Seams		Description of Monument		
Pittsburgh	1,018.5'-1,025'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of February, 2025

And further deposes that said:



Matthew A. Yearsley

Matthew A. Yearsley

Delbert Moore

Delbert Moore

Sworn to and subscribed before me this 26th day of March

My commission expires:

August 13, 2029

RECEIVED
Office of Oil and Gas
APR 14 2025
WV Department of
Environmental Protection
Permit No. 47-103-03691
Well No. 7341
Latitude: 39° 30' 24.08" N
Longitude: -80° 31' 43.28" W
05/23/2025