

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

RECEIVED
Office of Oil and Gas

APR 22 2025

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Norris 5 Operator Well No.: 7342

LOCATION: Elevation: _____ Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.5188 Feet South of 39 Deg. 31 Min. 07.6809 Sec.
Longitude: 80.5253 Feet West of 80 Deg. 31 Min. 31.0967 Sec.

Well Type: OIL ☒ GAS ☐

| | | | |
|--------------------|---|---------------|---|
| Company | <u>West Virginia Land Resources, Inc.</u> | Coal Operator | <u>West Virginia Land Resources, Inc.</u> |
| | <u>1 Bridge Street</u> | or Owner | <u>1 Bridge Street</u> |
| | <u>Monongah, WV 26554</u> | | <u>Monongah, WV 26554</u> |
| Agent | <u>David Roddy</u> | Coal Operator | _____ |
| Permit Issued Date | <u>1/31/25</u> | or Owner | _____ |

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5th day of March, 2025, and the well was plugged and filled in the following manner:


| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|-----------------------------------|-------|---------|---------------------------|------|
| Thixotropic Cement with Green Dye | 1310' | 881' | 16" Conductor Casing - 0' | 20' |
| Expanding Cement | 881' | Surface | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 24th day of March, 2025.

And further deponents saith not.

Matthew A. Yearsley

Delbert L. Moore



Sworn and subscribe before me this 15th day of April, 2025

My commission expires: August 13, 2029
Stephen Mccoy
Notary Public for Stephen Mccoy

Affidavit reviewed by the Office of Oil and Gas: _____ Date: 2025.04.18 10:03:33 -04'00'

04/25/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

APR 22 2025

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WV Department of
Environmental Protection

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
R L ENSMINGER EST
Lease or Property Owner
10100 SCHNEITER CIR, ANCHORAGE AK
Address

WEST VIRGINIA LAND RESOURCES, INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN WV
Well Location
GRANT
District
WETZEL
County
7342
Well No.
NORRIS 5
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

Stephen Mccoy

Digitally signed by Stephen
McCoy
Date: 2025.04.18 10:02:45 -04'00'

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and Delbert L. Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 5th day of March, 2025 and that the well was plugged in the following manner:

| Sand or Zone Record | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|---|------------------|--|------------------|-------------------|
| Formation | | | | |
| Cleaned a 12 1/4" hole from surface to 244'. Reduced hole to 9 7/8" at 244'. Cleaned a 9 7/8" hole from 244' to 1186'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1081' - 1088'). Reduced hole to 6 1/4" at 1186'. Cleaned a 6 1/4" hole from 1186' to an approved depth of 1310'. Left 20' of 16" casing from 20' to surface. | | 16" Conductor Casing | 0' | 20' |
| <u>Cemented Hole from 1310' to surface as follows:</u> Cemented from 1310' to 881' with 225 sacks of Thixotropic Cement with green dye and gas blocker. From 881' to surface with 580 sacks of Expanding Cement. Cement did circulate at surface. A total of 805 sacks were used to fill hole from 1310' to surface. | | | | |
| Coal Seams | | Description of Monument | | |
| Pittsburgh | 1081' - 1088' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |
| | | | | |
| | | | | |

... and that the work of plugging and filling said well was completed on the 24th day of March, 2025

And further deponents saith not



Matthew A. Yearsley
Matthew A. Yearsley

Delbert L. Moore
Delbert L. Moore

Sworn to and subscribed before me this 15th day of April

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03716
Well No. #7342
Latitude: 39° 31' 07.6809"N
Longitude: -80° 31' 31.0967"W

04/25/2025