

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Ensminger 4 Operator Well No.: 7344
LOCATION: Elevation: 1250' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.5230 Feet South of 39 Deg. 31 Min. 23.13 Sec.
Longitude: -80.5231 Feet West of -80 Deg. 31 Min. 23.65 Sec.

Well Type: OIL _____ GAS _____

Company	<u>West Virgina Land Resources INC</u>	Coal Operator	<u>West Virgina Land Resources INC</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>3/14/25</u>	or Owner	_____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of April, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ green dye	1275'	845'	8-5/8" - None	UNKNOWN
Expanding	845'	Surface	13-3/8" Conductor Casing	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 15th day of May, 2025.

And further deponents saith not.


Delbert Moore

Matthew A. Yearsley

Sworn and subscribe before me this 11th day of July, 2025

My commission expires: August 13, 2029

Kerri A McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
R L ENSMINGER
Lease or Property Owner
10100 SCHNEITER CIRCLE ANCHORAGE AK 99507
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN WV
Well Location
GRANT
District
WETZEL
County
7344
Well No.
ENSMINGER 4
Farm

STATE INSPECTOR SUPERVISING PLUGGING STEVE MCCOY


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and **DELBERT MOORE** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of April 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 490'. Reduced hole to 9 7/8" at 490'. Cleaned 9 7/8" hole from 490' to 1066'. Cleaned 9 7/8" hole through Pittsburgh Coal 1045' to 1052'. Reduced hole to 7 7/8" at 1066'. Cleaned 7 7/8" hole from 1066' to 1275'. Placed cuts in 8 5/8" casing at 1252'. Pulled 8 5/8" casing up the wellbore 14' until casing was unable to continue to be pulled. Left 1052' of 8 5/8" casing from 1052' to an unknown depth. A diligent effort to pull remaining 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Perforated 8 5/8" casing with 6 shots each at the following depths 1202', 1152', 1102', 1062', 1057'.		8-5/8" Casing	0'	Unknown
		13-3/8" Conductor Casing	0'	20'
Cemented hole from 1275' to surface as follows: Cemented hole from 1275' to 845' with 180 sacks Thixotropic Cement with Green dye and gas blocker additive. Cemented hole from 845' to surface with 505 sacks Expanding Cement. Cement did circulate at Surface. Left 20' of 13 3/8" conductor casing in hole from surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	1045'-1052'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 15th day of May, 2025



Matthew A. Yearsley

Matthew A. Yearsley

Delbert Moore

Delbert Moore

Sworn to and subscribed before me this

11th day of July 2025

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03723

Well No. 7344

Latitude: 39° 31' 23.13"N

Longitude: -80° 31' 23.65"W