

### AFFIDAVIT OF PLUGGING AND FILLING WELL

Farm name: **B W Peterson 49** Operator Well No.: **7430**

Well Type: OIL GAS X

|                    |                              |               |                              |
|--------------------|------------------------------|---------------|------------------------------|
| Company            | West Virginia Land Resources | Coal Operator | West Virginia Land Resources |
|                    | 1 Bridge Street              | or Owner      | 1 Bridge Street              |
|                    | Monongah, WV 26554           |               | Monongah, WV 26554           |
| Agent              | David Roddy                  | Coal Operator |                              |
| Permit Issued Date | 4-30-25                      | or Owner      |                              |

RECEIVED  
Office Of Oil and Gas

NOV 6 2025

WV Department of  
Environmental Protection

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of July, 2025, and the well was plugged and filled in the following manner:

| TYPE                       | FROM   | TO      | PIPE REMOVED         | LEFT    |
|----------------------------|--------|---------|----------------------|---------|
| Thixotropic w/ Gas Blocker | 1,163' | 963'    | 5 1/2" Casing - None | Unknown |
| Thixotropic w/ Green Dye   | 963'   | 737'    | 7" Casing - 888'     | None    |
| Expanding Cement           | 737'   | Surface | 16" Conductor - None | 18'     |
|                            |        |         |                      |         |
|                            |        |         |                      |         |
|                            |        |         |                      |         |
|                            |        |         |                      |         |

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed. and that the work of plugging and filling said well was completed on the 2nd day of October, 2025.


And further deponents saith not.

Matthew A. Yearley

Thomas Thrasher


Sworn and subscribe before me this 27<sup>th</sup> day of October, 2025

My commission expires: August 13, 2029

29   
Notary Public  
Digitally signed by Stephen

Notary Public  
Digitally signed by Stephen  
Mccoy

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Date: 2025.10.30 22:13:05 -04'00' Title: \_\_\_\_\_



11/14/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**JOHN DALE COEN**  
Lease or Property Owner  
**666 S LINDEN AVE ALLIANCE, OH 44601**  
Address

**WEST VIRGINIA LAND RESOURCES**  
Name of Well Operator  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Complete Address  
**BIG RUN, WV 7.6'**  
Well Location  
**GRANT**  
District  
**WETZEL**  
County  
**7430**  
Well No.  
**B W PETERSON 49**  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

Stephen Mccoy  
Digitally signed by Stephen Mccoy  
Date: 2025.10.30 22:12:44 -04'00'

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of WETZEL ss:

**MATTHEW A. YEARSLEY** and **THOMAS THRASHER** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18<sup>th</sup> day of July, 2025 and that the well was plugged in the following manner:

| Sand or Zone<br>Record   | Filling Material | Casing/Tubing Size   | Casing<br>Pulled | Casing<br>Left In |
|--|------------------|--|------------------|-------------------|
| Formation  |                  |  |                  |                   |
| Cleaned out existing 7" casing from surface to 888' with a 6 1/4" bit. Cleaned open hole from 888' to 902' with a 6 1/4" bit. Tagged existing 5 1/2" casing at 902'. Cleaned out existing 5 1/2" casing with a 4 3/4" bit from 902' to 1,163'. Cut 5 1/2" casing at 1,143'. Made a diligent effort to remove 5 1/2" casing from 902' to 1,143'. All attempts were unsuccessful. Placed cuts 5 1/2" casing at 1,093', 1,043', and 993'. Cemented hole from 1,163' to 963' using 25 sacks of Thixotropic Cement with Gas Blocker additive. Pulled 7" casing from surface to 888' leaving no remaining 7" casing in hole. Cleaned hole with a 9 7/8" bit from surface to 902' to the top of 5 1/2" casing at 902'. Milled 5 1/2" casing from 902' to 921' using a 9 1/4" flat-bottom mill. Cleaned out 5 1/2" casing with a 4 3/4" bit from 921' to 963'. Tagged cement plug at 963'. Cleaned a 4 3/4" hole through the Pittsburgh Coal Seam from 937' to 943'. Perforated 5 1/2" casing at 953', 948', 943', 939', 937', 932', and 927' using 6 shots at each location for 42 total shots in hole. | 5 1/2"           | None   | Unknown          |                   |
|  |                  | 7"   | 888'             | None              |
|  |                  | 16"  | None             | 18'               |
| RECEIVED<br>Office Of Oil and Gas<br>NOV 6<br>WV Department of Environmental Protection  |                  |  |                  |                   |
| <b><u>Cement Hole from 963' to surface as followed:</u></b><br>Cemented hole from 963' to 737' using 105 sacks of Thixotropic Cement with Green Dye and from 737' to surface using 475 sacks of Expanding Cement. Used a total of 605 sacks of Cement. Cement did circulate at surface. Left 18' of 16" conductor in hole from surface to 18'.   |                  |  |                  |                   |
| Coal Seams   |                  | Description of Monument  |                  |                   |
| Pittsburgh   | 937' – 943'      | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |                  |                   |

... and that the work of plugging and filling said well was completed on the 2<sup>nd</sup> day of October, 2025



Sworn to and subscribed before me this 27<sup>th</sup> day of October 2025

My commission expires:

August 13, 2029

Matthew A. Yearsley

Matthew A. Yearsley

Thomas Thrasher

Thomas Thrasher

Kerri A. McCormick  
Notary Public

Permit No. 47-103-03732

Well No. 7430

Latitude: 39° 31' 4.60" N

Longitude: 80° 31' 4.52" W

11/14/2025