

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B W Peterson 78 Operator Well No.: 7337

LOCATION: Elevation: 1,364.65' Quadrangle: Big Run, WV

District: Grant County: Wetzel

Latitude: 39.524806 Feet South of 39 Deg. 31 Min. 29.3 Sec.

Longitude: -80.527648 Feet West of 80 Deg. 31 Min. 39.5 Sec.

Well Type: OIL GAS X

Company	<u>West Virginia Land Resources</u> <u>1 Bridge Street</u> <u>Monongah, WV 26554</u>	Coal Operator or Owner	<u>West Virginia Land Resources</u> <u>1 Bridge Street</u> <u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator or Owner	
Permit Issued Date	<u>7-9-25</u>		

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of June, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye & Gas Block	1,502'	935'	8 5/8" Casing - None	Unknown
Expandable Cement	935'	Surface	16" Conductor - None	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed. and that the work of plugging and filling said well was completed on the 19th day of August, 2025.

And further deponents saith not.


Matthew A. Yearsley

Delbert L. Moore

Sworn and subscribe before me this 22nd day of September, 2025

My commission expires: August 13, 2029

Kerry McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES

Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

WEST VIRGINIA LAND RESOURCES

Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

DALLISON LUMBER INC

Lease or Property Owner

1528 Fallen Timber Rd Smithfield, WV 26437

Address

WEST VIRGINIA LAND RESOURCES

Name of Well Operator

1 BRIDGE STREET MONONGAH, WV 26554

Complete Address

Big Run, WV 7.5'

Well Location

GRANT

District

WETZEL

County

7337

Well No.

B W PETERSON 78

Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Wetzel ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26th day of June, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 314'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 314' to 714' which is the top of 8 5/8" casing. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 714' to 1,502'. Cleaned 7 7/8" hole through the Pittsburgh Coal Seam 1,135' to 1,142'. Made a diligent effort to pull 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Cut remaining 8 5/8" casing at the following depths: 1,035', 1,125', 1,152', 1,192', 1,242', 1,292', and 1,342'. Perforated 8 5/8" casing with 6 shots each location: 1,085', 1,130', 1,135', 1,137.5', 1,142', and 1,147'. Left an unknown amount of 8 5/8" casing in hole from 714' to an unknown depth.	8 5/8" 16"	None None	Unknown 20'	
<u>Cemented hole from 1,502' to surface as follows:</u>				
Cemented well from 1,502' to 935' with 165 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 935' to surface with 605 sacks of Expandable Cement. Cement did circulate at surface. Left 20' of 16" casing in hole from surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	1,135' – 1,142'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7"		
		casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of August, 2025Sworn to and subscribed before me this 22nd day of September 2025Matthew A. Yearsley
Matthew A. YearsleyDelbert L. Moore
Delbert Moore

Kerrri McCormick
Notary Public

My commission expires:

August 13, 2029Permit No. 47-103741Well No. 7337Latitude: 39° 31' 29.3" NLongitude: 80° 31' 39.5" W