

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

**AFFIDAVIT OF PLUGGING AND FILLING WELL**

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B W Peterson Operator Well No: 7429  
LOCATION: Elevation: 1,237.30' Quadrangle: Big Run, WV  
District: Grant County: Wetzel  
Latitude: 39.519828 Feet South of 39 Deg. 31 Min. 11.38 Sec.  
Longitude: -80.517886 Feet West of 80 Deg. 31 Min. 4.39 Sec.

Well Type: OIL  GAS

Company	West Virginia Land Resources 1 Bridge Street Monongah, WV 26554	Coal Operator or Owner	West Virginia Land Resources 1 Bridge Street Monongah, WV 26554
Agent	David Roddy	Coal Operator or Owner	
Permit Issued Date	8-1-25		

RECEIVED  
Office of Oil and Gas

## AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of October, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thickener w/ Green Dye & Gas Blocker	1,250'	819'	8 5/8" Casing - None	Unknown
Expanding Cement	819'	Surface	10 3/4" Casing - None	227'
			16" Conductor - None	14'

**Description of monument:** 77" of 7" casing with company name, well #, API #, and date completed. and that the work of plugging and filling  
said well was completed on the 29th day of October, 2025.

And further deponents saith not. *Matthew A. Yearsley*

Matthew A. Yearsley

Thomas Thrasher

Sworn and subscribe before me this 1<sup>st</sup> day of December, 2025



My commission expires: August 13, 2029

Jerry McCormick

Digital ~~Notary~~ PLATINUM  
McCoy  
Date: 2025.12.02 08:03:00  
05'00'

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

12/26/2025

## AFFIDAVIT OF PLUGGING AND FILLING WELL

**AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE**, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**JOHN DALE COEN**  
Lease or Property Owner  
666 S LINDEN AVE ALLIANCE, OH 44601  
Address

**WEST VIRGINIA LAND RESOURCES**  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN, WV 7.5'  
Well Location  
**GRANT**  
District  
**WETZEL**  
County  
7429  
Well No.  
**B W PETERSON**  
Farm  
**Stephen Mccoy** Digitally signed by Stephen Mccoy  
Date: 2025.12.02 08:02:44-05'00'

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy


## AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

**MATTHEW A. YEARSLEY** and **THOMAS THRASHER** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of October, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned hole with a 12 1/4" bit from surface to 261'. Reduced hole to 9 7/8" bit at 261'. Cleaned hole with a 9 7/8" bit from 261' to 999'. Cleaned out existing 10 3/4" casing from 442' to 669' with a 9 7/8" bit. Tagged existing 8 5/8" casing at 999'. Cleaned out 8 5/8" casing with a 6 1/4" bit from 999' to 1,250'. Cut 8 5/8" casing at 1,036'. Made a diligent effort to pull 8 5/8" casing from 999' to 1,036' by pulling 150% of string weight with no success. All attempts to remove remaining casing were unsuccessful. Cut 8 5/8" at 1,226', 1,176', 1,126', 1,076', 1,031', 1,026', 1,024.25', 1,022.50', 1,020.75', 1,019', 1,014', and 1,009'. Cleaned a 6 1/4" hole through the Pittsburg Coal Seam from 1,019' to 1,026'.		8 5/8" Casing 10 3/4" Casing 16" Conductor	None None None	Unknown 227' 14'
<b>Cemented the hole from 1,250' to surface as follows:</b> Cemented from 1,250' to 819' using 170 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 819' to surface using 435 sacks of Expanding Cement. Used a total of 605 sacks of cement. Cement did circulate at surface. Left 14' of 16" conductor in hole from surface to 14'.				
Coal Seams		Description of Monument		
Pittsburgh	1,019' – 1,026'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29<sup>th</sup> day of October, 2025



*Matthew A. Yearsley*  
Matthew A. Yearsley

*Thomas Thrasher*  
Thomas Thrasher

RECEIVED  
Office of Oil and Gas

DEC 16 2025

WV Department of  
Environmental Protection

Sworn to and subscribed before me this

51  
day of *December 2025*  
*Jerrim McCormick*  
Notary Public

My commission expires:

*August 13, 2029*

Permit No. 47-103-03746  
Well No. 7429  
Latitude: 39° 31' 11.38" N  
Longitude: 80° 31' 4.39" W

12/26/2025