

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7348

LOCATION: Elevation: 1247.25' Quadrangle: Big Run, WV  
District: Grant County: Wetzel  
Latitude: 39.525293 Feet South of 39 Deg. 31 Min. 31.05 Sec.  
Longitude: -80.52996 Feet West of 80 Deg. 31 Min. 47.86 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company	<u>West Virginia Land Resources</u>	Coal Operator	<u>West Virginia Land Resources</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>8-13-25</u>	or Owner	_____

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of August, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thermoplastic w/ Green Dye & Gas Blocker	1,312'	813'	8 5/8" Casing - 280'	Unknown
Expandable Cement	813'	Surface	16" Conductor - None	20'

RECEIVED  
Office of Oil and Gas  
OCT 27 2025

WV Department of  
Environmental Protection


Description of monument: 77" of 7" casing with company name, well #, API #, and date completed. and that the work of plugging and filling said well was completed on the 8th day of September, 2025.

And further deponents saith not. Matthew A. Yearsley

Delbert Moore

Sworn and subscribe before me this 14<sup>th</sup> day of October, 2025

My commission expires: August 13, 2029  
Stephen McCoy  
Notary Public  
Digitally signed by Stephen McCoy  
Date: 2025.10.15 08:35:52 -04'00'



Affidavit reviewed by the Office of Oil and Gas: McCoy Title: \_\_\_\_\_

10/31/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**WEST VIRGINIA LAND RESOURCES**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**DALLISON LUMBER INC**  
Lease or Property Owner  
**PO BOX 159 JACKSONBURG, WV 26377**  
Address

**WEST VIRGINIA LAND RESOURCES**  
Name of Well Operator  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Complete Address  
**Big Run, WV 7.5'**  
Well Location  
**GRANT**  
District  
**WETZEL**  
County  
**7348**  
Well No.  
**B. W. PETERSON**  
Farm  
**Stephen Mccoy**

Digitally signed by Stephen  
Mccoy  
Date: 2025.10.15 08:35:39 -04'00'

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

**MATTHEW A. YEARSLEY** and **DELBERT MOORE** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24<sup>th</sup> day of August, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 217'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 217' to the top of the 8 5/8" casing at 423'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 423' to 1,312'. Cleaned 6 1/4" hole through the Pittsburgh Coal Seam from 1,013' to 1,020'. Pulled 280' of 8 5/8" casing from 423' to 703'. Made a diligent effort to pull remaining 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Cut remaining 8 5/8" casing at the following depths: 1,220', 1,170', 1,120', 1,070', 1,030', 1,025', 1,020', 1,017.5', 1,015', 1,013', 1,008', 1,003', 963', and 913'. Left an unknown amount of 8 5/8" casing in hole from 703' to unknown.		8 5/8" Casing	280'	Unknown
Cemented hole from 1,312' to surface as follows: Cemented from 1,312' to 813' with 150 sacks Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 813' to surface with 625 sacks of Expanding Cement. Cement did circulate at surface. Left 20' of 16" casing in hole from surface to 20'.		16" Conductor	None	20'
Coal Seams		Description of Monument		
Pittsburgh	1,013' - 1,020'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8<sup>th</sup> day of September, 2025



Sworn to and subscribed before me this

14<sup>th</sup> day of October 2025

Matthew A. Yearsley  
Matthew A. Yearsley

Delbert L. Moore  
Delbert Moore

Kerria McCormick  
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03747  
Well No. 7348  
Latitude: 39° 31' 31.05" N  
Longitude: 80° 31' 47.86" W

RECEIVED  
Office of Oil and Gas  
OCT 27 2025  
WV Department of  
Environmental Protection

10/31/2025