



---

west virginia department of environmental protection

---

Office of Oil and Gas  
601 57<sup>th</sup> Street, S.E.  
Charleston, WV 25304  
(304) 926-0450  
fax: (304) 926-0452

Harold D. Ward, Cabinet Secretary  
[www.dep.wv.gov](http://www.dep.wv.gov)

Friday, January 30, 2026  
WELL WORK PERMIT  
Horizontal 6A / New Drill

EQT PRODUCTION COMPANY  
2200 ENERGY DRIVE

CANONSBURG , PA 15317

Re: Permit approval for Nextwave EFT 7H  
47-103-03805-00-00

This well work permit is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to any additional specific conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas Inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days of completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

Per 35 CSR 4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926- 0450.

H. Jason Harmon  
Acting Chief

Operator's Well Number: Nextwave EFT 7H  
Farm Name: RDFS LLC  
U.S. WELL NUMBER: 47-103-03805-00-00  
Horizontal 6A New Drill  
Date Issued: 1/3/2026

# PERMIT CONDITIONS

West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

## CONDITIONS

---

1. This proposed activity may require permit coverage from the United States Army Corps of Engineers (USACE). Through this permit, you are hereby being advised to consult with USACE regarding this proposed activity.
2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than one hundred (100) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.
3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the moisture content of the fill material shall be within limits as determined by the Standard Proctor Density test of the actual soils used in specific engineered fill, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort, to achieve 95 % compaction of the optimum density. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.
4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.
5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations*, 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.
6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.
7. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Also, 24 hours prior to the initiation of the completion process the operator shall notify the Chief or his designee.
8. During the completion process the operator shall monitor annular pressures and report any anomaly noticed to the chief or his designee immediately.
9. If any explosion or other accident causing loss of life or serious personal injury occurs in or about a well or well work on a well, the well operator or its contractor shall give notice, stating the particulars of the explosion or accident, to the oil and gas inspector and the Chief, within 24 hours of said accident.
10. During the casing and cementing process, in the event cement does not return to the surface, the oil and gas inspector shall be notified within 24 hours.
11. The operator shall provide to the Office of Oil and Gas the dates of each of the following within 30 days of their occurrence: completion of construction of the well pad, commencement of drilling, cessation of drilling, completion of any other permitted well work, and completion of the well. Such notice shall be provided by sending an email to DEPOOGNotify@wv.gov.

4710303805

WW-6B  
(04/15)API NO. 47- \_\_\_\_\_  
OPERATOR WELL NO. 7H \_\_\_\_\_  
Well Pad Name: Nextwave EFT \_\_\_\_\_

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
WELL WORK PERMIT APPLICATION

1) Well Operator:	EQT Production Company		306686	Wetzel	Church	Hundred	
			Operator ID	County	District	Quadrangle	
2) Operator's Well Number:	7H		Well Pad Name: Nextwave EFT				
3) Farm Name/Surface Owner:	RDFS LLC		Public Road Access: CR 250/2				
4) Elevation, current ground:	1,443'		Elevation, proposed post-construction: 1,443'				
5) Well Type	(a) Gas <input checked="" type="checkbox"/>	Oil _____	Underground Storage _____				
	Other _____						
	(b) If Gas	Shallow <input checked="" type="checkbox"/>	Deep _____				
		Horizontal <input checked="" type="checkbox"/>					
6) Existing Pad: Yes or No	No						
7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Pressure(s):	Marcellus, 7,820', 52', 2,620 PSI		Estimated Pressure _____				
8) Proposed Total Vertical Depth:	7,820'						
9) Formation at Total Vertical Depth:	Marcellus						
10) Proposed Total Measured Depth:	8,198'						
11) Proposed Horizontal Leg Length:	1,043'						
12) Approximate Fresh Water Strata Depths:	377', 457', 482'						
13) Method to Determine Fresh Water Depths:	Offset Wells - 103-00290, 103-30382, 103-30006, 103-30696						
14) Approximate Saltwater Depths:	N/A						
15) Approximate Coal Seam Depths:	839'-843', 1,078'-1,082', 1,184'-1,191'						
16) Approximate Depth to Possible Void (coal mine, karst, other):	N/A						
17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine?	Yes _____		No <input checked="" type="checkbox"/>				
(a) If Yes, provide Mine Info:	Name: _____						
	Depth: _____						
	Seam: _____						
	Owner: _____						

WW-6B  
(04/15)

1710303005  
API NO. 47-  
OPERATOR WELL NO. 7H  
Well Pad Name: Nextwave EFT

18)

CASING AND TUBING PROGRAM

<u>TYPE</u>	<u>Size (in)</u>	<u>New or Used</u>	<u>Grade</u>	<u>Weight per ft. (lb/ft)</u>	<u>FOOTAGE: For Drilling (ft)</u>	<u>INTERVALS: Left in Well (ft)</u>	<u>CEMENT: Fill-up (Cu. Ft.)/CTS</u>
Conductor	26	New	A252	85.6	53	53	50 ft^3 / CTS
Fresh Water	13 3/8	New	J-55	54.5	1241	1241	1125 ft^3 / CTS
Coal							
Intermediate	9 5/8	New	J-55	36	2866	2866	1100 ft^3 / CTS
Production	5 1/2	New	P-110	20	8198	8198	500' above intermediate casing
Tubing							
Liners							

<u>TYPE</u>	<u>Size (in)</u>	<u>Wellbore Diameter (in)</u>	<u>Wall Thickness (in)</u>	<u>Burst Pressure (psi)</u>	<u>Anticipated Max. Internal Pressure (psi)</u>	<u>Cement Type</u>	<u>Cement Yield (cu. ft./k)</u>
Conductor	26	30	0.312	1000	18	Class A/L	1.04 - 1.20
Fresh Water	13 3/8	17 1/2	0.380	2730	2184	Class A/L	1.04 - 1.20
Coal							
Intermediate	9 5/8	12 3/8 - 12 1/4	0.352	3520	2816	Class A/L	1.04 - 1.20
Production	5 1/2	8 3/4 - 8 1/2	0.400	14360	11488	Class A/H/L	1.04 - 2.10
Tubing							
Liners							

PACKERS

Kind:				
Sizes:				
Depths Set:				

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Drill and complete a new horizontal well in the Marcellus Formation. Drill the vertical, kick off and drill curve. Drill the lateral in the Marcellus. Cement casing.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.1%) of chemicals (including 15% Hydrochloric acid, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressure is expected to be approximately 10,000 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 350,000 gallons of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 200,000-600,000 pounds of proppant per stage.

21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): 42.82 acres

22) Area to be disturbed for well pad only, less access road (acres): 13.26 acres

23) Describe centralizer placement for each casing string:

- Surface: Bow spring centralizers – One centralizer at the shoe and one spaced every 500'.
- Intermediate: Bow spring centralizers – One centralizer at the shoe and one spaced every 500'.
- Production: One solid body centralizer spaced every other joint from production casing shoe to landing point. One solid body centralizer spaced every joint from landing point to planned top of cement.

24) Describe all cement additives associated with each cement type:

Conductor: No additives

Surface: Calcium Chloride. Used to speed the setting of cement slurries

Intermediate: Calcium Chloride. Used to speed the setting of cement slurries.

Production: Calcium Carbonate, Fluid Loss, Extender, Dispersant, Viscosifier, Defoamer, POZ, Bonding Agent, Retarder, Anti-Settling/Suspension Agent

25) Proposed borehole conditioning procedures:


Surface: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface.

Intermediate: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface.

Production: Perform a cleanup cycle by pumping 3-8 bottoms up or until the shakers are clean. Check volume of cuttings coming across the shakers every 15 minutes.

\*Note: Attach additional sheets as needed.

4710303805

EQT Production	Wellbore Diagram
Well: Nextwave EFT 7H	County: Wetzel
Pad: Nextwave EFT	State: West Virginia
Elevation: 1443' GL 1456' KB	
	 <p>Conductor @ 53' 26", 85.6#, A252, cement to surface w/ Class A/L</p> <p>Surface @ 1,241' 13-3/8", 54.5#, J-55, cement to surface w/ Class A/L</p> <p>Intermediate @ 2,866' 9-5/8", 36#, J-55, cement to surface w/ Class A/H/L</p> <p>Production @ 8,198' MD / 7,820' TVD 5-1/2", 20#, P-110, cement to 500' inside 9-5/8" w/ Class A/H/L</p> <p>Formation: Marcellus</p>
	NOT TO SCALE

01/30/2026

4710303805

EQT Production  
Hydraulic Fracturing Monitoring Plan

Pad ID: Nextwave EFT

County: Wetzel

October 2025

Page 1 of 2

01/30/2026

## Purpose

The purpose of this pad-specific Hydraulic Fracturing Monitoring Plan is to identify and notify conventional well operators near EQT hydraulic fracturing in Wetzel County, WV prior to hydraulic fracturing at the following EQT wells on the Nextwave EFT Pad.

Due to the requirements under 35CSR8 5.11, the permittee is required to review the area surrounding the proposed well pad so as to identify and evaluate potential conduits for unintended fracture propagation.

A report is required to be submitted along with a well work permit application.

The plan is being implemented as an additional safety measure to be utilized in conjunction with existing best management practices and emergency action plans for the site. These additional measures include coordination with well operators of the timing and location of the hydraulic fracturing, establishment of measures well operators should implement, and assurance that the OOG is notified of the timeline, as well as any issues that may arise during fracturing.

### 1. Communications with Well Operators

EQT, using available data (WV Geological Survey, WVDEP website, and IHS data service), has identified all known wells and well operators within 500 feet of this pad and the lateral sections that are known or could reasonably be expected to be within range of the fracture propagation. A map showing these wells along with a list of the wells and operators is included in **Attachment A**.

EQT will notify these operators of the hydraulic fracturing schedule for these wells, and coordinate with them throughout the fracturing process.


EQT will recommend to these operators at a minimum to:

1. Inspect their surface equipment prior to fracturing to establish integrity and establish pre-frac well conditions
2. Observe wells closely during and after fracturing and monitor for abnormal increases in water, gas or pressure
3. Inspect or install master valves or other necessary equipment for wellhead integrity capable of a pressure recommended by EQT
4. Notify the OOG and EQT if any changes in water, gas production, pressure, or other anomalies are identified

### 2. Reporting

EQT will provide information relating to the hydraulic fracturing schedule, communication with other operators, and ongoing monitoring of the work upon request of OOG or immediately in the event of any noted abnormalities.

4710303805



RECEIVED  
Office of Oil and Gas

DEC 20 2025

WV Department of  
Environmental Protection

Legend	
●	Nextwave 7H Tophole
—	Nextwave Lateral
----	Lateral Buffer 500'

SHEET: 1 OF 1		AREA OF REVIEW (AOR) PLAT		PREPARED FOR: <b>EQT</b>	PREPARED BY: <b>KEystone</b> A CURE COMPANY Foster Place 10 680 Anderson Drive, Suite 400 Pittsburgh, PA 15220 412-279-2100 412-279-2105 Fax	No.	Revisions	Date
SCALE: 1 in = 200 ft	Well (Farm) Name: Nextwave 7H	DATE: 10/9/2025	Well #: 7H	DEP ID#:				
Wetzel County, WV	0 100 200	Feet						

01/30/2026

4710303805



E Q T P R O D U C T I O N C O M P A N Y  
2200 Energy Drive | Canonsburg, PA 15317

November 20, 2025

Mr. Taylor Brewer  
West Virginia Department of Environmental Protection  
Office of Oil and Gas  
601 57th Street SE  
Charleston, WV 25304

Re: Class L Cement Variance Request  
Nextwave EFT 7H  
Church District, Wetzel County

Dear Mr. Brewer,

EQT Production Company (EQT) has been notified by our cement providers that they will no longer be providing Class A cement. As a result of this, EQT is requesting the option to utilize Class L cement, if necessary, in place of Class A cement for its cement jobs.

The variance request from Legislative Rule 35CSR8, Section 9.2.h.8, related to the use of Class L Cement, was approved by the Office of Oil and Gas on September 13, 2022. A copy of the variance is included with this request.

If you have any questions, please do not hesitate to contact me at 412-913-4005

Sincerely,

*Kristen Brooks*

Kristen Brooks  
Permitting

RECEIVED  
Office of Oil and Gas  
DEC 29 2025  
WV Department of  
Environmental Protection

Enc.

01/30/2026



4710303805

---

west virginia department of environmental protection

---

Office of Oil and Gas  
601 57<sup>th</sup> Street, SE  
Charleston, WV 25304  
Phone (304) 926-0450

Harold D. Ward, Cabinet Secretary  
dep.wv.gov

**BEFORE THE OFFICE OF OIL AND GAS  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
STATE OF WEST VIRGINIA**

**IN THE MATTER OF A VARIANCE FROM )  
LEGISLATIVE RULE 35CSR4 ) ORDER NO. 2022-14  
SECTION 11.5 AND LEGISLATIVE RULE )  
35CSR8 SECTION 9.2.h.8., )  
RELATING TO THE CEMENTING )  
OF OIL AND GAS WELLS )**

**REPORT OF THE OFFICE**

In response to industry requests, the West Virginia Department of Environmental Protection, Office of Oil and Gas has reviewed the proposed use of American Petroleum Institute (API) Class L cement to be used in place of API Class A cement for well construction.

**FINDINGS OF FACT**

1. On July 14, 2022, Northeast Natural Energy (NNE) submitted a variance request from Legislative Rule 35CSR8 Section 9.2.h.8., for the use of API Class L cement in place of API Class A cement, relating to the construction of horizontal wells.
2. Laboratory analysis submitted by NNE on July 14, 2022, indicates API Class L cement is comparable to API Class A cement and thereby satisfies the requirements of the West Virginia Code.
3. Contemporaneously, the Chief of the Office of Oil and Gas also chose to consider a variance to Legislative Rule 35CSR4 Section 11.5., for the use of API Class L cement in place of API Class A cement, relating to the construction of vertical wells.

Promoting a healthy environment.

01/30/2026

4. On August 18, 2022, the Office of Oil and Gas provided public notice of acceptance of public comments on the variance consideration. During the 20-day public comment period, no comments were received.

## CONCLUSIONS OF LAW

Pursuant to Article 6 and Article 6A, Chapter 22 of the Code of West Virginia, the Office of Oil and Gas has jurisdiction over the subject matter, and the persons interested therein, and jurisdiction to promulgate the hereinafter prescribed Order.

Pursuant to Legislative Rule 35CSR4, Section 18 and Legislative Rule 35CSR8, Section 14, the Chief of the Office of Oil and Gas may grant a variance from any requirement of these rules.

## ORDER

It is ordered that the Class L cement product approved and monogrammed by API is approved for use in place of API Class A cement for well construction subject to the provisions of Legislative Rule 35CSR4 and Legislative Rule 35CSR8.

RECEIVED  
Office of Oil and Gas


Dated this, the 13th day of September, 2022.

DEC 22 2022

WV Department of  
Environmental Protection

IN THE NAME OF THE STATE OF WEST VIRGINIA

OFFICE OF OIL AND GAS  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OF THE STATE OF WEST VIRGINIA

  
James Martin, Chief  
Office of Oil and Gas

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

## FLUIDS/ CUTTINGS DISPOSAL &amp; RECLAMATION PLAN

Operator Name EQT Production Company OP Code 306686Watershed (HUC 10) West Virginia Fork Fish Creek Quadrangle HundredDo you anticipate using more than 5,000 bbls of water to complete the proposed well work? Yes  No Will a pit be used? Yes  No If so, please describe anticipated pit waste: N/AWill a synthetic liner be used in the pit? Yes  No  If so, what ml.? N/A

## Proposed Disposal Method For Treated Pit Wastes:

## Land Application

 Underground Injection ( UIC Permit Number 0014, 8462, 4037) Reuse (at API Number Various) Off Site Disposal (Supply form WW-9 for disposal location)

Other (Explain)

Will closed loop system be used? If so, describe: Yes, The closed loop system will remove drill cuttings from the drilling fluid. The drill cuttings are then prepared for transportation to an off-site disposal facility.Drilling medium anticipated for this well (vertical and horizontal)? Air, freshwater, oil based, etc. See Attached RECEIVED  
Office of Oil and Gas  
01/30/2026-If oil based, what type? Synthetic, petroleum, etc. Synthetic MudAdditives to be used in drilling medium? See Attached 01/30/2026Drill cuttings disposal method? Leave in pit, landfill, removed offsite, etc. Landfill West Virginia  
Department of  
Environmental Protection-If left in pit and plan to solidify what medium will be used? (cement, lime, sawdust) N/A-Landfill or offsite name/permit number? See Attached List

Permittee shall provide written notice to the Office of Oil and Gas of any load of drill cuttings or associated waste rejected at any West Virginia solid waste facility. The notice shall be provided within 24 hours of rejection and the permittee shall also disclose where it was properly disposed.

I certify that I understand and agree to the terms and conditions of the GENERAL WATER POLLUTION PERMIT issued on August 1, 2005, by the Office of Oil and Gas of the West Virginia Department of Environmental Protection. I understand that the provisions of the permit are enforceable by law. Violations of any term or condition of the general permit and/or other applicable law or regulation can lead to enforcement action.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments thereto and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment.

Company Official Signature Kristen BrooksCompany Official (Typed Name) Branden WeimerCompany Official Title Regional Permitting - ManagerSubscribed and sworn before me this 20th day of November, 2025Kristen Brooks  
My commission expires Feb. 17, 2029

Notary Public

Commonwealth of Pennsylvania - Notary Seal  
Kristen Brooks, Notary Public  
Fayette County  
My commission expires February 17, 2029  
Commission number 1285524  
Member, Pennsylvania Association of Notaries  
01/30/2026

**EQT Production Company**

Proposed Revegetation Treatment: Acres Disturbed \_\_\_\_\_ Prevegetation pH \_\_\_\_\_

Lime 3 Tons/acre or to correct to pH 6.5Fertilizer type Granular 10-20-20Fertilizer amount 500 lbs/acreMulch 2 Tons/acre**Seed Mixtures****Temporary****Permanent**

Seed Type	lbs/acre
KY-31	40
Alsike Clover	5
Annual Rye	15

Seed Type	lbs/acre
Orchard Grass	15
Alsike Clover	5

## Attach:

Maps(s) of road, location, pit and proposed area for land application (unless engineered plans including this info have been provided). If water from the pit will be land applied, include dimensions (L x W x D) of the pit, and dimensions (L x W), and area in acreage, of the land application area

Photocopied section of involved 7.5' topographic sheet.

**Stephen Mccoy** Digitally signed by Stephen Mccoy  
Date: 2025.10.23 08:59:56 -04'00'

Plan Approved by: \_\_\_\_\_

Comments: Properly reclaim, seed and mulch all disturbed areas to DEP standards.

Title: \_\_\_\_\_

Date: \_\_\_\_\_

Field Reviewed? (      ) Yes (      ) No

4710303805

WW-9 Attachment

Drilling medium anticipated for this well (vertical and horizontal)? Air, freshwater, oil based, etc.

- Air is used to drill the top-hole sections of the wellbore (surface, intermediate, and pilot). Water based mud may be necessary depending on hole conditions to stabilize and drill the intermediate section. The pilot hole, curve, and lateral sections will be drilled with either air, water based mud, or synthetic mud.

Additives to be used in drilling medium?

- Air - biodegradable oil lubricant, detergent, defoaming, water.
- Water based mud – Barite, viscosifer, alkalinity control, lime, filtration control, deflocculates, biodegradable oil lubricant, defoaming, walnut shell, salt, x-cide, carbonates.
- Synthetic mud – synthetic base oil, emulsifier, salt, lime, viscosifer, alkalinity control, filtration control, deflocculates, biodegradable oil lubricant, defoaming, carbonates.

01/30/2026  
01/30/2026  
01/30/2026  
01/30/2026



## **EMERGENCY RESPONSE PLAN (ERP)**

## (SITE SAFETY AND ENVIRONMENTAL PLAN)

EQT Nextwave EFT Well Pad

## Church District Wetzel County, WV

Prepared By: Scott M. Held, CSP, Senior EHS Coordinator

Approved By: Scott M. Held, CSP, Senior EHS Coordinator

Created Date: 2-Jul-24

## **RECORD OF REVISION AND CHANGES**

Plan Administrator:  
Scott M. Held, CSP  
Senior EHS Coordinator

Approver:  
Michael Lauderbaugh  
Vice President of EHS

Stephen  
McCoy

Digitally signed by  
Stephen McCoy  
Date: 2025.10.22  
19:35:30 -04'00'

1030473085


Topo Quad: Hundred  
County: Wetzel  
District: Church

RECEIVED  
Office of Oil and Gas  
REC'D 20 025  
WV Department of  
Environmental Protection

Scale: 1"=1000'  
Date: March 28, 2024  
Project No: \_\_\_\_\_

# NEXTWAVE WELL PAD

Water



**KEYSTONE**  
CONSULTANTS, LLC

Keystone Consultants, LLC  
32 East Main Street  
Carnegie, PA 15106  
412 278-2100

Prepared For:  
EQT Production Company  
400 Woodcliff Drive  
Canonsburg, PA 15317

**EQT**  
EQT PRODUCTION COMPANY  
400 WOODCLIFF DRIVE  
CANONSBURG, PA 15317

01/30/2026

Nextwave EFT 7H  
Nextwave EFT  
EQT Production Company

LATITUDE 39° 42' 30" TH: 8,865'

LATITUDE 39° 42' 30" BH: 9,225'

NORTH

**NOTES ON SURVEY**

1. COORDINATES SYSTEM IS UTM, NAD 83 DATUM, ZONE 17, U.S. FOOT AND WELL COORDINATES ESTABLISHED USING SURVEY GRADE GPS.
2. SURFACE AND ROYALTY OWNER INFORMATION AND THEIR BOUNDARIES SHOWN HEREON WERE PLOTTED FROM DEEDS AND/OR TAX PARCEL MAPS PROVIDED BY CLIENT AND FIELD LOCATIONS.
3. THIS PLAT DOES NOT REPRESENT A BOUNDARY SURVEY OF THE PARCELS SHOWN HEREON.
4. NO DWELLINGS AND BUILDINGS WITHIN 625 FEET OF PROPOSED CENTER OF PAD.
5. NO WATER WELLS OR DEVELOPED SPRINGS WITHIN 250 FEET OF PROPOSED WELL.
6. NO PERENNIAL STREAMS, LAKES, PONDS, RESERVOIRS OR WETLANDS WITHIN 100 FEET OF THE LIMITS OF DISTURBANCE.
7. NO NATURALLY PRODUCING TROUT STREAM WITHIN 300 FEET OF LIMITS OF DISTURBANCE.

**LEGEND**

- Active Well Location
- Drilled Well Location
- Surface Tract Identification
- Proposed Gas Well
- Located Corner, as noted
- Surface Tract Lines (Surveyed)
- Surface Tract Lines (Tax Map)
- Reference Line
- Lease Boundary
- Creek or Drain
- WV County Route
- WV State Route

(—) Denotes Location of Well on United States Topographic Maps

**KEYSTONE**  
CONSULTANTS, LLC

I, the undersigned, hereby certify that this plat is correct to the best of my knowledge and belief and shows all the information required by law and the regulations issued and prescribed by the Department of Environmental Protection.

*T. Rowe*  
L. L. S. 2394



FILE NO:  
DRAWING NO:  
SCALE: 1" = 2000'  
MINIMUM DEGREE OF ACCURACY:  
1:2500  
PROVEN SOURCE OF ELEVATION:  
NGS CORS Station

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS DIVISION  
MONTANI SEMPER LIBERTI

DATE: September, 26 20 25  
OPERATORS WELL NO: Nextwave EFT 7H  
API WELL NO  
47 - 103 03805  
STATE COUNTY PERMIT

WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
(IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW  
LOCATION ELEVATION: 1443' WATERSHED: West Virginia Fork Fish Creek QUADRANGLE: Hundred  
DISTRICT: Church COUNTY: Wetzel  
SURFACE OWNER: RDFS LLC ACREAGE: 58 ±  
ROYALTY OWNER: Three Rivers Royalty II, LLC, et al. LEASE NO: 119573002 ACREAGE: 95.95 ±  
PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY)  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus ESTIMATED DEPTH: 7,820'

WELL OPERATOR: EQT Production Company


DESIGNATED AGENT: Joseph C Mallow

ADDRESS: 2200 Energy Drive

ADDRESS: 427 Midstate Drive


Canonsburg, PA 15317

Clarksburg, WV 26301



Nextwave EFT 7H  
Nextwave EFT  
EQT Production Company

Tract ID.	Tax Map No.	Parcel No.	County	District	Surface Tract Owner	Acres
1	7	5.0	Wetzel	Church	RDFS LLC	58.00
Lease	Owner				Acres	
119573002	Three Rivers Royalty II, LLC, et al.				95.95 ac	



Well References

Ref Stake  
N08°23'18"W  
257  
Ref Stake —S15°56'09"W  
411

1" = 1000' NEXTWAVE EFT 7H


Notes:

NEXTWAVE EFT 7H coordinates are  
NAD 27 N: 431,452.781 E: 1,733,083.932  
NAD 27 Lat: 39.680718 Long: -80.448364  
NAD 83 UTM N: 4,392,475.655 E: 547,323.156

NEXTWAVE EFT 7H Bottom Hole coordinates are  
NAD 27 N: 431,681.725 E: 1,732,728.293  
NAD 27 Lat: 39.681336 Long: -80.449636  
NAD 83 UTM N: 4,392,543.598 E: 547,213.644

West Virginia Coordinates system of 1927 (North Zone)  
based upon Differential GPS Measurements  
Plat orientation, Corner and well ties are based upon  
the grid north meridian  
Well location references are based upon the grid north  
meridian.  
UTM coordinates are NAD83, Zone 17, Meters.

NEXTWAVE EFT PAD



**KEystone**  
CONSULTANTS, LLC

I, the undersigned, hereby certify that this plat is correct to the best of my knowledge and belief and shows all the information required by law and the regulations issued and prescribed by the Department of Environmental Protection.

*L. L. S. 2394*  
L. L. S. 2394



FILE NO: \_\_\_\_\_  
DRAWING NO: \_\_\_\_\_  
SCALE: 1" = 1000'  
MINIMUM DEGREE OF ACCURACY:  
1:2500  
PROVEN SOURCE OF ELEVATION:  
NGS CORS Station

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS DIVISION  
MONTANI SEMPER LIBERI

DATE: September, 26 20 25  
OPERATORS WELL NO: Nextwave EFT 7H  
API WELL NO  
47 - 103 - 03805  
STATE COUNTY PERMIT

WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
(IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW  
LOCATION ELEVATION: 1443' WATERSHED: West Virginia Fork Fish Creek QUADRANGLE: Hundred  
DISTRICT: Church COUNTY: Wetzel  
SURFACE OWNER: RDFS LLC ACREAGE: 58 ±  
ROYALTY OWNER: Three Rivers Royalty II, LLC, et al. LEASE NO: 119573002 ACREAGE: 95.95 ±  
PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY)  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus ESTIMATED DEPTH: 7,820'  
WELL OPERATOR: EQT Production Company DESIGNATED AGENT: Joseph C Mallow  
ADDRESS: 2200 Energy Drive ADDRESS: 427 Midstate Drive  
Canonsburg, PA 15317 Clarksburg, WV 26301

01/30/2026

WW-6A1  
(5/13)Operator's Well No. Nextwave EFT 7H

**INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE**  
**Chapter 22, Article 6A, Section 5(a)(5)**  
**IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)**

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that –

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
-------------------------	-----------------------	-----------------------	---------	-----------

See Attached

RECEIVED  
 Office of Oil and Gas  
 DEC 29 2013  
 WV Department of  
 Environmental Protection

**Acknowledgement of Possible Permitting/Approval**  
**In Addition to the Office of Oil and Gas**

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

Well Operator: EQT Production Company

By: Branden Weimer

Its: Regional Manager - Permitting

Lease No.	Grantor, Lessor, etc.	Acres	Grantee, Lessee, etc.	Royalty	Book/Page
<u>119573002</u>	<u>Three Rivers Royalty II, LLC, et al.</u> Three Rivers Royalty II, LLC	95.95 ac	EQT Production Company	"at least 1/8th per WV Code 22-6-8"	OG 208A/335

47120200300

4710303805



E Q T P R O D U C T I O N C O M P A N Y  
2200 Energy Drive | Canonsburg, PA 15317

November 20, 2025

Mr. Taylor Brewer  
West Virginia Department of Environmental Protection  
Office of Oil and Gas  
601 57th Street SE  
Charleston, WV 25304

RECEIVED  
Office of Oil and Gas  
DEC 29 2015  
WV Department of  
Environmental Protection

Re: Nextwave EFT 7H  
Church District, Wetzel County, WV

Dear Mr. Brewer,

EQT Production Company is applying for a well work permit for the well referenced above. Upon information and belief, the Operator's lease and/or other real property rights permit it to conduct drilling operations for the subject well in the location shown on the plat, including under any public roads that the well lateral crosses.

Sincerely,

A handwritten signature in black ink, appearing to read "Branden Weimer".

Branden Weimer  
Regional Manager - Permitting

01/30/2026

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
NOTICE CERTIFICATIONDate of Notice Certification: 12/18/2025

API No. 47- \_\_\_\_\_

Operator's Well No. 7HWell Pad Name: Nextwave EFT**Notice has been given:**

Pursuant to the provisions in West Virginia Code § 22-6A, the Operator has provided the required parties with the Notice Forms listed below for the tract of land as follows:

State: West Virginia  
County: Wetzel  
District: Church  
Quadrangle: Hundred  
Watershed: West Virginia Fork Fish Creek

UTM NAD 83      Easting: 547323.156  
Northing: 4392475.655  
Public Road Access: CR 250/2  
Generally used farm name: RDFS LLC

Pursuant to West Virginia Code § 22-6A-7(b), every permit application filed under this section shall be on a form as may be prescribed by the secretary, shall be verified and shall contain the following information: (i) A certification from the operator that (i) it has provided the owners of the surface described in subdivisions (1), (2) and (4), subsection (b), section ten of this article, the information required by subsections (b) and (c), section sixteen of this article; (ii) that the requirement was deemed satisfied as a result of giving the surface owner notice of entry to survey pursuant to subsection (a), section ten of this article six-a; or (iii) the notice requirements of subsection (b), section sixteen of this article were waived in writing by the surface owner; and Pursuant to West Virginia Code § 22-6A-11(b), the applicant shall tender proof of and certify to the secretary that the notice requirements of section ten of this article have been completed by the applicant.

Pursuant to West Virginia Code § 22-6A, the Operator has attached proof to this Notice Certification that the Operator has properly served the required parties with the following:

\*PLEASE CHECK ALL THAT APPLY

1. NOTICE OF SEISMIC ACTIVITY or  NOTICE NOT REQUIRED BECAUSE NO SEISMIC ACTIVITY WAS CONDUCTED

2. NOTICE OF ENTRY FOR PLAT SURVEY or  NO PLAT SURVEY WAS CONDUCTED

3. NOTICE OF INTENT TO DRILL or  NOTICE NOT REQUIRED BECAUSE NOTICE OF ENTRY FOR PLAT SURVEY WAS CONDUCTED or  
 WRITTEN WAIVER BY SURFACE OWNER (PLEASE ATTACH)

4. NOTICE OF PLANNED OPERATION

5. PUBLIC NOTICE

6. NOTICE OF APPLICATION

**OOG OFFICE USE ONLY**

RECEIVED/NOT REQUIRED

RECEIVED

RECEIVED/NOT REQUIRED

RECEIVED

RECEIVED

RECEIVED

**Required Attachments:**

The Operator shall attach to this Notice Certification Form all Notice Forms and Certifications of Notice that have been provided to the required parties and/or any associated written waivers. For the Public Notice, the operator shall attach a copy of the Class II Legal Advertisement with publication date verification or the associated Affidavit of Publication. The attached Notice Forms and Certifications of Notice shall serve as proof that the required parties have been noticed as required under West Virginia Code § 22-6A. Pursuant to West Virginia Code § 22-6A-11(b), the Certification of Notice to the person may be made by affidavit of personal service, the return receipt card or other postal receipt for certified mailing.

**Certification of Notice is hereby given:**

THEREFORE, I Branden Weimer, have read and understand the notice requirements within West Virginia Code § 22-6A. I certify that as required under West Virginia Code § 22-6A, I have served the attached copies of the Notice Forms, identified above, to the required parties through personal service, by registered mail or by any method of delivery that requires a receipt or signature confirmation. I certify under penalty of law that I have personally examined and am familiar with the information submitted in this Notice Certification and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.


Well Operator: EQT Production Company  
By: Branden Weimer   
Its: Regional Manager - Permitting  
Telephone: 844-378-5263

Address: 2200 Energy Drive  
Canonsburg, PA 15317

---

Facsimile:

Email: branden.weimer@eqt.com



Subscribed and sworn before me this 18th day of December, 2022

Kristen Brooks Notary Public  
My Commission Expires Feb 17 2029

## **Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
NOTICE OF APPLICATION

**Notice Time Requirement:** notice shall be provided no later than the **filing date of permit application**.

**Date of Notice:** 12/16/2025 **Date Permit Application Filed:** 12/19/2025

**Notice of:**

PERMIT FOR ANY WELL WORK       CERTIFICATE OF APPROVAL FOR THE CONSTRUCTION OF AN IMPOUNDMENT OR PIT

**Delivery method pursuant to West Virginia Code § 22-6A-10(b)**

PERSONAL SERVICE       REGISTERED MAIL       METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to W. Va. Code § 22-6A-10(b) no later than the filing date of the application, the applicant for a permit for any well work or for a certificate of approval for the construction of an impoundment or pit as required by this article shall deliver, by personal service or by registered mail or by any method of delivery that requires a receipt or signature confirmation, copies of the application, the erosion and sediment control plan required by section seven of this article, and the well plat to each of the following persons: (1) The owners of record of the surface of the tract on which the well is or is proposed to be located; (2) The owners of record of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for roads or other land disturbance as described in the erosion and sediment control plan submitted pursuant to subsection (c), section seven of this article; (3) The coal owner, operator or lessee, in the event the tract of land on which the well proposed to be drilled is located [sic] is known to be underlain by one or more coal seams; (4) The owners of record of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for the placement, construction, enlargement, alteration, repair, removal or abandonment of any impoundment or pit as described in section nine of this article; (5) Any surface owner or water purveyor who is known to the applicant to have a water well, spring or water supply source located within one thousand five hundred feet of the center of the well pad which is used to provide water for consumption by humans or domestic animals; and (6) The operator of any natural gas storage field within which the proposed well work activity is to take place. (c)(1) If more than three tenants in common or other co-owners of interests described in subsection (b) of this section hold interests in the lands, the applicant may serve the documents required upon the person described in the records of the sheriff required to be maintained pursuant to section eight, article one, chapter eleven-a of this code. (2) Notwithstanding any provision of this article to the contrary, notice to a lien holder is not notice to a landowner, unless the lien holder is the landowner. W. Va. Code R. § 35-8-5.7.a requires, in part, that the operator shall also provide the Well Site Safety Plan ("WSSP") to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

Application Notice  WSSP Notice  E&S Plan Notice  Well Plat Notice is hereby provided to:

 SURFACE OWNER(s)Name: See Attached List

Address: \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_

 SURFACE OWNER(s) (Road and/or Other Disturbance)Name: See Attached List

Address: \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_

 SURFACE OWNER(s) (Impoundments or Pits)

Name: \_\_\_\_\_

Address: \_\_\_\_\_

 COAL OWNER OR LESSEEName: See Attached List

Address: \_\_\_\_\_

 COAL OPERATOR

Name: \_\_\_\_\_

Address: \_\_\_\_\_

 SURFACE OWNER OF WATER WELL AND/OR WATER PURVEYOR(s)

Name: \_\_\_\_\_

Address: \_\_\_\_\_

 OPERATOR OF ANY NATURAL GAS STORAGE FIELD

Name: \_\_\_\_\_

Address: \_\_\_\_\_

\*Please attach additional forms if necessary

**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-10(b), notice is hereby given that the undersigned well operator has applied for a permit for well work or for a certificate of approval for the construction of an impoundment or pit.

**This Notice Shall Include:**

Pursuant to W. Va. Code § 22-6A-10(b), this notice shall include: (1) copies of the application; (2) the erosion and sediment control plan required by section seven of this article; and (3) the well plat.

Pursuant to W. Va. Code § 22-6A-10(f), this notice shall include: (1) a statement of the time limits for filing written comments; (2) who may file written comments; (3) the name and address of the secretary for the purpose of filing the comments and obtaining additional information; and (4) a statement that the persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

Pursuant to W. Va. Code R. § 35-8-5.7.a, the operator shall provide the Well Site Safety Plan to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

Pursuant to W. Va. Code R. § 35-8-15.2.c, this notice shall: (1) contain a statement of the surface owner's and water purveyor's right to request sampling and analysis; (2) advise the surface owner and water purveyor of the rebuttable presumption for contamination or deprivation of a fresh water source or supply; advise the surface owner and water purveyor that refusal to allow the operator to conduct a pre-drilling water well test constitutes a method to rebut the presumption of liability; (3) advise the surface owner and water purveyor of his or her independent right to sample and analyze any water supply at his or her own expense; advise the surface owner and water purveyor whether or not the operator will utilize an independent laboratory to analyze any sample; and (4) advise the surface owner and or water purveyor that he or she can obtain from the Chief a list of water testing laboratories in the subject area capable of and qualified to test water supplies in accordance with standard acceptable methods.

Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/oil-and-gas/pages/default.aspx](http://www.dep.wv.gov/oil-and-gas/pages/default.aspx).

**Well Location Restrictions**

Pursuant to W. Va. Code § 22-6A-12, Wells may not be drilled within two hundred fifty feet measured horizontally from any existing water well or developed spring used for human or domestic animal consumption. The center of well pads may not be located within six hundred twenty-five feet of an occupied dwelling structure, or a building two thousand five hundred square feet or larger used to house or shelter dairy cattle or poultry husbandry. This limitation is applicable to those wells, developed springs, dwellings or agricultural buildings that existed on the date a notice to the surface owner of planned entry for surveying or staking as provided in section ten of this article or a notice of intent to drill a horizontal well as provided in subsection (b), section sixteen of this article was provided, whichever occurs first, and to any dwelling under construction prior to that date. This limitation may be waived by written consent of the surface owner transmitted to the department and recorded in the real property records maintained by the clerk of the county commission for the county in which such property is located. Furthermore, the well operator may be granted a variance by the secretary from these distance restrictions upon submission of a plan which identifies the sufficient measures, facilities or practices to be employed during well site construction, drilling and operations. The variance, if granted, shall include terms and conditions the department requires to ensure the safety and protection of affected persons and property. The terms and conditions may include insurance, bonding and indemnification, as well as technical requirements. (b) No well pad may be prepared or well drilled within one hundred feet measured horizontally from any perennial stream, natural or artificial lake, pond or reservoir, or a wetland, or within three hundred feet of a naturally reproducing trout stream. No well pad may be located within one thousand feet of a surface or ground water intake of a public water supply. The distance from the public water supply as identified by the department shall be measured as follows: (1) For a surface water intake on a lake or reservoir, the distance shall be measured from the boundary of the lake or reservoir. (2) For a surface water intake on a flowing stream, the distance shall be measured from a semicircular radius extending upstream of the surface water intake. (3) For a groundwater source, the distance shall be measured from the wellhead or spring. The department may, in its discretion, waive these distance restrictions upon submission of a plan identifying sufficient measures, facilities or practices to be employed during well site construction, drilling and operations to protect the waters of the state. A waiver, if granted, shall impose any permit conditions as the secretary considers necessary. (c) Notwithstanding the foregoing provisions of this section, nothing contained in this section prevents an operator from conducting the activities permitted or authorized by a Clean Water Act Section 404 permit or other approval from the United States Army Corps of Engineers within any waters of the state or within the restricted areas referenced in this section. (d) The well location restrictions set forth in this section shall not apply to any well on a multiple well pad if at least one of the wells was permitted prior to the effective date of this article. (e) The secretary shall, by December 31, 2012, report to the Legislature on the noise, light, dust and volatile organic compounds generated by the drilling of horizontal wells as they relate to the well location restrictions regarding occupied dwelling structures pursuant to this section. Upon a finding, if any, by the secretary that the well location restrictions regarding occupied dwelling structures are inadequate or otherwise require alteration to address the items

4710303805

WW-6A  
(8-13)

API NO. 47-  
OPERATOR WELL NO. 7H  
Well Pad Name: Nextwave EFT

examined in the study required by this subsection, the secretary shall have the authority to propose for promulgation legislative rules establishing guidelines and procedures regarding reasonable levels of noise, light, dust and volatile organic compounds relating to drilling horizontal wells, including reasonable means of mitigating such factors, if necessary.

#### **Water Well Testing:**

Pursuant to West Virginia Code § 22-6A-10(d), notification shall be made, with respect to surface landowners identified in subsection (b) or water purveyors identified in subdivision (5), subsection (b) of this section, of the opportunity for testing their water well. The operator shall provide an analysis to such surface landowner or water purveyor at their request.

#### **Water Testing Laboratories:**

Pursuant to West Virginia Code § 22-6A-10(i), persons entitled to notice pursuant to subsection (b) of this section may contact the department to ascertain the names and locations of water testing laboratories in the subject area capable and qualified to test water supplies in accordance with standard accepted methods. In compiling that list of names the department shall consult with the state Bureau for Public Health and local health departments. A surface owner and water purveyor has an independent right to sample and analyze any water supply at his or her own expense. The laboratory utilized by the operator shall be approved by the agency as being certified and capable of performing sample analyses in accordance with this section.

#### **Rebuttable Presumption for Contamination or Deprivation of a Fresh Water Source or Supply:**

W. Va. Code § 22-6A-18 requires that (b) unless rebutted by one of the defenses established in subsection (c) of this section, in any action for contamination or deprivation of a fresh water source or supply within one thousand five hundred feet of the center of the well pad for horizontal well, there is a rebuttable presumption that the drilling and the oil or gas well or either was the proximate cause of the contamination or deprivation of the fresh water source or supply. (c) In order to rebut the presumption of liability established in subsection (b) of this section, the operator must prove by a preponderance of the evidence one of the following defenses: (1) The pollution existed prior to the drilling or alteration activity as determined by a predrilling or prealteration water well test. (2) The landowner or water purveyor refused to allow the operator access to the property to conduct a predrilling or prealteration water well test. (3) The water supply is not within one thousand five hundred feet of the well. (4) The pollution occurred more than six months after completion of drilling or alteration activities. (5) The pollution occurred as the result of some cause other than the drilling or alteration activity. (d) Any operator electing to preserve its defenses under subdivision (1), subsection (c) of this section shall retain the services of an independent certified laboratory to conduct the predrilling or prealteration water well test. A copy of the results of the test shall be submitted to the department and the surface owner or water purveyor in a manner prescribed by the secretary. (e) Any operator shall replace the water supply of an owner of interest in real property who obtains all or part of that owner's supply of water for domestic, agricultural, industrial or other legitimate use from an underground or surface source with a comparable water supply where the secretary determines that the water supply has been affected by contamination, diminution or interruption proximately caused by the oil or gas operation, unless waived in writing by that owner. (f) The secretary may order the operator conducting the oil or gas operation to: (1) Provide an emergency drinking water supply within twenty-four hours; (2) Provide temporary water supply within seventy-two hours; (3) Within thirty days begin activities to establish a permanent water supply or submit a proposal to the secretary outlining the measures and timetables to be used in establishing a permanent supply. The total time in providing a permanent water supply may not exceed two years. If the operator demonstrates that providing a permanent replacement water supply cannot be completed within two years, the secretary may extend the time frame on case-by-case basis; and (4) Pay all reasonable costs incurred by the real property owner in securing a water supply. (g) A person as described in subsection (b) of this section aggrieved under the provisions of subsections (b), (e) or (f) of this section may seek relief in court... (i) Notwithstanding the denial of the operator of responsibility for the damage to the real property owner's water supply or the status of any appeal on determination of liability for the damage to the real property owner's water supply, the operator may not discontinue providing the required water service until authorized to do so by the secretary or a court of competent jurisdiction.

#### **Written Comment:**

Pursuant to West Virginia Code § 22-6A-11(a), all persons described in subsection (b), section ten of this article may file written comments with the secretary as to the location or construction of the applicant's proposed well work within thirty days after the application is filed with the secretary. All persons described in West Virginia Code § 22-6A-10(b) may file written comments as to the location or construction of the applicant's proposed well work to the Secretary at:

Chief, Office of Oil and Gas  
Department of Environmental Protection  
601 57<sup>th</sup> St. SE  
Charleston, WV 25304  
(304) 926-0450

Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water. **NOTE: YOU ARE NOT REQUIRED TO FILE ANY COMMENT.**

**Time Limits and Methods for Filing Comments.**

The law requires these materials to be served on or before the date the operator files its Application. You have **THIRTY (30) DAYS** after the filing date to file your comments. Comments must be filed in person or received in the mail by the Chief's office by the time stated above. You may call the Chief's office to be sure of the date. Check with your postmaster to ensure adequate delivery time or to arrange special expedited handling. If you have been contacted by the well operator and you have signed a "voluntary statement of no objection" to the planned work described in these materials, then the permit may be issued at any time.

Pursuant to West Virginia Code § 22-6A-11(c)(2), Any objections of the affected coal operators and coal seam owners and lessees shall be addressed through the processes and procedures that exist under sections fifteen, seventeen and forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article. The written comments filed by the parties entitled to notice under subdivisions (1), (2), (4), (5) and (6), subsection (b), section ten of this article shall be considered by the secretary in the permit issuance process, but the parties are not entitled to participate in the processes and proceedings that exist under sections fifteen, seventeen or forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article.

**Comment Requirements**

Your comments must be in writing and include your name, address and telephone number, the well operator's name and well number and the approximate location of the proposed well site including district and county from the application. You may add other documents, such as sketches, maps or photographs to support your comments.

Disclaimer: All comments received will be placed on our web site <http://www.dep.wv.gov/oil-and-gas/Horizontal-Permits/Pages/default.aspx> and the applicant will automatically be forwarded an email notice that such comments have been submitted. The applicant will be expected to provide a response to comments submitted by any surface owner, water purveyor or natural gas storage operator noticed within the application.

**Permit Denial or Condition**

The Chief has the power to deny or condition a well work permit. Pursuant to West Virginia Code § 22-6A-8(d), the permit may not be issued or be conditioned, including conditions with respect to the location of the well and access roads prior to issuance if the director determines that:

- (1) The proposed well work will constitute a hazard to the safety of persons;
- (2) The plan for soil erosion and sediment control is not adequate or effective;
- (3) Damage would occur to publicly owned lands or resources; or
- (4) The proposed well work fails to protect fresh water sources or supplies.

A permit may also be denied under West Virginia Code § 22-6A-7(k), the secretary shall deny the issuance of a permit if the secretary determines that the applicant has committed a substantial violation of a previously issued permit for a horizontal well, including the applicable erosion and sediment control plan associated with the previously issued permit, or a substantial violation of one or more of the rules promulgated under this article, and in each instance has failed to abate or seek review of the violation within the time prescribed by the secretary pursuant to the provisions of subdivisions (1) and (2), subsection (a), section five of this article and the rules promulgated hereunder, which time may not be unreasonable.

Pursuant to West Virginia Code § 22-6A-10(g), any person entitled to submit written comments to the secretary pursuant to subsection (a), section eleven of this article, shall also be entitled to receive from the secretary a copy of the permit as issued or a copy of the order modifying or denying the permit if the person requests receipt of them as a part of the written comments submitted concerning the permit application. Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

RECEIVED  
DEPARTMENT OF  
ENVIRONMENTAL  
PROTECTION  
WELL PERMIT  
SECTION 11  
01/30/2026

WW-6A  
(8-13)

4710303805  
API NO. 47-  
OPERATOR WELL NO. 7H  
Well Pad Name: Nextwave EFT

**Notice is hereby given by:**

Well Operator: EQT Production Company  
Telephone: 844-378-5263  
Email: branen.weimer@eqt.com

*[Signature]*

Address: 2200 Energy Drive  
Canonsburg, PA 15317

Facsimile:

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use of your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

Commonwealth of Pennsylvania - Notary Seal  
Kristen Brooks, Notary Public  
Fayette County  
My commission expires February 17, 2029  
Commission number 1285524  
Member, Pennsylvania Association of Notaries

Subscribed and sworn before me this 18<sup>th</sup> day of December, 2025  
*Kristen Brooks* Notary Public  
My Commission Expires *Feb. 17, 2029*

RECEIVED  
Office of Oil and Gas  
DEC 20 2025  
WV Department of  
Environmental Protection

**Surface Owners:**

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

Hundred Resources, Inc.  
63 Mountain Park Drive  
Fairmont, WV 26554

**Surface Owners (All other disturbance):**

William Straight, Et al  
12910 Cable Rd  
Berlin Heights, OH 44814

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

**Coal Owners:**

Consol RCPC, LLC  
275 Technology Drive  
Canonsburg, PA 15317

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

Edwin Roshon  
2945 Blayney Road  
Sunbury, OH 43-74

Danny Roshon  
6440 Housemann Road  
Ostrander, Ohio 43061

**Water Supply Owners within 1,500':**

Robert F Knight III  
30 Church Fork Rd.  
Hundred, WV 26575

Topo Quad: Hundred

Scale: 1"=1000' 4710303805

County: Wetzel

Date: March 28, 2024


District: Church

Project No: \_\_\_\_\_

# NEXTWAVE WELL PAD

Water

28 Potential Water Sources Within 2500'



Keystone Consultants, LLC  
32 East Main Street  
Carnegie, PA 15106  
412 278-2100

Prepared For:  
EQT Production Company  
400 Woodcliff Drive  
Canonsburg, PA 15317



EQT PRODUCTION COMPANY  
400 WOODCLIFF DRIVE  
CANONSBURG, PA 15317

01/30/2026

**STATE OF WEST VIRGINIA**  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS**  
**NOTICE OF INTENT TO DRILL**

Pursuant to W. Va. Code § 22-6A-16(b), the Notice of Intent to Drill is only required if the notice requirements of W. Va. Code § 22-6A-10(a) have NOT been met or if the Notice of Intent to Drill requirement has NOT been waived in writing by the surface owner.

**Notice Time Requirement:** Notice shall be provided at least **TEN (10)** days prior to filing a permit application.

**Date of Notice:** 10/10/2025

**Date Permit Application Filed:** 12/19/25

**Delivery method pursuant to West Virginia Code § 22-6A-16(b):**

**HAND**  
**DELIVERY**       **CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Pursuant to W. Va. Code § 22-6A-16(b), at least ten days prior to filing a permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner notice of its intent to enter upon the surface owner's land for the purpose of drilling a horizontal well: *Provided*, That notice given pursuant to subsection (a), section ten of this article satisfies the requirements of this subsection as of the date the notice was provided to the surface owner: *Provided, however*, That the notice requirements of this subsection may be waived in writing by the surface owner. The notice, if required, shall include the name, address, telephone number, and if available, facsimile number and electronic mail address of the operator and the operator's authorized representative.

**Notice is hereby provided to the SURFACE OWNER(s):**

Name: See Attached List  
Address: \_\_\_\_\_

Name: See Attached List  
Address: \_\_\_\_\_

**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-16(b), notice is hereby given that the undersigned well operator has an intent to enter upon the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State: West Virginia  
County: Wetzel  
District: Church  
Quadrangle: Hundred  
Watershed: West Virginia Fork Fish Creek

UTM NAD 83      Easting: 547323.156  
Northing: 4392475.655  
Public Road Access: CR 250/2  
Generally used farm name: RDFS LLC

**This Notice Shall Include:**

Pursuant to West Virginia Code § 22-6A-16(b), this notice shall include the name, address, telephone number, and if available, facsimile number and electronic mail address of the operator and the operator's authorized representative. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/oil-and-gas/pages/default.aspx](http://www.dep.wv.gov/oil-and-gas/pages/default.aspx).

**Notice is hereby given by:**

Well Operator: EQT Production Company  
Address: 2200 Energy Drive  
Canonsburg, PA 15317  
Telephone: 412-913-4005  
Email: kristen.brooks@eqt.com  
Facsimile: 412-395-2974

Authorized Representative: Kristen Brooks  
Address: 2200 Energy Drive  
Canonsburg, PA 15317  
Telephone: 412-913-4005  
Email: kristen.brooks@eqt.com  
Facsimile: 412-395-2974

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

4710303805

Nextwave EFT

**Surface Owners:**

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

Hundred Resources, Inc.  
63 Mountain Park Drive  
Fairmont, WV 26554

**Surface Owners (All other disturbance):**

William Straight, Et al  
12910 Cable Rd  
Berlin Heights, OH 44814

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

01/30/2026

WW-6A5

(1/12)

**STATE OF WEST VIRGINIA**  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS**  
**NOTICE OF PLANNED OPERATION**

**Notice Time Requirement:** notice shall be provided no later than the filing date of permit application.

**Date of Notice:** 10/10/2025      **Date Permit Application Filed:** 12/19/25

**Delivery method pursuant to West Virginia Code § 22-6A-16(c)**

**CERTIFIED MAIL**       **HAND**  
**RETURN RECEIPT REQUESTED**      **DELIVERY**

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

**Notice is hereby provided to the SURFACE OWNER(s)**

(at the address listed in the records of the sheriff at the time of notice):

Name: See Attached List      Name: \_\_\_\_\_  
 Address: \_\_\_\_\_

**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State:	West Virginia	Easting:	547323.156
County:	Wetzel	Northing:	4392475.655
District:	Church	Public Road Access:	CR 250/2
Quadrangle:	Hundred	Generally used farm name:	RDFS LLC
Watershed:	West Virginia Fork Fish Creek		

**This Notice Shall Include:**

Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1) A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/oil-and-gas/pages/default.aspx](http://www.dep.wv.gov/oil-and-gas/pages/default.aspx).

Well Operator: EQT Production Company  
 Telephone: 412-913-4005  
 Email: kristen.brooks@eqt.com

Address: 2200 Energy Drive  
Canonsburg, PA 15317  
 Facsimile: 412-395-2974

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

4710303805

Nextwave EFT

**Surface Owners:**

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

Hundred Resources, Inc.  
63 Mountain Park Drive  
Fairmont, WV 26554

**Surface Owners (All other disturbance):**

William Straight, Et al  
12910 Cable Rd  
Berlin Heights, OH 44814

RDFS LLC  
11023 Mason Dixon Highway  
Burton, West Virginia 26562

01/30/2026

4710303805



WEST VIRGINIA  
DEPARTMENT OF TRANSPORTATION

1900 Kanawha Boulevard East • Building Five • Room 109  
Charleston, West Virginia 25305-0440 • (304) 558-0444

Michael J. DeMers  
Deputy Secretary of Transportation

Stephen T. Rumbaugh, P.E.  
Secretary of Transportation  
Commissioner of Highways

October 6, 2025

James A. Martin, Chief  
Office of Oil and Gas  
Department of Environmental Protection  
601 57<sup>th</sup> Street, SE  
Charleston, WV 25304

Subject: DOH Permit for the Nextwave EFT Well Pad, Wetzel County  
Nextwave EFT 1H Well Site    Nextwave EFT 3H Well Site  
Nextwave EFT 5H Well Site    Nextwave EFT 7H Well Site  
Nextwave EFT 9H Well Site    Nextwave EFT 11H Well Site  
Nextwave EFT 13H Well Site    Nextwave EFT 15H Well Site  
Nextwave EFT 17H Well Site

RECEIVED  
Office of Oil and Gas  
DEC 8 2025  
WV Department of  
Environmental Protection

Dear Mr. Martin,

This well site will be accessed from a DOH permit #06-2022-0060 which has been issued to EQT Production Company for access to the State Road for a well site located off Wetzel County Route 250/2 SLS MP 0.78.

This operator is in compliance with §22-6A-20 of the WV Code. Operator has signed a STATEWIDE OIL AND GAS ROAD MAINTENANCE BONDING AGREEMENT and provided the required Bond. This operator is currently in compliance with the DOH OIL AND GAS POLICY dated March 6, 2023. This letter is valid for permitting purposes for one year from the date of this letter.

Very Truly Yours,

A handwritten signature in blue ink that reads "Lacy D. Pratt".

Lacy D. Pratt  
Central Office O&G Coordinator

Cc: Kristen Brooks  
EQT Production Company  
OM, D-6  
File

E.E.O./AFFIRMATIVE ACTION EMPLOYER

01/30/2026

**Anticipated Frac Additives**  
**Chemical Names and CAS Numbers**

<u>Material</u>	<u>Ingredient</u>	<u>CAS Number</u>
<b>Sand (Proppant)</b>	<b>Silica Substrate</b>	<b>14808-60-7</b>
<b>Water</b>	<b>Water</b>	<b>7732-18-5</b>
<b>Hydrochloric Acid (HCl)</b>	<b>Hydrogen Chloride</b>	<b>7647-01-0</b>
<b>Friction Reducer</b>	<b>Copolymer of 2-propenamide</b>	<b>Proprietary</b>
	Petroleum Distillate	64742-47-8
	Oleic Acid Diethanolamide	93-83-4
	Alcohols, C12-16, ethoxylated	68551-12-2
	Ammonium chloride ((NH4)Cl)	12125-02-9
<b>Biocide</b>	<b>Glutaraldehyde</b>	<b>111-30-8</b>
	Alkyl dimethyl benzyl ammonium chloride	68391-01-5
	Didecyl dimethyl ammonium chloride	7173-51-5
	Non-hazardous substances	Proprietary
<b>Scale Control</b>	<b>Bis(HexaMethylene Triamine Penta(Methylene Phosphonic Acid)(BHMT)</b>	<b>34690-00-1</b>
	Non-hazardous substances	Proprietary
<b>Acid Chelating Agent</b>	<b>Ferriplex 66</b>	
	Citric Acid	77-92-9
	Acetic Acid	64-19-7
<b>Corrosion Inhibitor</b>	<b>PLEXHIB 166</b>	
	Methanol	67-56-1
	Alcohols, C14-15, ethoxylated	68951-67-7

4710303805

# EROSION & SEDIMENT CONTROL PLAN & SITE RESTORATION PLAN

## NEXTWAVE WELL SITE

### WETZEL COUNTY, WEST VIRGINIA FOR

## EQT

### EQT PRODUCTION COMPANY

APPROVED  
WVDEP OOG  
10/10/2024

W: Client EQT 2023-2024 - NextWave Well Pad CAD Plans/ES Plans/Title Sheet/Op

12/2024 10/2024

7/31/24

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024

10/2024


10/2024

10/2024

10/2024

10/2024&lt;/

4710303805



OPERATOR: EQT Production Company WELL NO: 7H

PAD NAME: Nextwave EFT

REVIEWED BY: Branden Weimer SIGNATURE: T. Weimer

## WELL RESTRICTIONS CHECKLIST

### HORIZONTAL 6A WELL

#### Well Restrictions

At Least 100 Feet from Pad and LOD (including any E&S Control Feature) to any Perennial Stream, Lake, Pond, Reservoir or Wetland; OR

DEP Waiver and Permit Conditions

At Least 300 Feet from Pad and LOD (including any E&S Control Feature) to any Naturally Producing Trout Stream; OR

DEP Waiver and Permit Conditions

At Least 1000 Feet from Pad and LOD (including any E&S Control Feature) to any Groundwater Intake or Public Water Supply; OR

DEP Waiver and Permit Conditions

At Least 250 Feet from an Existing Water Well or Developed Spring to Well Being Drilled; OR

Surface Owner Waiver and Recorded with County Clerk, OR

DEP Variance and Permit Conditions

At Least 625 Feet from an Occupied Dwelling Structure to Center of the Pad; OR

Surface Owner Waiver and Recorded with County Clerk, OR

DEP Variance and Permit Conditions

At Least 625 Feet from Agricultural Buildings Larger than 2500 Square Feet to the Center of the Pad; OR

Surface Owner Waiver and Recorded with County Clerk, OR

DEP Variance and Permit Conditions

RECEIVED  
Office of Oil and Gas  
DEC 20  
W/Disclaimer  
Environmental Protection  
Engineering Division

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026

01/30/2026