


Wish Ice



O T Midcap

Green District, Wetzel County, W. Va.

By O. T. Midcap, New Martinsville, W. Va. (HFD No. 2, Box 70-2).

Abandoned under permit Wet-90.

On 6 acres; surface and minerals owned by Richard Carroll,
Middlebourne, W. Va.

Drilled in 1928.

Elevation.....

10" casing, 200' 5"; 8" casing, 1466'; 6" casing, 2096'.

No packer. Casing not perforated. No liners used.

Coal was encountered at 993-993 1/2'.

Abandonment reported to Dept. of Mines Aug. 30, 1932.

Well was shot at 2230'.

Salt water at 2130'.

Oil well. Record to ROT from Mrs. Griffith Sept. 10, 1938.

	Top.	Bottom.
Pittsburgh Coal, black	993	993 1/2
Marion Sand	1930	1960
Pencil Cove	2042	2062
Big Lime	2062	2129
Keener Sand (gas, 2129'; water, 2130')	2129	2215
Big Injun Sand (gas, 2227'; oil, 2230')	2216
Total depth		2240