


30094
Church



WET-94-A

Church District, Wetzel County, W. Va.

By The Manufacturers Light & Heat Co., 800 Union Trust Bldg.,
Pittsburgh, Pa.On 64 acres, surface owned by Margaretta Talkington, Hundred,
W. Va., and mineral rights by MLANCo., Pgh., Pa.

Drilled prior to June 1, 1929.

Elevation, 1096' L.

10" casing, 308'; 8 $\frac{1}{2}$ " 1380'; 6-5/8" 2204' 8".

Coal was encountered at 485-488, 630-633, 850-856, and 950-958'.

Abandonment reported to Dept. of Mines Oct. 5, 1932.

Gas well.

	Top.	Bottom.	Thickness.
Clay	0	13	13
Lime (water at 180')	160	180	20
Coal	485	488	3
Bluff Sand	575	615	40
Fairview (Waynesburg) Coal	630	633	3
Slate	840	850	10
Mapletown (Sewickley) Coal (little gas)	850	856	6
Pittsburgh Coal (1 $\frac{1}{2}$ bailers water)	950	958	8
Gritty lime	958	1010	52
Red rock	1030	1045	15
Red rock	1065	1075	10
Red rock	1120	1160	40
Red rock	1200	1245	45
Lime	1338	1353	15
Gas Sand	1620	1645	25
1st Salt Sand	1650	1660	10
2nd Salt Sand	1725	1825	100
3rd Salt Sand	1900	1965	65
Maxton Sand (little gas)	2060	2144	84
Big Injun Sand (show gas, 2240-42')	2198	2435	237
50-Ft. Sand	2900	2950	50
Gordon Stray Sand (gas, 2998-3003')	2994	3013	19
Gordon Sand	3065	3125	60
4th Sand (little gas, 3166-3168')	3148	3170	22
Slate	3170	3230	60
Total depth		3230	
(well connected up in 6-5/8" casing) (6/10 Water in 2")			