





STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

143

Quadrangle Zettlitz

WELL RECORD

Oil or Gas Well Gas  
(KIND)

Permit No. WV-1020-A

Company THE MANUFACTURERS LIGHT AND HEAT COMPANY

Address 800 Union Trust Bldg., Pgh., Penna.

Farm W. M. Straight Acres 100

Location (waters) \_\_\_\_\_

Well No. 1329 Elev. 1331.60'

District Green County Wetzel

The surface of tract is owned in fee by \_\_\_\_\_

Address \_\_\_\_\_

Mineral rights are owned by \_\_\_\_\_

Address \_\_\_\_\_

Drilling commenced February 11, 1905

Drilling completed March 29, 1905

Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

With \_\_\_\_\_

Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch

\_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch

Volume \_\_\_\_\_ Cu. Ft.

Rock Pressure 320 lbs. \_\_\_\_\_ hrs.

Oil \_\_\_\_\_ bbls., 1st 24 hrs.

Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet

Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer _____
13			
10	154	154	Size of <u>3 x 6-5/8</u>
8 1/2	1392		
6 5/8	2412	2412	Depth set _____
5 3/16			
3	3104	3104	Perf. top _____
2			Perf. bottom _____
Liners Used			Perf. top _____
			Perf. bottom _____



CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT 544 FEET \_\_\_\_\_ INCHES

910 FEET \_\_\_\_\_ INCHES 990 FEET \_\_\_\_\_ INCHES

\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Native Coal			544				
Mapletown Coal			910				
Pittsburgh Coal			990				
Little Dunkard			1286	1316			
Big Dunkard			1392	1450			
Gas Sand			1520	1550			
Salt Sand			1620	1660			
Second Salt Sand			1760	1810			
Third Salt Sand			1840	1900			
Maxon Sand			2020	2080			
			2207	2264			
Big Lime			2264	2290			
Big Indian Sand			2290	2520			
Gas			2300				
Water			2405				
Gordon Sand			3071				
Gas			3079				
Total Depth			3188				



JUNE 21 1956

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date October 14, 19 55

APPROVED THE MANUFACTURERS LIGHT AND HEAT CO., Owner

By *J. B. Cooper*  
**LAND AGENT** (Title)