

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Moses Bartrug Operator Well No.: 8138

LOCATION: Elevation: 1408.18' Quadrangle: Hundred W.VA, PA
District: Church County: Wetzel
Latitude: 39.668792 Feet South of 39 Deg. 40 Min. 7.65 Sec.
Longitude: -80.403328 Feet West of -80 Deg. 24 Min. 11.98 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, INC. Coal Operator West Virginia Land Resources, INC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 10/12/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Mathew A. Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of November, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w Green Dye/Gas Blocker	1523'	1029'	16" Conductor - 0'	20'
Expandable Cement	1029'	Surface		


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 28th day of November, 2023.

And further deponents saith not. Matthew Yearsley
John Campbell

Sworn and subscribe before me this 12th day of December, 2023

My commission expires: June 8, 2027

Christopher Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COLUMBIA GAS TRANSMISSION CORP.
Lease or Property Owner
13016 Indian Creek RD. Jacksonburg, WV 26377
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Hundred W.VA, PA
Well Location
Church
District
WETZEL
County
8138
Well No.
MOSES BARTRUG
Fam

STATE INSPECTOR SUPERVISING PLUGGING _____ Steve Mccoy _____

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Wetzel ss:

MATTHEW A. YEARSLEY and JOHN CAMPBELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7th day of November, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from surface to 263'. Reduced to a 9 7/8" hole at 263'. Cleaned 9 7/8" hole from 263' to 1229'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1229' - 1235.5'). Cleaned a 9 7/8" hole from 1235.5' to 1523'. Left 20' of 16" conductor pipe in the hole from 20' to surface. <u>Cemented hole from 1523' to the surface as follows:</u> Cemented from 1523' to 1029' with 315 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Cemented from 1029' to surface with 555 sacks of Expandable Cement. Cement did circulate at the surface. A total of 870 sacks of cement were used to fill the hole from 1523' to surface.	16" Conductor	0'	20'
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>Pittsburgh</u>	1229' - 1235.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 28th day of November, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

John Campbell


John Campbell

Sworn to and subscribed before me this 12th day of December, 2023

Christopher Willis
Notary Public

My commission expires

June 8, 2027



Permit No. 47-103-71397
Well No. 8138
Latitude: 39° 40' 7.65"N
Longitude: -80° 24' 11.98"W