State of West Virginia Department of Environmental Protection - Office of Oil and Gas Well Operator's Report of Well Work

RECEIVED Office of Oil and Gas

JUN 9 2017

API 47 - 009 _ 00168	County BROOKE	Е Г	District BUFFALC	
Quad STEUBENVILLE EAST & BETI	HANY Pad Name BROOKE	COUNTY PARKS-BRK-1H	ield/Pool Name F	PANHANDLE FIELD
Farm name BROOKE CO. PAR			Well Number BRC	OOKE COUNTY PARKS BRK 10H
Operator (as registered with the OC	OG) SWN PRODUCTIO	N COMPANY, LLC		
Address PO BOX 12359	City SPR	ING	State TX	Zip 77391-2359
As Drilled location NAD 83/UT Top hole	M Attach an as-drilled Northing 4,456,758.133	plat, profile view, and Easti	deviation survey ng 538,454.654	
Landing Point of Curve	Northing 4,456,656.503	Eastin	ng 538,723.912	
Bottom Hole	Northing 4,454,485.470	Eastin	ng <u>539,464.501</u>	
Elevation (ft) 1206' GI	L Type of Well	New □ Existing	Type of Repor	t □Interim BFinal
Permit Type Deviated	Horizontal B Horizonta	al 6A 🗆 Vertical	Depth Type	□ Deep ■ Shallow
Type of Operation □ Convert	□ Deepen	Plug Back □ Redrill	ing Rework	■ Stimulate
Well Type □ Brine Disposal □ C	BM ■ Gas □ Oil □ Seco	ondary Recovery Sol	lution Mining S	torage 🗆 Other
Type of Completion ■ Single □	Multiple Fluids Produc	ed □ Brine ■Gas	□ NGL □ Oil	□ Other
Drilled with □ Cable ■ Rotary		to selve sen,	-11	
Production hole Air Mud Mud Type(s) and Additive(s) SOBM	□ Fresh Water □ Brine			
Date permit issued 12/10/201	5 Date drilling comm	enced 11/6/2016	Date drilling	g ceased11/17/2016
Date completion activities began	03/04/2017	Date completion activ		04/03/2017
Verbal plugging (Y/N) N	_ Date permission granted		Granted by	N/A
Please note: Operator is required to	o submit a plugging applica	tion within 5 days of ve	erbal permission to	plug
Freshwater depth(s) ft	250'	Open mine(s) (Y/N) de	epths	N
Salt water depth(s) ft	44001	Void(s) encountered (N STATE OF THE PARTY OF THE PAR
Coal depth(s) ft	0401	Cavern(s) incommerce		
Is coal being mined in area (Y/N)				
		NAME: (Reviewed by:
		DATE: ((-8.17	01/05/2018

Rev. 8/23/13									
API 47- 009	_ 00168	Farm na	me_BROOKE	CO. PARK	COMMIS	SION Well	number_BR	OOKE COU	INTY PARKS BRK 10F
CASING	Hole	Casing		New or	Grade		Basket		ent circulate (Y/N)
STRINGS	Size	Size	Depth	Used	w <u>t/ft</u>		Depth(s)	* Provid	de details below*
Conductor	24	20	126	NEW	 	5/94#		+	YY
Surface	17.5	13.375	369	NEW	H-4	10/48#		Y; 22	BBLS RETURNED
Coal	SURFACE								
Intermediate 1	12.25	9.625	1682	NEW	J-5	55/36#		Y; 23	BBLS RETURNED
Intermediate 2					 _				
Intermediate 3									
Production	8.75/8.50	5.5	14040	NEW	HCP-	-110/20#			<u>Y</u>
Tubing		2.375	6261	NEW	L-8	0/4.7#			N
Packer type and d	epth set								
Comment Details						· ·			
CEMENT	Class/Type	Numbe	r Slurr	ry	Yield	Volume	Cen	nent	woc
DATA	of Cement	of Sack	s wt (pr	og) (ft ³/sks)	(R ³)	Top ((hrs)
Conductor	CLASS A	150	17.0	_		150		FACE	24
Surface	CLASS A	380	15.6	0	1.20	456	SURI	FACE	8
Coal	SURFACE								
Intermediate 1	CLASS A	650	15.6	0	1.20	780	SURI	FACE	8
Intermediate 2									
Intermediate 3									-
Production	CLASS A	856/168	36 15.6	0 1.	23/1.19	1052.88/2006	.34 SUR	FACE	24
Tubing						<u> </u>			
Drillers TD (fl	14,040"			Loggers 1	ΓD (θ) 14.	.040			
	tion penetrated	MARCELLUS			to (ft) N/				
Plug back pro	•						, •		
Kick off depth	(ft) <u>5,371'</u>								
Chaok all wire	lina laga mm	a caliman	B donaitu	a douis	tad/dinasti	ional sim	duction		
Check all wire	eline logs run	■ caliper■ neutron	-		ted/directi		nduction emperature	□soni	•
		a neutron	= lesistivity	e ganin	а гау	= 10	emperature	USOIII	·
Well cored	Yes B No	Conventi	onal Side	wall	W	ere cuttings	collected	□ Yes ■	■ No
DESCRIBE T	HE CENTRAL	IZER PLACEM	ENT USED FO	OR EACH C	ASING S	TRING			
SURFACE: 7 CENTE	RALIZERS - EVERY TH	IRD JOINT OF CASING							
		ERY THIRD JOINT OF CA		F CURVE, THEN	EVERY JOINT	UNTIL TD			
WAS WELL	COMPLETED	AS SHOT HOLE	E □Yes ■	No D	ETAILS			Office	ECEIVED of Oil and Gas
	-			.				4UL	9-2017
WAS WELL	COMPLETED	OPEN HOLE?	□ Yes ▮ N	io DET	AILS _			WV [Environr	Department of mental Protection
WERE TRAC	ERS USED 1	Yes A No	TYPE OF T	RACER(S)	USED _				
			<u> </u>			· · · · · · · · · · · · · · · · · · ·			01/05/2018

API 47- 009 - 00168 Farm name BROOKE CO. PARK COMMISSION Well number BROOKE COUNTY PARKS BRK 10H

PERFORATION RECORD

Stage No.	Perforation date	Perforated from MD ft.	Perforated to MD ft.	Number of Perforations	Formation(s)
	SEE	ATTACHMEN	1		
			-		
-			-		
					
			_		-
-					
					
					
					
		 			
-					
-					
				<u> </u>	

Please insert additional pages as applicable.

STIMULATION INFORMATION PER STAGE

Complete a separate record for each stimulation stage.

Stage No.	Stimulations Date	Ave Pump Rate (BPM)	Ave Treatment Pressure (PSI)	Max Breakdown Pressure (PSI)	ISIP (PSI)	Amount of Proppant (lbs)	Amount of Water (bbls)	Amount of Nitrogen/other (units)
			ATTACHMENT	2				
								-
			1					
								
		-						
							RECE Office of Oi	VED.
		-					Office of O	and Gas
		· -					JUN	2017
							WV Depar Environmenta	tment of I Protection
			Ì					

Please insert additional pages as applicable.

WR-35 Rev. 8/23/13

ICCV. 0/23/13											401
API 47- 009	00168	Farm I	name_BROOKE	CO. PAI	RK COM	MISSIO	Well n	umber	BROOKE COL	JNTY PARKS BR	K 101
PRODUCING	FORMATION(<u>s)</u>	<u>DEPTHS</u>								
MARCELLUS			5937.58'	_ TVD	6305.3	30'	MD				
	·						_				
				_							
Please insert ad	Iditional pages a	s applicable.									
GAS TEST	Build up	Drawdown	□ Open Flow		OIL T	EST ol	Flow 🗆	Pump			
SHUT-IN PRE	SSURE Surf	ace 1400	_psi Botto	m Hole_		psi	DURAT	ION C	F TEST _	hrs	
OPEN FLOW	Gas 1748 mcf	Oil pd <u>236</u> l	NGL bpd	_ bpd	Water 283	bpd			IRED BY	□ Pilot	
LITHOLOGY/ FORMATION	TOP DEPTH IN FT NAME TVD	BOTTOM DEPTH IN FT TVD	TOP DEPTH IN FT MD	BOTTO DEPTH II MD	NFT D				RECORD QUA	ANTITYAND IL, GAS, H2S, E1	C)
	0		0				, one (, , , , , , , , , , , , , , , , , , ,				
	SEE	ATTACHMENT	3		_						
					-				RECE Office of O	IVED I and Gas	
									JUN (2017	
									WV Depar	tment of	
										FIOUSCHON	
	lditional pages a										
Drilling Contra Address PO BO	ox 12359	LING COMPAN	Y City	SPRING			State	тх	Zip _7739	1-2359	
Logging Comp	any BAKER HU	GHES									
Address 9110 G	ROGAN MILL RD	<u>-, -</u>	City	THE WO	ODLAND	s	State	TX	Zip <u>7738</u>	30	_
Cementing Cor	mpany SCHLUM	IBERGER WEL	L SERVICES								
	CHLUMBERGER D		City	SUGAR	LAND		State	TX	Zip <u>7747</u>	'8	_
Stimulating Co	mpany US WE	LL SERVICES									
Address 770 S I	POST OAK LN #40)5	City	HOUSTO	ON		State	TX	Zip <u>7705</u>	56	_
Please insert ad	lditional pages a	s applicable.									
Completed by	DENISE GRAN				_ To	elephone	832-796	6139			
Signature 1	unacqu	anthai	Title RI	EGULATO	RY TECH	NICIAN		Date 6	/8/2017		

Well Name: BROOKE COUNTY PARKS BRK 10H 47009001680000

LITHOLOGY/FORMATION	TOP DEPTH, MD (FT)	TOP DEPTH, TVD (FT)	BOTTOM DEPTH, MD (FT)	BOTTOM DEPTH, TVD (FT)	QUANTITY AND TYPE OF FLUID
Base of Fresh Water	N/A	N/A	250.00	250.00	
Top of Salt Water	1126.00	1126.00	N/A	N/A	
Pittsburgh Coal	316.00	316.00	321.00	321.00	
Big Injun (ss)	1425.00	1424.95	1632.00	1631.93	
Berea (siltstone)	1976.00	1975.89	5446.81	5373.35	
Rhinestreet (shale)	5446.81	5373.35	5711.67	5616.77	
Cashaqua (shale)	5711.67	5616.77	5782.18	5675.09	
Middlesex (shale)	5782.18	5675.09	5855.56	5731.00	
Burket (shale)	5855.56	5731.00	5881.25	5748.70	
Tully (Is)	5881.25	5748.70	5968.60	5804.97	
Mahantango (shale)	5968.60	5804.97	6305.30	5937.58	
Marcellus (shale)	6305.30	5937.58	N/A	N/A	GAS

HECEIVED
Office of Oil and Gas
JUN 9 2017
WV Department of Environmental Protection

BROOKE COUNTY PARKS BRK 10H PERF SUMMARY

STAGE NUM	Perf Date	Perf Top MD	Perf Bottom MD	# SHOTS PER STG
	3/4/2017	13,737	13,931	42
	3/4/2017	13,481	13,675	42
	3/4/2017	13,225	13,419	42
	3/5/2017	12,969	13,163	
	3/5/2017	12,713	12,907	42
(3/5/2017	12,457	12,651	42
	3/5/2017	12,201	12,395	42
	3/5/2017	11,945	12,139	43
	3/7/2017	11,689	11,883	42
10	3/7/2017	11,433	11,627	42
13	3/8/2017	11,177	11,371	42
12	2 3/8/2017	10,921	11,115	42
13	3/8/2017	10,665	10,859	42
14	3/9/2017	10,409	10,603	42
15	3/9/2017	10,153	10,347	42
16	3/9/2017	9,897	10,091	42
17	7 3/9/2017	9,641	9,835	42
18	3/10/2017	9,385	9,579	31
19	3/10/2017	9,129	9,323	42
20			9,067	42
2:	1 3/17/2017	8,617	8,811	42
2:	3/17/2017	8,361	8,555	42
23				
24	3/17/2017	7,849	8,043	42
25	3/17/2017	7,593	7,787	42
26	3/18/2017	7,337	7,531	. 42
27				
28				
25				
30				

RECEIVED Office of Oil and Gas

JUN 9 2017

BROOKE COUNTY PARKS BRK 10H FRAC STAGE SUMMARY

TAGE		Ave Pump Rate		Max Breakdown		Amount of	Amount of	Amount of
IUM	Stim Date	The state of the s	Pressure (PSI)	Pressure (PSI)		Proppant (lbs)	water bbls	nitrogen/other
1	3/4/2017		7,591			499,120		
2	3/4/2017		7,555		4,279	500,020		
3			8,114		4,412	500,040		
4	- SKEK-SES		7,499					
5			7,878		4,034			
6	-1-1		8,110		4,524	500,240		
7		98	7,655					
8			7,701		4,116			
9	-1-7		7,306					
10	3/7/2017		7,428					
11	3/8/2017	99	7,520	7,889	4,227			
12	3/8/2017	98	7,191	8,007	4,431	500,020		
13	3/8/2017	99	7,151	7,447	4,208	499,860		
14	3/9/2017	98	6,941			500,400	6,930	
15	3/9/2017	95	7,132	7,631	4,628	495,600	6,991	
16	3/9/2017	96	7,056	8,307	4,610	500,400	6,930	
17	3/9/2017	93	6,517	7,374	4,098	331,900	7,318	
18	3/10/2017	95	6,955	7,206	4,346	501,100	6,901	
19	3/10/2017	96	6,696	7,110	4,517	501,780	6,915	0
20	3/17/2017	95	7,173	8,558	4,352	494,300	6,901	
21	3/17/2017	100	7,149	7,771	4,306	510,340	6,776	
22	3/17/2017	99	7,099	8,100	4,524	502,060	6,773	11 -
23	3/17/2017	96	6,779	7,385	4,510	499,840	6,791	
24	3/17/2017	95	6,673	6,981	4,510	504,930	6,811	
25	3/17/2017	94	6,970	7,585	4,270	501,680	6,693	
26	3/18/2017	99	6,995	7,446	4,177	500,480	6,716	
27	3/18/2017	100	6,951	7,775	4,313	498,900	6,702	D. C.
28	3/18/2017	96	7,040	8,175	4,102	510,440	6,671	
29	3/18/2017	100	6,788	8,880	4,238	503,760	6,606	
30	3/18/2017	99	6,499	7,238	4,116	498,560	6,648	

RECEIVED Office of Oil and Gas

JUN 9 2017

Hydraulic Fracturing Fluid Product Component Information Disclosure

RECEIVED Office of Oil and Gas


JUN 9 2017

WV Department of Environmental Protection









Hydraulic Fracturing Fluid Composition:

Trade Name	Supplier	Purpose	Ingredients	Chemical Abstract Service Number (CAS #)	Maximum Ingredient Concentration in Additive (% by mass)**	Maximum Ingredient Concentration in HF Fluid (% by mass)**	Comments
Water	Southwestern Energy	Carrier/Base Fluid			A Value land		
			Water	7732-18-5	100.00000	82.14497	
Sand	U.S. Well Services, LLC	Proppant					
			Crystalline Silica, quartz	14808-60-7	100.00000	16.55146	
HCL Acid (12.6%- 17.5%)	U.S. Well Services, LLC	Bulk Acid					
			Water	7732-18-5	87.40000	1.00034	
			Hydrogen Chloride	7647-01-0	17.50000	0.23258	
WFRA-2000	U.S. Well Services, LLC	Friction Reducer					
			Water	7732-18-5	60.00000	0.03659	
			2-Propenoic acid, polymer with 2 propenamide	9003-06-9	30.00000	0.01829	
			Hydrated light distillate (petroleum)	64742-47-8	30.00000	0.01500	
AI-303	U.S. Well Services, LLC	Acid Corrosion Inhibitors					
			Ethylene glycol	107-21-1	40.00000	0.00033	
			Cinnamaldehyde	104-55-2	20.00000	0.00012	
			Formic acid	64-18-6	20.00000	0.00012	


Butyl cellosolve	111-76-2	20.00000	0.00010
Polyether	60828-78-6	10.00000	0.00006
Acetophenone,thiourea,form	hiourea,formalde 58527-49-1	5.00000	0.00003
hyde polymer			

* Total Water Volume sources may include fresh water, produced water, and/or recycled water ** Information is based on the maximum potential for concentration and thus the total may be over 100%

Note: For Field Development Products (products that begin with FDP), MSDS level only information has been provided. Ingredient information for chemicals subject to 29 CFR 1910.1200(i) and Appendix D are obtained from suppliers Material Safety Data Sheets (MSDS)

RECEIVED Office of Oil and Gas


9 2017 NOS





THE THRASHER GROUP, INC. 600 WHITE DAKS BLVD. BRIDGEPORT, WV 26330 PHONE 304-624-4108

RACT	ADJOINER	PARCEL
A	COUNTY COURT OF BROOKE COUNTY	05-03-B34-0049-0000
В	JOHN PAUL POTTER, PENNY POTTER SUAVE, JAY M POTTER II	05-03-B33-0108-0000
C	JOHN G. RADVANSKY & BARBARA J RADVANSKY	05-03-B33-0109-0000
D	GEORGE GIPALO & RHONDA GIPALO	05-03-B33-0110-0000
E	GEORGE GIPALO & RHONDA GIPALO	05-03-B33-0114-0001
F	COUNTY COURT OF BROOKE COUNTY	05-03-B33-0113-0000
G	KEITH SMITH & KATHY SMITH	05-03-B33-0026-0000
Н	KEITH SMITH & KATHY SMITH	05-03-B33-0025-0000
Ī	KEITH SMITH & KATHY SMITH	05-03-B28-0045-0000
J	KEITH R SMITH & KATHY J SMITH	05-03-B28-0063-0000
K	DAVID L. RAGAN	05-03-B28-0062-0000
L	DAVID L. RAGAN	05-03-B28-0059-0000
M	WILLOW SPRINGS INC	05-03-B28-0058-0000
N	WILLIAM CURTIS HUNT & SUSAN L HUNT	05-03-B28-0057-0001
0	DELORES JEANNE BUYAN, SARAH LYNN LYCANS STENGER, JUDITH LEE BRINKLEY	05-03-B28-0066-0000
P	NANCY J AMBROSE	05-03-B29E-0001-0000
Q	NANCY J AMBROSE	05-03-B29J-0007-0000
R	DAVID RAGAN	05-03-B29J-0024-0000
S	CARMAN FANASE	05-03-B29J-0025-0000
T	JAMES L & LAURA INMAN	05-03-B29-0014-0000
U	BRIAN E & JENNIFER B PLANTS	05-03-B34-0001-0000
٧	MARK OWEN WEAVER & VIRGINIA BEALL KREUTZ	05-03-B34-0016-0001
W	DENZIL & MARY LOU CONLEY	05-03-B34-0016-0002
X	MARLENE K. HUKILL	05-03-B34-0016-0005
Y	JOHN C WALES & BARBARA A WALES	05-03-B34-0001-0001
Z	BRIAN SMITH	05-03-B34-0016-0004
AA	PHOENIX-GREENLAWN PARTNERS	05-03-B34-0010-0002
BB	STARVAGGI INDUSTRIES INC.	05-03-B34-0007-0000
CC	STARVAGGI INDUSTRIES INC.	05-03-B34-0010-0000
DD	RUSSELL D HERVEY	05-03-B34-0011-0000
EE	STARVAGGI INDUSTRIES INC.	05-03-B34-0014-0000
FF	STARVAGGI INDUSTRIES INC.	05-03-B34-0015-0000
GG	BERNARD J KNORR III & NICOLE C KNORR	05-03-B34-0018-0000
НН	RUBY FAYE KNORR & BERNARD JOHN KNORR JR	05-03-B34-0019-0000
11	BERNARD J KNORR JR & RUBY F KNORR	05-03-B34-0048-0000



01/05/2018

SWN Production Company, LLC Production Company™ DATE: 05-11-2017
SHEET 2 OF 3
DRAWN BY: K. POTH
SCALE: 1" = 2000'
DRAWING NO: 050-5525
WELL LOCATION PLAT REVISIONS:

COMPANY: