




WELL NO 8304  
 HOPE NATURAL GAS CO  
 E. M. TALBOTT  
 TROY  
 Owner: GILMER



LEGEND

- Location
- Oil Well
- ⊙ Aband.
- ⊛ Gas Well
- ⊞ Aband.
- ⊕ Dev Hole

Field Book No. 515 P. 29-40  
 Scale 1" = 400'  
 MAY 29 1931

ENGINEERS CERTIFICATE

The undersigned hereby certify that this map is correct and shows all the information in the books of our knowledge.

Troy District, Gilmer County, W. Va.  
 Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.  
 On 56 acres, surface owned by Madora L. Talbott Heirs, Troy, W. Va.  
 Drilled prior to June 1, 1929.  
 Elevation, 761' L.  
 13" casing, 52'; 10", 204'; 8 $\frac{1}{4}$ ", 380'; 6-5/8", 1399'.  
 No coal was encountered.  
 Abandonment reported to Dept. of Mines May 29, 1931.  
 Well was shot at 1587-1592'.  
 Salt water at 1112'.  
 Gas well; now exhausted to extent of not being commercially  
 productive.

	Top.	Bottom.
Little Dunkard Sand	329	- 348
Big Dunkard Sand	410	- 445
Gas Sand	645	- 681
First Salt Sand	746	- 792
Second Salt Sand	807	- 867
Third Salt Sand (water, 1112'; show of gas, 1112')	1062	- 1154
Maxton Sand	1225	- 1247
Little Lime	1360	- 1377
Pencil Cave	1377	- 1382
Big Lime	1382	- 1500
Big Injun Sand (gas, 1590')	1500	- 1612
Total depth		1632

Company Name  
 645 West 1st St.  
 Clarksville, W. Va.

COMPLETION DATA SHEET  
 NO. 2  
 FORMATION RECORD

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Little Dunkard Sand				339	340	19'		
Big Dunkard Sand				410	448	38'		
Gas Sand				645	681	36'		
First Salt Sand				746	792	46'		
Second Salt Sand				807	867	60'		
Third Salt Sand				1062	1154	92'		
Maxon Sand			Water-1112 show of gas -1112	1235	1247	22'		
Little Lime				1360	1377	17'		
Pencil Cave				1377	1382	5'		
Big Lime				1382	1500	118'		
Big Injun Sand			Gas- 1590	1500	1612	112'	1632	

*Oil-19-A*

shot  
 Well was not shot at 1537 - 1592 feet; well was shot at \_\_\_\_\_ feet.  
 Salt  
 Fresh water at -- feet; salt fresh water at 1112 feet.  
 producing

WEST VIRGINIA DEPARTMENT OF MINES

Oil and Gas Section

PRELIMINARY DATA SHEET NO. 1

File No. 19-A Well No. 6364

Hope Natural Gas Company, of 448 West Main St.

Clarksburg, W. Va. on the E. M. Talbott Farm

containing 36 acres. Location

Troy District, in Gilmer County, West Virginia.

The surface of the above tract is owned in fee by Madora L. Talbott Heirs.

of Troy, W. Va. address, and the mineral rights are owned by

--- of ---

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. --- issued by the West Virginia Department of Mines, Oil and Gas Section.

Drilled prior to law act, 1929. 19

Elevation of surface atop of well, 761 spirit  
~~mercurial~~

The number of feet of the different sized casings used in the well.

	feet	size.	Wood conductor
<u>58</u>	<u>feet</u>	<u>10"</u> size, cog <u>304</u>	<u>feet</u> <u>10"</u> sized cog
<u>300</u>	<u>feet</u>	<u>8 1/4"</u> size, cog <u>1399</u>	<u>feet</u> <u>8-5/8"</u> sized cog
	<u>feet</u>	size, cog	<u>feet</u> sized cog
	packer of		size, set at
	packer of		size, set at
	casing perforated at		feet to feet
	casing perforated at		feet to feet

Coal was encountered at None feet, thickness inches, and at inches feet, thickness inches; and at feet, thickness inches.

Liners were used as follows: (Give details)

May 29, 1931 Date.

AFFIDAVIT IN TRIPPLICATE TO TIME AND MANNER OF  
PLUGGING AND FILLING WELL

(REQUIRED BY SECTION 8, CHAPTER 20, ACT OF 1920)

WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS SECTION

No Coal.	Hope Natural Gas Company
COAL OPERATOR	NAME OF WELL OPERATOR
ADDRESS	445 West Main St., Clarkshurg, W. Va.
COAL OPERATOR	COMPLETE ADDRESS
ADDRESS	July 25, 1931 19
COAL OPERATOR	WELL AND LOCATION
ADDRESS	Troy District
COAL OPERATOR	Gilmer County
ADDRESS	Well No. 6384
	E. M. Talbott Farm

AFFIDAVIT TO BE MADE IN TRIPPLICATE: ONE COPY TO BE MAILED BY REGISTERED MAIL TO THE DEPARTMENT, ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ABOVE NAMED AT THEIR RESPECTIVE ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA,  
COUNTY OF Gilmer

} ss: 8-1-19-A

Jacob R. Straley and John L. AMON  
being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Hope Natural Gas Co, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22nd day of July, 1931, and that the well was plugged and filled in the following manner:

Manner in which said well was plugged: Filled with Mud & Clay from 1545 ft. up to 1450  
Drove Lead Plug at 1450 ft. filled with mud & Clay to 1410 and set Cement Plug.  
Pulled 6-5/8" Casing and filled with mud & Clay to 1340 and set Cement Plug.  
Bridged hole at 1184 and ~~set wood and cement plug at 1048~~ filled with  
mud and clay to 1048 and set wood and cement plug at 1048, Bridged hole at 897 ft  
~~Manner in which well was plugged:~~  
and filled with mud & clay to 726 ft. and set wood & Cement Plug at 726 ft.  
Bridged hole at 465 and filled with mud & Clay to 410 ft. Set wood and cement  
plug at 410, Bridged hole at 390 ft & set wood and cement plug at 390 ft.  
Pulled 8 1/2" Casing, and bridged hole at 214 ft. set wood & Cement Plug at 214 ft.  
Pulled 10" Casing, and filled solid with mud & Clay to 52 ft. and pulled 12"  
Casing, then filled solid with mud, Clay ~~and cement~~ to surface of ground.  
Description of monument:  
Erected Concrete marker 5 ft. long, extending 30" below ground and set in  
fresh concrete, Marker indicating the number of well and Company.

8-1-19-A  
8-6-31

(THE ABOVE DESCRIPTIONS MUST BE IN DETAIL AND IN ACCORDANCE WITH THE PROVISIONS OF SECTION 16, OIL AND GAS ACT OF 1920.)  
and that the work of plugging and filling said well was completed on the 22nd day of July

1931  
And further deponents saith not.

J. R. Straley