

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Peck, Mary Operator Well No.: 4

LOCATION: Elevation: 1065 Quadrangle: 7.5 West Milford  
District: Clark County: Harrison  
Latitude: 39.24660686252 Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
Longitude: -80.38021714663 Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Spencer Enterprises LLC Coal Operator \_\_\_\_\_  
PO Box 143 or Owner \_\_\_\_\_  
Smithburg, WV 26436  
Agent Ron Spencer Coal Operator \_\_\_\_\_  
Permit Issued Date 10/19/2023 or Owner \_\_\_\_\_

AFFIDAVIT

RECEIVED  
Office of Oil and Gas

JUN 23 2025

STATE OF WEST VIRGINIA,  
County of Harrison ss:

Terry Rexroad and Marshall Rexroad being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of June, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	3300	2700	2200' Of 3"	1112' of 3"
Cement	2300	1850	1500' of 5 1/2"	642' of 5 1/2 "
Cement	1550	1380	57' of 7"	1400' of 7"
Cement	1115	1015		
Cement	700	600	Perforated 7"	1115 to 1015, 700 to 600 and 250 to surface
Cement	250	Surface		
6% Gel	Between all Plugs			


Description of monument: 7" Casing with API # and date welded on and that the work of plugging and filling said well was completed on the 13th day of July, 2025.

And further deponents saith not.

Sworn and subscribe before me this 17th day of June, 2025

My commission expires: 7-6-30

Notary Public



Affidavit reviewed by the Office of Oil and Gas: [Signature]

Title: Inspector 6/18/2025  
06/27/2025