

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: September 23rd, 2013
API #: 47-033-00707P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: ZIRKLE, JOHN H. Operator Well No.: 8143 DTI Plugging

LOCATION: Elevation: 1105.55' Quadrangle: West Milford
District: Union County: Harrison
Latitude: 23,800 Feet South of: 39 Deg. 15 Min. 00 Sec.
Longitude: 14,150 Feet West of: 80 Deg. 25 Min. 00 Sec.

Well Type: OIL GAS X

Company: CNX Gas Company LLC Coal Operator or Owner See List on Page 2
P.O. Box 1248
Jane Lew, WV 26378

Agent: Matt Imrich

Permit Issued Date: 8/27/2013

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Lewis ss:

Richard C. Jones and Mike Frederick being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of November, 2013, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement Plug	3391'	2564'		
6% Gel	2564'	Surface		
Cut 3 1/2" CSG @ 2070'	2070'	Surface	2070'	1299'
Cement Plug	2070'	1882'		
6% Gel	1882'	1500'		
Cut 5 1/2" CSG @ 1540'	1540'	Surface	1540'	
Perfed 7" CSG			None: Perfed @ 1500', 1150', 1050', 700', 600', 200'	
Cement Plug	1500'	1400'		
Gel	1400'	1150'		
Cement Plug	1150'	1050'		
Gel	1050'	700'		
Cement Plug	700'	600'		
Gel	600'	200'		
Cement Plug	200'	0'		

RECEIVED
Office of Oil and Gas
SEP 24 2014
WV Department of
Environmental Protection

Description of monument: Installed 7" x 4' Monument with API # 47-033-00707.


and that the work of plugging and filling said well was completed on the 22nd day of November, 2013.

And further deponents saith not.

Sworn and subscribe before me this 24th day of July, 2014

My commission expires: Sept. 24, 2021

Richard C. Jones
Mike Frederick
Cindy L. Kovach
Notary Public



Affidavit reviewed by the Office of Oil and Gas

S. L. Dwan

Title: OOG Inspector