

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Sharon S. McDonald Operator Well No.: W-5117

LOCATION: Elevation: 1,120' Quadrangle: West Milford 7.5'
District: Union County: Harrison
Latitude: 2,150 Feet South of 39 Deg. 10 Min. 00 Sec.
Longitude: 11,080 Feet West of 80 Deg. 25 Min. 00 Sec.

Well Type: OIL _____ GAS X

Company Dominion Transmission Inc. Coal Operator Sharon S. McDonald
445 West Main Street or Owner P.O. Box 204
Clarksburg, WV 26301 Lost Creek, WV 26385
Agent James Blasingame Coal Operator _____
Permit Issued Date 10/18/13 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Harrison ss:

James Blasingame and _____ being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of December, 2013 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
PLEASE SEE ATTACHED				
				JAN 21 2014

Received

Office of Oil and Gas
WV Dept. of Environmental Protection

Description of monument: Dominion Transmission, Inc. 12/6/13 API #47-033-00126 and that the work of plugging and filling said well was completed on the 6th day of December, 2013.


And further deponents saith not.

James D. Blasingame 1/2/14

Sworn and subscribe before me this 2nd day of January, 2014

My commission expires: 3-31-20

Brenda M. Johnson
Notary Public



Affidavit reviewed by the Office of Oil and Gas: S. P. O'Connell Title: Oil Gas 01/31/2014

33.00126P

WR-38 for API #47-033-00126
Attachment
Dominion Transmission, Inc. Well No. W-5117

Set solid plug cement Class A from 2,220' to surface

- Shot holes at Gantz 1,690' – 1,700' – 20 holes
- Shot holes at bottom 5" 1,830' – 1,840' – 20 holes
- Shot holes at Injun 1,400' – 1,410' – 20 holes
- Shot holes at bottom 7" 1,380' – 1,390' – 20 holes
- Shot holes at elevation 1,120' – 1,130' – 20 holes
- Shot holes at bottom 8 5/8" 865' – 875' – 20 holes
- Shot holes at Coal 350' – 360' – 20 holes
- Shot holes at bottom 10" 140' – 150' – 20 holes

Plugged with 280 sacks Class A cement

62 Bbl mixed at 15.6 PPG

Set 4 1/2" x 4" monument on top of well

2,264' of 3 1/2" tubing was retrieved, no other casing would come out of hole

Received

JAN 21 2014

Office of Oil and Gas
WV Dept. of Environmental Protection

RECEIVED
Office of Oil and Gas

JAN 10 2014

WV Department of
Environmental Protection

01/31/2014