

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Downs, Thomas H. & Rebecca Operator Well No.: WV 604237 (Martin 4237)

LOCATION: Elevation: 1004' Quadrangle: Wolf Summit  
District: Sardis County: Harrison  
Latitude: \_\_\_\_\_ Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
Longitude: \_\_\_\_\_ Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company EQT Production Company Coal Operator Linda Martin Walden Agent  
1710 Pennsylvania Avenue or Owner 212B Carl Noah Rd  
Charleston, WV 25302 Snow Camp, NC 27349

Agent Rex C. Ray Coal Operator \_\_\_\_\_  
Permit Issued Date 7-16-2012 or Owner \_\_\_\_\_

**RECEIVED**  
**Office of Oil & Gas**

AUG 28 2013

STATE OF WEST VIRGINIA, KY  
County of Floyd ss:

AFFIDAVIT

WV Department of  
Environmental Protection

Charles Moore and Rodney Osborne being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of May, 2013, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
6% gel	2770'	Surface	10' of 6 5/8"	16' of 13"
C1A Cement	1840'	1685'	1840' of 3"	153' of 10"
C1A Cement	1431'	1301'		1387' of 6 5/8"
C1A Cement	882'	520'		456' of 3"
C1A Cement	215'	Surface		
				Perforated 10 holes each @ 846' and 814
				5 holes each @ 745', 695', 640', 590', 540', 200', 150', 100'


Description of monument: Metal Plate w/ EQT, API, Well #, and date welded on 4" tubing 36" above ground and that the work of plugging and filling said well was completed on the 22nd day of May, 2013.

And further deponents saith not. Charles Moore  
Rodney Osborne

Sworn and subscribe before me this 28th day of May, 2013

My commission expires: 9-26-14

Michelle Handshoe  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: S. J. DeWanna Title: Chief Gas Inspector

08/30/2013