

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Lease or Property Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
SHINNISTON 7.6'  
Well Location  
EAGLE  
District  
HARRISON  
County  
K-3 ROBINSON 1  
Well No.  
CONSOLIDATED COAL CO.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING

*[Signature]* 5-5-14

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8<sup>th</sup> day of November, 2013 and that the well was plugged in the following manner:

| Sand or Zone Record  | Filling Material               | Casing/Tubing Size   | Casing Pulled    | Casing Left In |
|--|--------------------------------|--|------------------|----------------|
| <b>Formation</b>   |                                |  |                  |                |
| Cleaned 3 1/2" hole inside 4 1/2" casing from the surface to 3487'. Tagged solid plug at 3487'. Perforated 4 1/2" casing at the following depths: 3350', 3250', 3150', 3050', 2950', 2850', 2759', 2650', 2550', 2450', 2350', 2250', 2150' and 2050'. Cement bottom hole from 3487' to 2415' with 70 sacks of Superlite Cement. Tag to of bottom hole plug at 2415'. Remove 1948' to 4 1/2" casing from the surface to 1948'. Left an unknown amount of 4 1/2" casing in the hole from 1948' to unknown depth. Cleaned 7 7/8" hole inside of 8 5/8" casing from the surface to 1948'. Tagged top of 4 1/2" casing at 1948'. Cleaned 7 7/8" hole inside of 8 5/8" casing through the Pittsburgh Coal seam from 206' to 212'. Left 1253' of 8 5/8" casing in the hole from the surface to 1253'. Cut remaining 8 5/8" casing at the following depth: 1156', 1040', 949', 848', 732', 628', 525', 420', 320', 230' and 130'. | 8 5/8" Casing<br>4 1/2" Casing | 0'<br>1948'  | 1253'<br>Unknown |                |
| <b>Cemented hole from top of bottom hole plug at 2415' back to surface as follows:</b>   |                                |  |                  |                |
| Left fresh water gel spacer from 2415' to 1353'. From 1353' to 1243' with 35 sacks of Thixotropic Cement with Dye. Left fresh water gel spacer from 1243' to 316'. From 316' to Surface with 84 sacks of Thixotropic Cement with Dye. A total of 189 sacks of cement were used to fill the hole from 3487' back to surface. Cement did circulate at the surface.   |                                |  |                  |                |
| <b>Coal Seams</b>  |                                | <b>Description of Monument</b>   |                  |                |
| <u>Pittsburgh</u>  | (206' - 212')                  | 77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |                  |                |

RECEIVED  
Office of Oil & Gas  
MAY 06 2014  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 21<sup>st</sup> day of November, 2013.

And further deponents saith not.


*[Signature]*  
Russell Smallwood  
*[Signature]*  
Kevin S. Wright

Sworn to and subscribed before me this 1st day of April 2014

*[Signature]*  
Notary Public

My commission expires: 11/4/23

Permit No. 47-033-003752-P  
Well No. K-3 ROBINSON 1



05/09/2014