

**State of West Virginia
Division of Environmental Protection
Section of Oil and Gas
Well Operator's Report of Well Work**

Farm name: HERROD, DON M. & DEBRA L. Operator Well No.: H. FLANAGAN 6
 LOCATION: Elevation: 1,325' Quadrangle: WOLF SUMMIT 7.5'
 District: TEN MILE County: HARRISON
 Latitude: 8,490 Feet south of 39 Deg 20 Min 0 Sec.
 Longitude: 2,360 Feet west of 80 Deg 27 Min 30 Sec.

RECEIVED
OCT 19 2012
WV DEP - OIL & GAS DIVISION


| | | | | | |
|-------------------------------------|--|-----------------|------------------|--------------|------------------------|
| Company Address: | HG Energy PO Box 5519 Vienna, WV 26105 | Casing & Tubing | Used in Drilling | Left in Well | Cement Fill Up Cu. Ft. |
| Inspector: | Tristan Jenkins | | | | |
| Date Permit Issued: | 06/19/2012 | | | | |
| Date Well Work Commenced: | 09/04/2012 | | | | |
| Date Well Work Completed: | 09/12/2012 | | | | |
| Verbal Plugging: | | | | | |
| Date Permission Granted On: | | | | | |
| Rotary X Cable Rig | | 8 5/8" | 659' | 659' | 210 sks |
| Total vertical Depth (ft): | 3,018' | | | | |
| Total Measured Depth (ft): | | 4 1/2" | 2962' | 2962' | 385 sks |
| Fresh Water Depth (ft): | none | | | | |
| Salt Water Depth (ft): | none | | | | |
| Is Coal being mined in ares (Y/N)? | No | | | | |
| Coal Depths (ft): x | 552'-560' | | | | |
| Void(s) encountered (Y/N) depth(s): | NONE | | | | |

OPEN FLOW DATA * Waterflood Injector

Producing formation Fifth Sand Pay zone depth (ft) 2912'-2914'
2922'-2924'
 Gas: Initial open flow * MCF/d Oil: Initial open flow * Bbl/d
 Final open flow * MCF/d Final open flow * Bbl/d
 Time of open flow between initial and final tests * Hours
 Static rock pressure * psig (surface pressure) after * Hours

Second producing formation Pay zone depth (ft) _____
 Gas: Initial open flow _____ MCF/d Oil: Initial open flow _____ Bbl/d
 Final open flow _____ MCF/d Final open flow _____ Bbl/d
 Time of open flow between initial and final tests _____ Hours
 Static rock pressure _____ psig (surface pressure) after _____ Hours

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this document and all the attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information I believe that the information is true, accurate, and complete.



 Signature

10/2/12

 Date

Were core samples taken? No

Were cuttings caught during drilling? No

Were Y Electrical, N Mechanical, N or Geophysical logs recorded on this well?
Y/N Y/N Y/N

NOTE: IN THE AREA BELOW PUT THE FOLLOWING: 1). DETAILS OF PERFORATED INTERVALS, FRACTURING OR STIMULATING, PHYSICAL CHANGE, ETC. 2). THE WELL LOG WHICH IS A SYSTEMATIC DETAILED GEOLOGICAL RECORD OF THE TOPS AND BOTTOMS OF ALL FORMATIONS, INCLUDING COAL ENCOUNTERED BY THE WELLBORE FROM SURFACE TO TOTAL DEPTH.

Treatment : Treated perfs 2912'-2914', 2918'-2920', 2922'-2924' w/ 1000 gals 15% HCL acid, 291 bbls cross linked gel, and 20,000# 20/40 sand.

Well Log : See original WR35